



# **Project Costs Breakdown**

Outline Business Case - Appendix O

17 January 2020

Mott MacDonald  
22 Station Road  
Cambridge CB1 2JD  
United Kingdom

T +44 (0)1223 463500  
mottmac.com

# **Project Costs Breakdown**

Outline Business Case - Appendix O

17 January 2020

**Document reference:** | | 392438-MMD-BCA-XX-RP-BC-0045

**Information class: Standard**

---

This document is issued for the party which commissioned it and for specific purposes connected with the above-captioned project only. It should not be relied upon by any other party or used for any other purpose.

We accept no responsibility for the consequences of this document being relied upon by any other party, or being used for any other purpose, or containing any error or omission which is due to an error or omission in data supplied to us by other parties.

This document contains confidential information and proprietary intellectual property. It should not be shown to other parties without consent from us and from the party which commissioned it.

---

# Contents

|    |                            |    |
|----|----------------------------|----|
| 1  | Assumptions and Exclusions | 1  |
| 2  | Drawing                    | 4  |
| 3  | Construction Summary       | 5  |
| 4  | Whole Life Costs Summary   | 6  |
| 5  | Phase 1                    | 7  |
| 6  | Option 1                   | 13 |
| 7  | Option 2                   | 19 |
| 8  | Option 3                   | 24 |
| 9  | Waterworks P&R             | 29 |
| 10 | Scotland Farm P&R          | 34 |
| 11 | WLC Maintenance Costs      | 39 |
| 12 | Phase 1 WLC                | 40 |
| 13 | Option 1 WLC               | 43 |
| 14 | Option 2 WLC               | 46 |
| 15 | Option 3 WLC               | 49 |
| 16 | Waterworks P&R WLC         | 52 |
| 17 | Scotland Farm P&R WLC      | 55 |

# 1 Assumptions and Exclusions

## **Cambridge to Cambourne**

### **General Assumptions**

- 1 Estimate is based at 4Q18
- 2 Risk and contingency is applied based on a Phase 3 estimate, Option Selection, as per agreed procedure
- 3 Works expected to be carried out in normal working hours 08:00 to 18:00, Monday to Friday
- 4 Uplifts have been applied to the estimate to cover any night time or out of hours working that may be required on
- 5 Works can be carried out under half road closure wherever possible
- 6 Allowances have been included where we have not received sufficient information to allow us to price the works confidently. These have been clearly identified in the estimate and will require validation when further information becomes available
- 7 Existing ground level approximately same as finished construction levels
- 8 All signage to be unlit
- 9 All excavated material is assumed as inert
- 10 Land deemed relatively flat
- 11 No hard digging required for any element of the scheme
- 12 Topsoil can be reused - no imported topsoil needed
- 13 Where possible budget quotations have been used from specialist subcontractors
- 14 2.5% of the total Direct Construction Costs have been used for environmental mitigation measures
- 15 1000m length of new road is allowed for in Option 1-3 to connect the road from Bourn Airfield to Wellington Way Roundabout
- 16 Rate book dated 8th April 2019 applied
- 17 See estimates and rates sheet for further assumptions and details of scope
- 18 All lighting columns assumed to be 8m high in absence of specific design information

### **Specific Option Assumptions**

#### **Phase 1**

- 19 Length of Guided Busway; 4760m
- 20 Length of Maintenance track/ Footway/ Cycleway; 4749m
- 21 Allowed for unbound subbase only below the guided busway - specific construction details not known
- 22 Allowance made for 4 nr of bus stops
- 23 Concrete batching plant site compound allowed for within the prelims allowance
- 24 Out of hours allowance included
- 25 Drainage surveys included in the design percentage
- 26 Bridges are assumed to not be painted eg Corten weathering steel or concrete finish
- 27 Resurfacing is needed on M11 road ridge.
- 28 Allowance made for demolishing existing bridge at Bin Brook Crossing and building a new one.

#### **Phase 2 Option 1**

- 29 Length of Guided Busway; 5694m
- 30 Allowance made for 4 nr of bus stops
- 31 Concrete batching plant site compound allowed for within the prelims allowance
- 32 Out of hours allowance included

#### **Phase 2 Option 2**

- 33 Length of Guided Busway; 2078m
- 34 Allowance made for 4 nr of bus stops
- 35 Concrete batching plant site compound allowed for within the prelims allowance
- 36 Out of hours allowance included

#### **Phase 2 Option 3**

- 37 Length of Guided Busway; 2078m
- 38 Length of Bus Lane; 6159m
- 39 Allowance made for 4 nr of bus stops
- 40 Concrete batching plant site compound allowed for within the prelims allowance
- 41 Out of hours allowance included

## **Cambridge to Cambourne**

### **Water Works Park and Ride**

- 42 Bare rooted native species whips as environmental barrier
- 43 Allowance made for 1nr attenuation pond

### **Scotland Farm Park and Ride**

- 44 Bare rooted native species whips as environmental barrier
- 45 Allowance made for 1nr attenuation pond and 1nr naturalised pond

### **General Exclusions**

- 46 Bus Depot
- 47 Fuel resistant asphalt
- 48 Telecommunication works for NRTS including any ducting for the dual carriageways
- 49 Optimism Bias
- 50 VAT
- 51 3rd party compensation costs
- 52 Planning and approval charges
- 53 Land purchase or rental
- 54 Costs associated with Statutory Fees (e.g. HMRI, Local Authority, etc.)
- 55 Costs associated with taxes, levies and licences
- 56 Costs associated with changes in legislation and any form of applicable standards
- 57 Allowances for unforeseen ground conditions / provisions for ground stabilisation unless specifically identified
- 58 Christmas, Easter and Bank Holiday working
- 59 Archaeological digs
- 60 Works that have not been specifically included for in the estimate
- 61 Re-location of affected businesses
- 62 Given the level of detail provided, it is not possible to quantify the extent of utilities to be relocated, protected or diverted. Costs for diversions can be extremely volatile and as such are very difficult to derive, and as such have been excluded from these estimates

### **Specific Option Exclusions**

#### **Phase 1 & Phase 2**

- 63 Telecomms work
- 64 Procurement of new buses excluded
- 65 New depot excluded

#### **Water Works Park and Ride**

- 66 Out of hours working is excluded

#### **Scotland Farm Park and Ride**

- 67 Out of hours working is excluded

### **Clarification of cost structure for each Option**

#### **Option 1a - Includes**

- 68 Phase 1 Madingley Mulch Roundabout to Grange Road
- 69 Phase 2 Cambourne to Bourn Roundabout
- 70 Phase 2 Bourn Roundabout to Madingley Mulch Roundabout (Full Off Road)

71 Waterworks Park and Ride

## **Cambridge to Cambourne**

### **Option 1b - Includes**

- 72 Phase 1 Madingley Mulch Roundabout to Grange Road
- 73 Phase 2 Cambourne to Bourn Roundabout
- 74 Phase 2 Bourn Roundabout to Madingley Mulch Roundabout (Full Off Road)
- 75 Scotland Farm Park and Ride

### **Option 2a - Includes**

- 76 Phase 1 Madingley Mulch Roundabout to Grange Road
- 77 Phase 2 Cambourne to Bourn Roundabout
- 78 Phase 2 Bourn Roundabout to Madingley Mulch Roundabout (Do Minimum On Road)
- 79 Waterworks Park and Ride

### **Option 2b - Includes**

- 80 Phase 1 Madingley Mulch Roundabout to Grange Road
- 81 Phase 2 Cambourne to Bourn Roundabout
- 82 Phase 2 Bourn Roundabout to Madingley Mulch Roundabout (Do Minimum On Road)
- 83 Scotland Farm Park and Ride

### **Option 3a - Includes**

- 84 Phase 1 Madingley Mulch Roundabout to Grange Road
- 85 Phase 2 Cambourne to Bourn Roundabout
- 86 Phase 2 Bourn Roundabout to Madingley Mulch Roundabout (Do Minimum with Bus Lanes)
- 87 Waterworks Park and Ride

### **Option 3b - Includes**

- 88 Phase 1 Madingley Mulch Roundabout to Grange Road
- 89 Phase 2 Cambourne to Bourn Roundabout
- 90 Phase 2 Bourn Roundabout to Madingley Mulch Roundabout (Do Minimum with Bus Lanes)
- 91 Scotland Farm Park and Ride

### **Whole Life Cost Estimate**

- 92 Capital costs for removing infrastructure have been omitted on the assumption that the infrastructure will remain in fit and proper condition
- 93 Costs evaluated over a 60 year period
- 94 The Discounted rate used of 3.5% is based on information obtained from HM Treasury's Green Book where the life
- 95 P80 costs referenced for WLC estimates
- 96 WLC estimate does not include for bus way renewals

## 2 Drawing

## DRAWINGS REGISTER

| <i>Ref:</i>              | <i>Title</i>                                                    | <i>Revision</i> |
|--------------------------|-----------------------------------------------------------------|-----------------|
| 5164295-ATK-ZZ-ZZ-DR-L-9 | SCOTLAND FARM PARK AND RIDE LANDSCAPE PLAN                      | N/A             |
| 5020059_HW_FS_301        | Waterworks Alternative Park and Ride Layout                     | A               |
| 5020059_HW_FS_130        | Do something 1B Off Road Phase 1 + Scotland Farm Sheet 1 of 5   | C               |
| 5020059_HW_FS_131        | Do something 1B Off Road Phase 1 + Scotland Farm Sheet 2 of 5   | C               |
| 5020059_HW_FS_132        | Do something 1B Off Road Phase 1 + Scotland Farm Sheet 3 of 5   | C               |
| 5020059_HW_FS_133        | Do something 1B Off Road Phase 1 + Scotland Farm Sheet 4 of 5   | C               |
| 5020059_HW_FS_134        | Do something 1B Off Road Phase 1 + Scotland Farm Sheet 5 of 5   | C               |
| 5020059_HW_FS_140        | Do something 1A Off Road Phase 1 + WaterWorks Sheet 1 of 5      | C               |
| 5020059_HW_FS_141        | Do something 1A Off Road Phase 1 + WaterWorks Sheet 2 of 5      | C               |
| 5020059_HW_FS_142        | Do something 1A Off Road Phase 1 + WaterWorks Sheet 3 of 5      | C               |
| 5020059_HW_FS_143        | Do something 1A Off Road Phase 1 + WaterWorks Sheet 4 of 5      | C               |
| 5020059_HW_FS_144        | Do something 1A Off Road Phase 1 + WaterWorks Sheet 5 of 5      | C               |
| 5020059_HW_FS_150        | Do something 2B Off Road Phase 1 + Scotland Farm Sheet 1 of 7   | C               |
| 5020059_HW_FS_151        | Do something 2B Off Road Phase 1 + Scotland Farm Sheet 2 of 7   | C               |
| 5020059_HW_FS_152        | Do something 2B Off Road Phase 1 + Scotland Farm Sheet 3 of 7   | C               |
| 5020059_HW_FS_153        | Do something 2B Off Road Phase 1 + Scotland Farm Sheet 4 of 7   | C               |
| 5020059_HW_FS_154        | Do something 2B Off Road Phase 1 + Scotland Farm Sheet 5 of 7   | C               |
| 5020059_HW_FS_155        | Do something 2B Off Road Phase 1 + Scotland Farm Sheet 6 of 7   | C               |
| 5020059_HW_FS_156        | Do something 2B Off Road Phase 1 + Scotland Farm Sheet 7 of 7   | C               |
| 5020059_HW_FS_160        | Do something 2A Off Road Phase 1 + WaterWorks Sheet 1 of 7      | C               |
| 5020059_HW_FS_161        | Do something 2A Off Road Phase 1 + WaterWorks Sheet 2 of 7      | C               |
| 5020059_HW_FS_162        | Do something 2A Off Road Phase 1 + WaterWorks Sheet 3 of 7      | C               |
| 5020059_HW_FS_163        | Do something 2A Off Road Phase 1 + WaterWorks Sheet 4 of 7      | C               |
| 5020059_HW_FS_164        | Do something 2A Off Road Phase 1 + WaterWorks Sheet 5 of 7      | C               |
| 5020059_HW_FS_165        | Do something 2A Off Road Phase 1 + WaterWorks Sheet 6 of 7      | C               |
| 5020059_HW_FS_169        | Do something 2A Off Road Phase 1 + WaterWorks Sheet 7 of 7      | C               |
| 5020059_HW_FS_220        | Phase 2 Option 1 Do Something Full Off Road Option Sheet 1 of 3 | A               |
| 5020059_HW_FS_221        | Phase 2 Option 1 Do Something Full Off Road Option Sheet 2 of 3 | A               |
| 5020059_HW_FS_222        | Phase 2 Option 1 Do Something Full Off Road Option Sheet 3 of 3 | A               |
| 5020059_HW_FS_223        | Phase 2 Option 2 Do Something Full Off Road Option Sheet 1 of 3 | A               |
| 5020059_HW_FS_224        | Phase 2 Option 2 Do Something Full Off Road Option Sheet 2 of 3 | A               |
| 5020059_HW_FS_225        | Phase 2 Option 2 Do Something Full Off Road Option Sheet 3 of 3 | A               |
| 5020059_HW_FS_226        | Phase 2 Option 3 Do Something Full Off Road Option Sheet 1 of 3 | A               |
| 5020059_HW_FS_227        | Phase 2 Option 3 Do Something Full Off Road Option Sheet 2 of 3 | A               |
| 5020059_HW_FS_228        | Phase 2 Option 3 Do Something Full Off Road Option Sheet 3 of 3 | A               |
| 5020059_HW_FS_231        | Phase 2 Option 4 Do Something Full Off Road Option Sheet 1 of 3 | A               |
| 5020059_HW_FS_232        | Phase 2 Option 4 Do Something Full Off Road Option Sheet 2 of 3 | A               |
| 5020059_HW_FS_233        | Phase 2 Option 4 Do Something Full Off Road Option Sheet 3 of 3 | A               |
| 5020059_HW_FS_290        | Phase 2 Option 5 Do Something Full Off Road Option Sheet 1 of 3 | A               |
| 5020059_HW_FS_291        | Phase 2 Option 5 Do Something Full Off Road Option Sheet 2 of 3 | A               |
| 5020059_HW_FS_292        | Phase 2 Option 5 Do Something Full Off Road Option Sheet 3 of 3 | A               |

### 3 Construction Summary

| WBS      | Cambridge to Cambourne                                                           | Option 1a            | Option 1b            | Option 2a            | Option 2b            | Option 3a            | Option 3b            |
|----------|----------------------------------------------------------------------------------|----------------------|----------------------|----------------------|----------------------|----------------------|----------------------|
| <b>1</b> | <b>DIRECT CONSTRUCTION COSTS</b>                                                 | <b>£ 52,736,385</b>  | <b>£ 54,946,290</b>  | <b>£ 44,505,783</b>  | <b>£ 46,715,688</b>  | <b>£ 50,939,181</b>  | <b>£ 53,149,087</b>  |
| 1.02     | SERIES 200: SITE CLEARANCE                                                       | £ 692,634            | £ 739,641            | £ 619,257            | £ 666,264            | £ 815,094            | £ 862,101            |
| 1.03     | SERIES 300: FENCING                                                              | £ 110,053            | £ 112,942            | £ 110,053            | £ 112,942            | £ 110,053            | £ 112,942            |
| 1.04     | SERIES 400: ROAD RESTRAINT SYSTEMS (VEHICLE AND PEDESTRIAN)                      | £ -                  | £ -                  | £ -                  | £ -                  | £ -                  | £ -                  |
| 1.05     | SERIES 500: DRAINAGE AND SERVICE DUCTS                                           | £ 6,840,091          | £ 6,934,656          | £ 5,494,488          | £ 5,589,053          | £ 6,586,794          | £ 6,681,359          |
| 1.06     | SERIES 600: EARTHWORKS                                                           | £ 6,135,782          | £ 6,575,500          | £ 5,196,599          | £ 5,636,316          | £ 6,155,102          | £ 6,594,820          |
| 1.07     | SERIES 700: PAVEMENTS                                                            | £ 6,880,918          | £ 7,310,638          | £ 6,663,761          | £ 7,093,481          | £ 8,726,943          | £ 9,156,663          |
| 1.11     | SERIES 1100: KERBS, FOOTWAYS AND PAVED AREAS                                     | £ 14,968,683         | £ 14,867,506         | £ 10,456,923         | £ 10,355,747         | £ 10,584,247         | £ 10,483,071         |
| 1.12     | SERIES 1200: TRAFFIC SIGNS AND ROAD MARKINGS                                     | £ 282,020            | £ 282,020            | £ 220,764            | £ 220,764            | £ 250,428            | £ 250,428            |
| 1.13     | SERIES 1300: ROAD LIGHTING COLUMNS AND BRACKETS, CCTV MASTS AND CANTILEVER MASTS | £ 1,680,124          | £ 1,682,017          | £ 1,367,625          | £ 1,369,518          | £ 1,889,014          | £ 1,890,907          |
| 1.14     | SERIES 1400: ELECTRICAL WORK FOR ROAD LIGHTING AND TRAFFIC SIGNS                 | £ 3,100,910          | £ 3,059,562          | £ 2,541,957          | £ 2,500,609          | £ 3,408,014          | £ 3,366,666          |
| 1.15     | SERIES 1500: MOTORWAY COMMUNICATION                                              | £ -                  | £ -                  | £ -                  | £ -                  | £ -                  | £ -                  |
| 1.16     | SERIES 1600: PILING AND EMBEDDED RETAINING WALLS                                 | £ -                  | £ -                  | £ -                  | £ -                  | £ -                  | £ -                  |
| 1.17     | SERIES 1700: STRUCTURAL CONCRETE                                                 | £ -                  | £ -                  | £ -                  | £ -                  | £ -                  | £ -                  |
| 1.18     | SERIES 1800: STEELWORK FOR STRUCTURES                                            | £ -                  | £ -                  | £ -                  | £ -                  | £ -                  | £ -                  |
| 1.19     | SERIES 1900: PROTECTION OF STEELWORK AGAINST CORROSION                           | £ -                  | £ -                  | £ -                  | £ -                  | £ -                  | £ -                  |
| 1.20     | SERIES 2000: WATERPROOFING FOR STRUCTURES                                        | £ -                  | £ -                  | £ -                  | £ -                  | £ -                  | £ -                  |
| 1.21     | SERIES 2100: BRIDGE BEARINGS                                                     | £ -                  | £ -                  | £ -                  | £ -                  | £ -                  | £ -                  |
| 1.23     | SERIES 2300: BRIDGE EXPANSION JOINTS AND SEALING OF GAPS                         | £ -                  | £ -                  | £ -                  | £ -                  | £ -                  | £ -                  |
| 1.24     | SERIES 2400: BRICKWORK, BLOCKWORK AND STONEWORK                                  | £ -                  | £ -                  | £ -                  | £ -                  | £ -                  | £ -                  |
| 1.25     | SERIES 2500: SPECIAL STRUCTURES                                                  | £ 8,892,016          | £ 9,109,026          | £ 8,892,016          | £ 9,109,026          | £ 8,892,016          | £ 9,109,026          |
| 1.27     | SERIES 2700: ACCOMMODATION WORKS                                                 | £ -                  | £ -                  | £ -                  | £ -                  | £ -                  | £ -                  |
| 1.30     | SERIES 3000: LANDSCAPING AND ECOLOGY                                             | £ 3,153,154          | £ 4,272,781          | £ 2,942,340          | £ 4,061,968          | £ 3,521,477          | £ 4,641,104          |
| 1.50     | SERIES 5000: MAINTENANCE PAINTING OF STEELWORK                                   | £ -                  | £ -                  | £ -                  | £ -                  | £ -                  | £ -                  |
| <b>2</b> | <b>INDIRECT CONSTRUCTION COSTS</b>                                               | <b>£ 25,459,105</b>  | <b>£ 26,315,444</b>  | <b>£ 21,356,150</b>  | <b>£ 22,212,488</b>  | <b>£ 24,563,199</b>  | <b>£ 25,419,538</b>  |
| 2.01     | CONTRACTORS PRELIMINARIES                                                        | £ 10,547,277         | £ 10,989,258         | £ 8,901,157          | £ 9,343,138          | £ 10,187,836         | £ 10,629,817         |
| 2.01a    | CONTRACTORS PRELIMINARIES: TRAFFIC MANAGEMENT                                    | £ 2,636,819          | £ 2,747,315          | £ 2,225,289          | £ 2,335,784          | £ 2,546,959          | £ 2,657,454          |
| 2.01b    | CONTRACTORS PRELIMINARIES: UPLIFT FOR OUT OF HOURS WORKING                       | £ 4,525,906          | £ 4,525,906          | £ 3,702,846          | £ 3,702,846          | £ 4,346,186          | £ 4,346,186          |
| 2.02     | CONTRACTORS OVERHEAD AND PROFIT                                                  | £ 7,749,103          | £ 8,052,965          | £ 6,526,858          | £ 6,830,720          | £ 7,482,218          | £ 7,786,080          |
|          | <b>BASE COST ESTIMATE (DIRECT COSTS + INDIRECT COSTS)</b>                        | <b>£ 78,195,490</b>  | <b>£ 81,261,734</b>  | <b>£ 65,861,933</b>  | <b>£ 68,928,177</b>  | <b>£ 75,502,380</b>  | <b>£ 78,568,624</b>  |
| <b>3</b> | <b>DESIGN COSTS</b>                                                              | <b>£ 12,511,278</b>  | <b>£ 13,001,877</b>  | <b>£ 10,537,909</b>  | <b>£ 11,028,508</b>  | <b>£ 12,080,381</b>  | <b>£ 12,570,980</b>  |
| 3.01     | Stated Project Phase Design Fees, inc Testing and Commissioning                  | £ 12,511,278         | £ 13,001,877         | £ 10,537,909         | £ 11,028,508         | £ 12,080,381         | £ 12,570,980         |
| 3.02     |                                                                                  |                      |                      |                      |                      |                      |                      |
| <b>4</b> | <b>PROJECT MANAGEMENT COSTS</b>                                                  | <b>£ 9,202,518</b>   | <b>£ 9,563,727</b>   | <b>£ 7,751,249</b>   | <b>£ 8,112,458</b>   | <b>£ 8,885,624</b>   | <b>£ 9,246,833</b>   |
| 4.01     | Client Project Organisation                                                      | £ 9,202,518          | £ 9,563,727          | £ 7,751,249          | £ 8,112,458          | £ 8,885,624          | £ 9,246,833          |
| <b>5</b> | <b>OTHER PROJECT COSTS</b>                                                       | <b>£ 1,318,410</b>   | <b>£ 1,373,657</b>   | <b>£ 1,112,645</b>   | <b>£ 1,167,892</b>   | <b>£ 1,273,480</b>   | <b>£ 1,328,727</b>   |
| 5.01     | Environmental Mitigations (2.5% of Base Cost Estimate)                           | £ 1,318,410          | £ 1,373,657          | £ 1,112,645          | £ 1,167,892          | £ 1,273,480          | £ 1,328,727          |
| <b>6</b> | <b>INFLATION</b>                                                                 | <b>£ 1,518,415</b>   | <b>£ 1,578,015</b>   | <b>£ 1,278,956</b>   | <b>£ 1,338,556</b>   | <b>£ 1,466,128</b>   | <b>£ 1,525,727</b>   |
| 6.01     | Base date 4Q18 ; 3% annual inflation applied to 2Q2019                           | £ 1,518,415          | £ 1,578,015          | £ 1,278,956          | £ 1,338,556          | £ 1,466,128          | £ 1,525,727          |
| <b>7</b> | <b>TAXATION</b>                                                                  | <b>£ -</b>           | <b>£ -</b>           | <b>£ -</b>           | <b>£ -</b>           | <b>£ -</b>           | <b>£ -</b>           |
| 7.01     | Stated Taxes                                                                     | £ -                  | £ -                  | £ -                  | £ -                  | £ -                  | £ -                  |
|          | <b>PROJECT COST ESTIMATE</b>                                                     | <b>£ 102,746,111</b> | <b>£ 106,779,010</b> | <b>£ 86,542,691</b>  | <b>£ 90,575,590</b>  | <b>£ 99,207,993</b>  | <b>£ 103,240,892</b> |
| <b>8</b> | <b>RISK &amp; CONTINGENCY COSTS</b>                                              |                      |                      |                      |                      |                      |                      |
| 8.01     | P50 Contingency                                                                  | £ 19,521,761         | £ 20,288,012         | £ 16,443,111         | £ 17,209,362         | £ 18,849,519         | £ 19,615,769         |
| 8.02     | P80 Contingency                                                                  | £ 25,686,528         | £ 26,694,753         | £ 21,635,673         | £ 22,643,898         | £ 24,801,998         | £ 25,810,223         |
| 8.03     | P90 Contingency                                                                  | £ 29,796,372         | £ 30,965,913         | £ 25,097,380         | £ 26,266,921         | £ 28,770,318         | £ 29,939,859         |
| 8.04     | Optimism Bias                                                                    | £ -                  | £ -                  | £ -                  | £ -                  | £ -                  | £ -                  |
|          | <b>ANTICIPATED FINAL COST (P50)</b>                                              | <b>£ 122,267,872</b> | <b>£ 127,067,022</b> | <b>£ 102,985,802</b> | <b>£ 107,784,952</b> | <b>£ 118,057,511</b> | <b>£ 122,856,662</b> |
|          | <b>ANTICIPATED FINAL COST (P80)</b>                                              | <b>£ 128,432,639</b> | <b>£ 133,473,763</b> | <b>£ 108,178,364</b> | <b>£ 113,219,488</b> | <b>£ 124,009,991</b> | <b>£ 129,051,115</b> |
|          | <b>ANTICIPATED FINAL COST (P90)</b>                                              | <b>£ 132,542,483</b> | <b>£ 137,744,923</b> | <b>£ 111,640,071</b> | <b>£ 116,842,511</b> | <b>£ 127,978,311</b> | <b>£ 133,180,751</b> |

## 4 Whole Life Costs Summary

[illegible]

## 5 Phase 1

## Cambridge to Cambourne

## Phase 1

| Item                                                                                                                                                                                    | Qty    | Unit | Unit rate<br>£ | Total<br>£ | Subtotal<br>£    |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------|----------------|------------|------------------|
| <b>INITIAL CONSTRUCTION</b>                                                                                                                                                             |        |      |                |            |                  |
| <b>SERIES 200: SITE CLEARANCE</b>                                                                                                                                                       |        |      |                |            | <b>350,642</b>   |
| General Site Clearance                                                                                                                                                                  | 76,177 | m²   | 2.16           | 164,542    |                  |
| Take up PCC Kerb and dispose of off site                                                                                                                                                | 581    | m    | 9.42           | 5,470      |                  |
| Take up and remove from site; 8m mounting height tubular galvanised steel column complete with a post top mounted luminaire                                                             | 30     | nr   | 270.99         | 8,130      |                  |
| <b>Bridge over Bin Brook Crossing</b>                                                                                                                                                   |        |      |                |            |                  |
| Demolition of existing bridge over Bin Brook Crossing                                                                                                                                   | 345    | m²   | 500.00         | 172,500    |                  |
| <b>SERIES 300: FENCING</b>                                                                                                                                                              |        |      |                |            | <b>81,668</b>    |
| Anti Dazzle Fencing (Charles Babbage Road) assumed chain link fence                                                                                                                     | 501    | m    | 20.31          | 10,181     |                  |
| Supply and install Timber Post & Four Rail Fencing as per Highways Construction Detail Drawing H3. Timber treated to H4 BS8417. Posts incised for ground contact. Desired 30 year life. | 2,340  | m    | 30.55          | 71,487     |                  |
| <b>SERIES 500: DRAINAGE AND SERVICE DUCTS</b>                                                                                                                                           |        |      |                |            | <b>2,761,361</b> |
| <u>Busway</u>                                                                                                                                                                           |        |      |                |            |                  |
| Precast concrete trapped gully with Class D400 grating and frame; 450mm x 750mm                                                                                                         | 476    | nr   | 491.64         | 234,021    |                  |
| 150mm diameter carrier drain with type S bed and surround; depth to invert not exceeding 2m                                                                                             | 1,571  | m    | 47.72          | 74,964     |                  |
| 225mm diameter carrier drain with type S bed and surround; depth to invert 2m - 2.5m                                                                                                    | 10,473 | m    | 84.11          | 880,863    |                  |
| Connections to existing drainage/outfalls; 225mm dia; depth to invert exceeding 2m but not exceeding 4m                                                                                 | 10     | nr   | 277.32         | 2,773      |                  |
| Manhole; Depth : not exceeding 1.5 m; Type 2A (1.5m internal diameter) complete with allowance for concrete butt and rocker pipes                                                       | 112    | nr   | 3,084.61       | 345,501    |                  |
| Drainage interceptor - Allowance of 1 per 1000m of drainage                                                                                                                             | 10     | nr   | 10,000.00      | 100,000    |                  |
| Outfalls - Allowance of 1 per 1000m of drainage                                                                                                                                         | 10     | nr   | 10,000.00      | 100,000    |                  |
| <u>Maintenance track /Cycleway</u>                                                                                                                                                      |        |      |                |            |                  |
| 225mm diameter carrier drain with type S bed and surround; depth to invert 2m - 2.5m                                                                                                    | 4,749  | m    | 84.11          | 399,470    |                  |
| Connections to existing drainage/outfalls; 225mm dia; depth to invert exceeding 2m but not exceeding 4m                                                                                 | 10     | nr   | 277.32         | 2,773      |                  |
| Manhole; Depth : not exceeding 1.5 m; Type 2A (1.5m internal diameter) complete with allowance for concrete butt and rocker pipes                                                       | 56     | nr   | 3,084.61       | 172,738    |                  |
| <u>Dual Carriageway</u>                                                                                                                                                                 |        |      |                |            |                  |
| 225mm diameter carrier drain with type S bed and surround; depth to invert 2m - 2.5m                                                                                                    | 966    | m    | 84.11          | 81,238     |                  |
| Connections to existing drainage/outfalls; 225mm dia; depth to invert exceeding 2m but not exceeding 4m                                                                                 | 1      | nr   | 277.32         | 277        |                  |
| Precast concrete trapped gully with Class D400 grating and frame; 450mm x 750mm                                                                                                         | 49     | nr   | 491.64         | 24,090     |                  |
| Manhole; Depth : not exceeding 1.5 m; Type 2A (1.5m internal diameter) complete with allowance for concrete butt and rocker pipes                                                       | 12     | nr   | 3,084.61       | 37,015     |                  |
| Drainage interceptor - Allowance of 1 per 1000m of drainage                                                                                                                             | 1      | nr   | 10,000.00      | 10,000     |                  |
| Outfalls - Allowance of 1 per 1000m of drainage                                                                                                                                         | 1      | nr   | 10,000.00      | 10,000     |                  |
| Culverts - Allowance                                                                                                                                                                    | 1      | nr   | 25,000.00      | 25,000     |                  |
| Ditch (assumed 1.3m³ per m with erosion control matting anchored in U-shaped trench, 100mm thick topsoil and seeding)                                                                   | 3,239  | m    | 80.47          | 260,637    |                  |
| <b>SERIES 600: EARTHWORKS</b>                                                                                                                                                           |        |      |                |            | <b>2,033,434</b> |
| <u>Excavation of Topsoil</u>                                                                                                                                                            |        |      |                |            |                  |

|                                                                                                                                                                             |        |    |       |           |                  |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|----|-------|-----------|------------------|
| Excavation of acceptable material Class 5A Topsoil 150mm                                                                                                                    | 11,427 | m³ | 5.61  | 64,103    |                  |
| <u>General Excavation</u>                                                                                                                                                   |        |    |       |           |                  |
| Excavation to bus stop subformation; Excavation of acceptable material; excluding Class 5A; normal material, excluding hard or artificially hard material, <2500m³          | 342    | m³ | 2.54  | 869       |                  |
| Excavation to busway subformation; Excavation of acceptable material normal material, excluding hard or artificially hard material, excluding Class 5A; > 2500m³            | 27,798 | m³ | 1.49  | 41,420    |                  |
| Excavation to maintenance track subformation; Excavation of acceptable material normal material, excluding hard or artificially hard material, excluding Class 5A; > 2500m³ | 11,969 | m³ | 1.49  | 17,833    |                  |
| Excavation to carriageway subformation; Excavation of acceptable material normal material, excluding hard or artificially hard material, excluding Class 5A; > 2500m³       | 4,417  | m³ | 1.49  | 6,581     |                  |
| Excavation to footpath subformation; Excavation of acceptable material normal material, excluding hard or artificially hard material, excluding Class 5A; < 2500m³          | 1,069  | m³ | 2.54  | 2,715     |                  |
| Excavation to attenuation pond; Excavation of acceptable material normal material, excluding hard or artificially hard material, excluding Class 5A; > 2500m³               | 5,554  | m³ | 1.49  | 8,276     |                  |
| <u>Imported Fill</u>                                                                                                                                                        |        |    |       |           |                  |
| Imported acceptable material; Capping material; Class 6F2; for carriageway, 240mm thick                                                                                     | 1,738  | m³ | 40.64 | 70,626    |                  |
| <u>Compaction of Material</u>                                                                                                                                               |        |    |       |           |                  |
| Compaction of fill material to large areas                                                                                                                                  | 1,738  | m³ | 3.50  | 6,082     |                  |
| <u>Disposal of Material</u>                                                                                                                                                 |        |    |       |           |                  |
| Disposal of acceptable Class 5A topsoil                                                                                                                                     | 7,073  | m³ | 28.23 | 199,670   |                  |
| Disposal of acceptable material excluding Class 5A                                                                                                                          | 51,149 | m³ | 28.23 | 1,443,945 |                  |
| <u>Topsoiling and Storage of Topsoil</u>                                                                                                                                    |        |    |       |           |                  |
| Topsoiling; Class 5A material excavated from site; 150mm thick; Sloping at 10 eg or less to the horizontal, >5000m² (>750m³)                                                | 29,024 | m² | 1.10  | 31,926    |                  |
| <u>Completion of Formation and Sub-formation</u>                                                                                                                            |        |    |       |           |                  |
| Completion of sub-formation on acceptable material; bus stops                                                                                                               | 360    | m² | 1.10  | 396       |                  |
| Completion of sub-formation on acceptable material; bus way                                                                                                                 | 38,080 | m² | 1.10  | 41,888    |                  |
| Completion of sub-formation on acceptable material; maintenance track/cycleway                                                                                              | 18,998 | m² | 1.10  | 20,898    |                  |
| Completion of sub-formation on acceptable material; carriageway                                                                                                             | 7,241  | m² | 1.10  | 7,965     |                  |
| Completion of sub-formation on acceptable material; footpath                                                                                                                | 4,751  | m² | 1.10  | 5,226     |                  |
| <u>Lining of Watercourses</u>                                                                                                                                               |        |    |       |           |                  |
| Lining of new watercourse; attenuation pond                                                                                                                                 | 6,747  | m² | 9.34  | 63,016    |                  |
| <b>SERIES 700: PAVEMENTS</b>                                                                                                                                                |        |    |       |           | <b>2,142,769</b> |
| <u>Sub-Base</u>                                                                                                                                                             |        |    |       |           |                  |
| Imported granular sub-base; Type 1 aggregate; 200mm depth; bus way                                                                                                          | 38,080 | m² | 9.86  | 375,469   |                  |
| Imported granular sub-base; Type 1 aggregate; 200mm depth; bus stop                                                                                                         | 360    | m² | 9.86  | 3,550     |                  |
| Imported granular sub-base; Type 1 aggregate; 200mm depth; maintenance track/cycleway                                                                                       | 18,998 | m² | 9.86  | 187,320   |                  |
| Imported granular sub-base; Type 1 aggregate; 200mm depth; carriageway                                                                                                      | 7,241  | m² | 9.86  | 71,396    |                  |
| <u>Maintenance Track / Cycleway Pavement</u>                                                                                                                                |        |    |       |           |                  |
| AC32 HDM base 40/60 Rec 150mm thick in carriageway                                                                                                                          | 18,998 | m² | 25.44 | 483,297   |                  |
| AC20 Dense binder course 40/60 Rec 60mm thick in carriageway                                                                                                                | 18,998 | m² | 10.72 | 203,721   |                  |
| 40mm Thin Surface course system                                                                                                                                             | 18,998 | m² | 11.12 | 211,165   |                  |
| <u>Carriageway Pavement</u>                                                                                                                                                 |        |    |       |           |                  |
| AC32 HDM base 40/60 Rec 150mm thick in carriageway                                                                                                                          | 7,241  | m² | 25.44 | 184,201   |                  |

|                                                                                                                                                                                            |        |        |          |           |           |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|--------|----------|-----------|-----------|
| AC20 Dense binder course 40/60 Rec 60mm thick in carriageway                                                                                                                               | 7,241  | m²     | 10.72    | 77,645    | 6,457,380 |
| 40mm Thin Surface course system                                                                                                                                                            | 6,893  | m²     | 11.12    | 76,614    |           |
| Master tint- Red surface course (40mm)                                                                                                                                                     | 348    | m²     | 44.75    | 15,574    |           |
| Resurfacing: 40mm Thin Surface course system                                                                                                                                               | 7,228  | m²     | 11.12    | 80,378    |           |
| <u>Works to Existing bridge over M11</u>                                                                                                                                                   |        |        |          |           |           |
| Resurfacing: 40mm Thin Surface course system                                                                                                                                               | 12,041 | m²     | 11.12    | 133,900   |           |
| <u>Cold Milling</u>                                                                                                                                                                        |        |        |          |           |           |
| Cold milling/planning; 40mm thick; existing carriageway; including disposal                                                                                                                | 7,228  | m²     | 2.00     | 14,456    |           |
| Cold milling/planning; 40mm thick; existing bridge over M11; including disposal                                                                                                            | 12,041 | m²     | 2.00     | 24,082    |           |
| <b>SERIES 1100: KERBS, FOOTWAYS AMD PAVED AREAS</b>                                                                                                                                        |        |        |          |           |           |
| <u>Slipform Guided Bus Route</u>                                                                                                                                                           |        |        |          |           | 130,844   |
| Steel Reinforcement supply and fit for bus route                                                                                                                                           | 571    | t      | 1,127.46 | 644,051   |           |
| Slip forming the mainline route. Excluding post grinding                                                                                                                                   | 9,521  | m      | 409.99   | 3,903,340 |           |
| Precision post grinding to achieve suitable gauge tolerance                                                                                                                                | 9,521  | m      | 128.12   | 1,219,794 |           |
| Precision post grinding to achieve suitable gauge tolerance                                                                                                                                | 90     | m      | 128.12   | 11,531    |           |
| In situ works for car traps/entry and exit splays                                                                                                                                          | 432    | m      | 1,024.96 | 442,784   |           |
| <u>Kerbs, Channels, Edgings, Combined Drainage and Kerb Blocks</u>                                                                                                                         |        |        |          |           |           |
| Precast concrete kerb; half battered (HB2 125 x 255 x 915mm) laid straight or curved                                                                                                       | 2,857  | m      | 20.19    | 57,686    |           |
| Precast concrete edgings; Laid straight or curved to radius exceeding 12m; 50mm x 150mm                                                                                                    | 754    | m      | 13.72    | 10,340    |           |
| <u>Footways and Paved Areas</u>                                                                                                                                                            |        |        |          |           |           |
| Footpath type 1: comprising Type 1 granular material sub-base 150mm thick; AC20 DBM binder course 40/60 40mm thick; AC6 DBM surface course 20mm thick                                      | 4,751  | m²     | 35.33    | 167,853   | 844,699   |
| <b>SERIES 1200: TRAFFIC SIGNS AND ROAD MARKINGS</b>                                                                                                                                        |        |        |          |           |           |
| <u>Traffic Signs</u>                                                                                                                                                                       |        |        |          |           |           |
| Signs - allowance                                                                                                                                                                          | 1      | nr     | 2,000.00 | 2,000     |           |
| <u>Road Markings</u>                                                                                                                                                                       |        |        |          |           |           |
| Road Marking (Lining Crew) - allowance: to include ped crossings/adjoining roads/maintenance bays, traffic calming measures etc                                                            | 11     | shifts | 1,000.00 | 11,000    |           |
| <u>Traffic Signal Installations</u>                                                                                                                                                        |        |        |          |           |           |
| Traffic signal installation; including; traffic signal head, 4m swan neck pole, NAL socket, pedestrian push button, pedestrian signal indicator, infrared detector, traffic detection loop | 17     | nr     | 5,332.00 | 90,644    |           |
| Traffic signal installation; controller cabinet                                                                                                                                            | 8      | nr     | 3,400.00 | 27,200    |           |
| <b>SERIES 1300: ROAD LIGHTING COLUMNS AND BRACKETS, CCTV MASTS AND CANTILEVER MASTS</b>                                                                                                    |        |        |          |           |           |
| <u>Busway and Road</u>                                                                                                                                                                     |        |        |          |           | 844,699   |
| 8m mounting height tubular galvanised steel column complete with a post top mounted Philips Luma 3 (BGP627 DS50 - 40klm neutral white LED) mounted at 0° tilt - Allowance @ 20m centres    | 268    | nr     | 1,671.12 | 447,860   |           |

|  |                                                                                                                                                                                        |        |      |           |                   |
|--|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------|-----------|-------------------|
|  | Maintenance track/ Cycle way/ Footway                                                                                                                                                  |        |      |           |                   |
|  | 8m mounting height tubular galvanised steel column complete with a post top mounted Philips Luma 3 (BGP627 DS50 - 40km neutral white LED) mounted at 0° tilt - Allowance @ 20m centres | 237    | nr   | 1,671.12  | 396,839           |
|  | <b>SERIES 1400: ELECTRICAL WORK FOR ROAD LIGHTING AND TRAFFIC SIGNS</b>                                                                                                                |        |      |           | <b>1,542,592</b>  |
|  | Busway and Road                                                                                                                                                                        |        |      |           |                   |
|  | Street lighting duct; 1 way x 100mm diameter duct route in verge; not exceeding 1m deep to invert                                                                                      | 5,341  | m    | 27.52     | 146,985           |
|  | Cabling 3 core XLPE/SWA/PVC- Allowance                                                                                                                                                 | 9,629  | m    | 33.14     | 319,105           |
|  | Terminations at each column- Allowance                                                                                                                                                 | 268    | Item | 86.83     | 23,270            |
|  | Tofco feeder pillar (medium), including DNO connection within 2m of LV main                                                                                                            | 14     | nr   | 3,382.51  | 47,355            |
|  | Telensa CMS node - Allowance                                                                                                                                                           | 268    | nr   | 153.22    | 41,063            |
|  | New DNO Connections - Allowance                                                                                                                                                        | 14     | nr   | 15,000.00 | 210,000           |
|  | DNO connection within 2m of lv main (into feeder pillar) - Allowance                                                                                                                   | 3      | nr   | 356.45    | 1,069             |
|  | Street lighting chambers 450 x 450 x 900 (allow 1 per 100m)                                                                                                                            | 53     | nr   | 575.75    | 30,515            |
|  | Maintenance track/ Cycle way/ Footway                                                                                                                                                  |        |      |           |                   |
|  | Street lighting duct; 1 way x 100mm diameter duct route in verge; not exceeding 1m deep to invert                                                                                      | 4,749  | m    | 27.52     | 130,703           |
|  | Cabling 3 core XLPE/SWA/PVC- Allowance                                                                                                                                                 | 8,549  | m    | 33.14     | 283,310           |
|  | Terminations at each column - Allowance                                                                                                                                                | 237    | Item | 86.83     | 20,619            |
|  | Tofco feeder pillar (medium), including DNO connection within 2m of LV main                                                                                                            | 12     | nr   | 3,382.51  | 40,590            |
|  | Telensa CMS node - Allowance                                                                                                                                                           | 237    | nr   | 153.22    | 36,385            |
|  | DNO new connections - Allowance                                                                                                                                                        | 12     | nr   | 15,000.00 | 180,000           |
|  | DNO connection within 2m of lv main (into feeder pillar) - Allowance                                                                                                                   | 12     | nr   | 356.45    | 4,277             |
|  | Street lighting chambers 450 x 450 x 900 (allow 1 per 100m)                                                                                                                            | 47     | nr   | 575.75    | 27,345            |
|  | <b>SERIES 1700: STRUCTURAL CONCRETE</b>                                                                                                                                                |        |      |           | -                 |
|  | Batching plant                                                                                                                                                                         | 1      | item |           | -                 |
|  | <b>SERIES 2500: SPECIAL STRUCTURES</b>                                                                                                                                                 |        |      |           | <b>7,905,295</b>  |
|  | Bus stops (25m in length), including fittings                                                                                                                                          | 4      | nr   | 41,850.00 | 167,400           |
|  | Ticket machine @ Park and Ride                                                                                                                                                         | 2      | nr   | 35,000.00 | 70,000            |
|  | <b>Green bridge over M11</b>                                                                                                                                                           |        |      |           |                   |
|  | Construct new overpass; including foundations, abutments, wingwalls, deck, parapets, approaches and drainage. Deck Area measured; Difficult Complexity                                 | 1,112  | m²   | 5,500.00  | 6,115,395         |
|  | <b>Bridge over Bin Brook Crossing</b>                                                                                                                                                  |        |      |           |                   |
|  | Construct new bridge; including foundations, abutments, wingwalls, deck, parapets, approaches and drainage. Deck Area measured; Normal Complexity                                      | 345    | m²   | 4,500.00  | 1,552,500         |
|  | <b>SERIES 3000: LANDSCAPING AND ECOLOGY</b>                                                                                                                                            |        |      |           | <b>1,657,605</b>  |
|  | Landscaping                                                                                                                                                                            | 79,937 | m²   | 20.00     | 1,598,744         |
|  | 1.2m high clipped hedgerow (along the busway)                                                                                                                                          | 1,678  | m    | 15.55     | 26,092            |
|  | Meadow planting- 100% meadow (near Cambridge Road)                                                                                                                                     | 19,593 | m²   | 0.77      | 15,182            |
|  | Extension to plantation woodland (across Top Pitch)                                                                                                                                    | 9,431  | m²   | 1.33      | 12,570            |
|  | <b>Green bridge over M11</b>                                                                                                                                                           |        |      |           |                   |
|  | Allowance for planting on the bridge (assumed bare rooted native species whips as screen)                                                                                              | 273    | m²   | 18.38     | 5,017             |
|  | <b>Total</b>                                                                                                                                                                           |        |      |           | <b>25,908,289</b> |
|  |                                                                                                                                                                                        |        |      |           | <b>25,908,289</b> |

|                                                                                                                                                       |       |        |              |                |                |
|-------------------------------------------------------------------------------------------------------------------------------------------------------|-------|--------|--------------|----------------|----------------|
| <b>30% SURFACING RENEWALS</b>                                                                                                                         |       |        |              |                |                |
| <b>SERIES 200: SITE CLEARANCE</b>                                                                                                                     |       |        |              |                | <b>20,082</b>  |
| General Site Clearance                                                                                                                                | 9,297 | m²     | 2.16         | 20,082         |                |
| <b>SERIES 600: EARTHWORKS</b>                                                                                                                         |       |        |              |                | <b>127,528</b> |
| <u>Excavation</u>                                                                                                                                     |       |        |              |                |                |
| Excavation of artificial hard material; Maintenance Track/ Cycle Way                                                                                  | 1,539 | m³     | 11.52        | 17,727         |                |
| Excavation of artificial hard material; Carriageway                                                                                                   | 587   | m³     | 11.52        | 6,757          |                |
| Excavation of artificial hard material; Footpaths                                                                                                     | 299   | m³     | 11.52        | 3,448          |                |
| Extra over for breaking out surfacing                                                                                                                 | 2,425 | m³     | 9.74         | 23,616         |                |
| <u>Disposal of Material</u>                                                                                                                           |       |        |              |                |                |
| Disposal of acceptable material excluding Class 5A                                                                                                    | 2,425 | m³     | 28.23        | 68,448         |                |
| <u>Completion of Formation and Sub-formation</u>                                                                                                      |       |        |              |                |                |
| Completion of sub-formation on acceptable material                                                                                                    | 9,297 | m²     | 0.81         | 7,531          |                |
| <b>SERIES 700: PAVEMENTS</b>                                                                                                                          |       |        |              |                | <b>372,337</b> |
| <b>Pavement; Car Park</b>                                                                                                                             |       |        |              |                |                |
| <u>Sub-base</u>                                                                                                                                       |       |        |              |                |                |
| Imported granular sub-base; Type 1 aggregate; 20mm depth (top up)                                                                                     | 186   | m²     | 0.99         | 183            |                |
| <u>Pavement</u>                                                                                                                                       |       |        |              |                |                |
| AC32 HDM base 40/60 Rec 150mm thick                                                                                                                   | 7,871 | m²     | 25.44        | 200,249        |                |
| AC20 Dense binder course 40/60 Rec 60mm thick                                                                                                         | 7,871 | m²     | 10.72        | 84,410         |                |
| 40mm Thin Surface course system                                                                                                                       | 7,871 | m²     | 11.12        | 87,494         |                |
| <b>SERIES 1100: KERBS, FOOTWAYS AMD PAVED AREAS</b>                                                                                                   |       |        |              |                | <b>50,356</b>  |
| <u>Footways and Paved Areas</u>                                                                                                                       |       |        |              |                |                |
| Footpath type 1; comprising Type 1 granular material sub-base 150mm thick; AC20 DBM binder course 40/60 40mm thick; AC6 DBM surface course 20mm thick | 1,425 | m²     | 35.33        | 50,356         |                |
| <b>SERIES 1200: TRAFFIC SIGNS AND ROAD MARKINGS</b>                                                                                                   |       |        |              |                | <b>4,000</b>   |
| <u>Road Markings</u>                                                                                                                                  |       |        |              |                |                |
| Road Marking (Lining Crew)                                                                                                                            | 4     | shifts | 1000.00      | 4,000          |                |
|                                                                                                                                                       |       |        | <b>Total</b> | <b>574,302</b> |                |

|                                              |                                               |                                           |        |         |         |        |
|----------------------------------------------|-----------------------------------------------|-------------------------------------------|--------|---------|---------|--------|
| 100% ROAD RESURFACE, INCLUDING BRIDGE DECKS  | 100% ROAD RESURFACE, INCLUDING BRIDGE DECKS   |                                           |        |         |         |        |
|                                              | SERIES 200: SITE CLEARANCE                    |                                           |        |         |         |        |
|                                              | General Site Clearance                        | 44,139                                    | m²     | 2.16    | 95,341  |        |
|                                              | SERIES 700: PAVEMENTS                         |                                           |        |         |         |        |
|                                              | Cold Milling                                  |                                           |        |         |         |        |
|                                              | Cold milling/planning; 40mm thick             | 44,139                                    | m²     | 2.00    | 88,279  |        |
|                                              | Pavement; Car Park                            |                                           |        |         |         |        |
|                                              | Pavement                                      |                                           |        |         |         |        |
|                                              | Tack coat                                     | 44,139                                    | m²     | 0.50    | 22,070  |        |
|                                              | 40mm Thin Surface course system               | 44,139                                    | m²     | 11.12   | 490,627 |        |
| SERIES 1200: TRAFFIC SIGNS AND ROAD MARKINGS | SERIES 1200: TRAFFIC SIGNS AND ROAD MARKINGS  |                                           |        |         |         |        |
|                                              | Road Markings                                 |                                           |        |         |         |        |
|                                              | Road Marking (Lining Crew)                    | 11                                        | shifts | 1000.00 | 11,000  |        |
|                                              | Total                                         |                                           |        |         | 707,316 |        |
| BRIDGE DECKS FULL DEPTH RESURFACING          | BRIDGE DECKS FULL DEPTH RESURFACING           |                                           |        |         |         |        |
|                                              | SERIES 200: SITE CLEARANCE                    |                                           |        |         |         |        |
|                                              | General Site Clearance                        | 1,457                                     | m²     | 2.16    | 3,147   |        |
|                                              | SERIES 700: PAVEMENTS                         |                                           |        |         |         |        |
|                                              | Cold Milling                                  |                                           |        |         |         |        |
|                                              | Cold milling/planning; 100mm thick            | 1,457                                     | m²     | 5.00    | 7,284   |        |
|                                              | Cold milling/planning; 150mm thick            | 1,457                                     | m²     | 7.50    | 10,927  |        |
|                                              | Pavement; Car Park                            |                                           |        |         |         |        |
|                                              | Pavement                                      |                                           |        |         |         |        |
|                                              | Tack coat                                     | 1,457                                     | m²     | 0.50    | 728     |        |
|                                              | AC32 HDM base 40/60 Rec 150mm thick           | 1,457                                     | m²     | 25.44   | 37,063  |        |
|                                              | AC20 Dense binder course 40/60 Rec 60mm thick | 1,457                                     | m²     | 10.72   | 15,623  |        |
|                                              | 40mm Thin Surface course system               | 1,457                                     | m²     | 11.12   | 16,194  |        |
|                                              | SERIES 1200: TRAFFIC SIGNS AND ROAD MARKINGS  |                                           |        |         |         |        |
|                                              | Road Markings                                 |                                           |        |         |         |        |
|                                              | Road Marking (Lining Crew)                    | 2                                         | shifts | 1000.00 | 2,000   |        |
|                                              | SERIES 2000: WATERPROOFING FOR STRUCTURES     | SERIES 2000: WATERPROOFING FOR STRUCTURES |        |         |         |        |
|                                              |                                               | Spray applied waterproofing system        | 1,457  | m²      | 25.00   | 36,422 |
| Total                                        |                                               |                                           |        | 129,389 |         |        |

## 6 Option 1

## Cambridge to Cambourne

## Phase 2 Option 1

| Item                                                                                                                                                                  | Qty    | Unit           | Unit rate<br>£ | Total<br>£ | Subtotal<br>£    |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|----------------|----------------|------------|------------------|
| <b>INITIAL CONSTRUCTION</b>                                                                                                                                           |        |                |                |            |                  |
| <b>SERIES 200: SITE CLEARANCE</b>                                                                                                                                     |        |                |                |            | <b>204,307</b>   |
| General Site Clearance                                                                                                                                                | 94,587 | m <sup>2</sup> | 2.16           | 204,307    |                  |
| <b>SERIES 500: DRAINAGE AND SERVICE DUCTS</b>                                                                                                                         |        |                |                |            | <b>2,978,630</b> |
| <u>Busway</u>                                                                                                                                                         |        |                |                |            |                  |
| Precast concrete trapped gully with Class D400 grating and frame; 450mm x 750mm                                                                                       | 569    | nr             | 491.64         | 279,918    |                  |
| 150mm diameter carrier drain with type S bed and surround; depth to invert not exceeding 2m                                                                           | 1,879  | m              | 47.72          | 89,660     |                  |
| 225mm diameter carrier drain with type S bed and surround; depth to invert 2m - 2.5m                                                                                  | 12,526 | m              | 84.11          | 1,053,546  |                  |
| Connections to existing drainage/outfalls; 225mm dia; depth to invert exceeding 2m but not exceeding 4m                                                               | 11     | nr             | 277.32         | 3,051      |                  |
| Manhole; Depth : not exceeding 1.5 m; Type 2A (1.5m internal diameter) complete with allowance for concrete butt and rocker pipes                                     | 134    | nr             | 3,084.61       | 413,233    |                  |
| Drainage interceptor - Allowance of 1 per 1000m of drainage                                                                                                           | 11     | nr             | 10,000.00      | 110,000    |                  |
| Outfalls - Allowance of 1 per 1000m of drainage                                                                                                                       | 11     | nr             | 10,000.00      | 110,000    |                  |
| <u>Dual Carriageway</u>                                                                                                                                               |        |                |                |            |                  |
| 225mm diameter carrier drain with type S bed and surround; depth to invert 2m - 2.5m                                                                                  | 5,320  | m              | 84.11          | 447,454    |                  |
| Connections to existing drainage/outfalls; 225mm dia; depth to invert exceeding 2m but not exceeding 4m                                                               | 6      | nr             | 277.32         | 1,664      |                  |
| Precast concrete trapped gully with Class D400 grating and frame; 450mm x 750mm                                                                                       | 266    | nr             | 491.64         | 130,776    |                  |
| Manhole; Depth : not exceeding 1.5 m; Type 2A (1.5m internal diameter) complete with allowance for concrete butt and rocker pipes                                     | 63     | nr             | 3,084.61       | 194,330    |                  |
| Drainage interceptor - Allowance of 1 per 1000m of drainage                                                                                                           | 6      | nr             | 10,000.00      | 60,000     |                  |
| Outfalls - Allowance of 1 per 1000m of drainage                                                                                                                       | 6      | nr             | 10,000.00      | 60,000     |                  |
| Culverts - Allowance                                                                                                                                                  | 1      | nr             | 25,000.00      | 25,000     |                  |
| <b>SERIES 600: EARTHWORKS</b>                                                                                                                                         |        |                |                |            | <b>2,333,248</b> |
| <u>Excavation of Topsoil</u>                                                                                                                                          |        |                |                |            |                  |
| Excavation of acceptable material Class 5A Topsoil 150mm                                                                                                              | 14,188 | m <sup>3</sup> | 5.61           | 79,595     |                  |
| <u>General Excavation</u>                                                                                                                                             |        |                |                |            |                  |
| Excavation to busway subformation; Excavation of acceptable material normal material, excluding hard or artificially hard material, excluding Class 5A; > 2500m3      | 33,250 | m <sup>3</sup> | 1.49           | 49,543     |                  |
| Excavation to bus stop subformation; Excavation of acceptable material; excluding Class 5A; normal material, excluding hard or artificially hard material, <2500m3    | 342    | m <sup>3</sup> | 2.54           | 869        |                  |
| Excavation to carriageway subformation; Excavation of acceptable material normal material, excluding hard or artificially hard material, excluding Class 5A; > 2500m3 | 11,845 | m <sup>3</sup> | 1.49           | 17,649     |                  |
| Excavation to attenuation pond; Excavation of acceptable material normal material, excluding hard or artificially hard material, excluding Class 5A; > 2500m3         | 6,908  | m <sup>3</sup> | 1.49           | 10,293     |                  |
| <u>Imported Fill</u>                                                                                                                                                  |        |                |                |            |                  |
| Imported acceptable material; Capping material; Class 6F2; for carriageway, 240mm thk                                                                                 | 4,660  | m <sup>3</sup> | 40.64          | 189,390    |                  |

|                                                                                                                              |        |    |          |           |                  |
|------------------------------------------------------------------------------------------------------------------------------|--------|----|----------|-----------|------------------|
| <u>Compaction of Material</u>                                                                                                |        |    |          |           |                  |
| Compaction of fill material to large areas                                                                                   | 4,660  | m³ | 3.50     | 16,311    |                  |
| <u>Disposal of Material</u>                                                                                                  |        |    |          |           |                  |
| Disposal of acceptable Class 5A topsoil                                                                                      | 10,333 | m³ | 28.23    | 291,709   |                  |
| Disposal of acceptable material excluding Class 5A                                                                           | 52,345 | m³ | 28.23    | 1,477,697 |                  |
| <u>Topsoiling and Storage of Topsoil</u>                                                                                     |        |    |          |           |                  |
| Topsoiling; Class 5A material excavated from site; 150mm thick; Sloping at 10 eg or less to the horizontal, >5000m2 (>750m3) | 25,698 | m² | 1.10     | 28,268    |                  |
| <u>Completion of Formation and Sub-formation</u>                                                                             |        |    |          |           |                  |
| Completion of sub-formation on acceptable material; bus stops                                                                | 360    | m² | 1.10     | 396       |                  |
| Completion of sub-formation on acceptable material; bus way                                                                  | 45,552 | m² | 1.10     | 50,107    |                  |
| Completion of sub-formation on acceptable material; carriageway                                                              | 19,417 | m² | 1.10     | 21,359    |                  |
| Completion of sub-formation on acceptable material; footpath                                                                 | 21,020 | m² | 1.10     | 23,122    |                  |
| <u>Lining of Watercourses</u>                                                                                                |        |    |          |           |                  |
| Lining of new watercourse; attenuation pond                                                                                  | 8,238  | m² | 9.34     | 76,941    |                  |
| <b>SERIES 700: PAVEMENTS</b>                                                                                                 |        |    |          |           | <b>1,865,715</b> |
| <u>Sub-Base</u>                                                                                                              |        |    |          |           |                  |
| Imported granular sub-base; Type 1 aggregate; 200mm depth; bus way                                                           | 45,552 | m² | 9.86     | 449,143   |                  |
| Imported granular sub-base; Type 1 aggregate; 200mm depth; bus stop                                                          | 360    | m² | 9.86     | 3,550     |                  |
| Imported granular sub-base; Type 1 aggregate; 200mm depth; carriageway                                                       | 19,417 | m² | 9.86     | 191,452   |                  |
| <u>Dual carriageway</u>                                                                                                      |        |    |          |           |                  |
| AC32 HDM base 40/60 Rec 150mm thick in carriageway                                                                           | 19,417 | m² | 25.44    | 493,981   |                  |
| AC20 Dense binder course 40/60 Rec 60mm thick in carriageway                                                                 | 19,417 | m² | 10.72    | 208,225   |                  |
| 40mm Thin Surface course system                                                                                              | 19,417 | m² | 11.12    | 215,833   |                  |
| Resurfacing: 40mm Thin Surface course system                                                                                 | 23,135 | m² | 11.12    | 257,261   |                  |
| <u>Cold Milling</u>                                                                                                          |        |    |          |           |                  |
| Cold milling/planning; 40mm thick; existing carriageway; including disposal                                                  | 23,135 | m² | 2.00     | 46,270    |                  |
| <b>SERIES 1100: KERBS, FOOTWAYS AMD PAVED AREAS</b>                                                                          |        |    |          |           | <b>8,076,886</b> |
| <u>Slipform Guided Bus Route</u>                                                                                             |        |    |          |           |                  |
| Steel Reinforcement supply and fit for bus route                                                                             | 683    | t  | 1,127.46 | 770,310   |                  |
| Slip forming the mainline route. Excluding post grinding                                                                     | 11,387 | m  | 409.99   | 4,668,546 |                  |
| Precision post grinding to achieve suitable gauge tolerance                                                                  | 11,387 | m  | 128.12   | 1,458,921 |                  |
| Precision post grinding to achieve suitable gauge tolerance                                                                  | 90     | m  | 128.12   | 11,531    |                  |
| In situ works for car traps/entry and exit splays                                                                            | 216    | m  | 1,024.96 | 221,392   |                  |
| <u>Kerbs, Channels, Edgings, Combined Drainage and Kerb Blocks</u>                                                           |        |    |          |           |                  |
| Precast concrete kerb; half battered (HB2 125 x 255 x 915mm) laid straight or curved                                         | 5,320  | m  | 20.19    | 107,408   |                  |
| Precast concrete edgings; Laid straight or curved to radius exceeding 12m; 50mm x 150mm                                      | 7,007  | m  | 13.72    | 96,133    |                  |

|                                                                                                                                                                                            |        |        |           |         |                  |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|--------|-----------|---------|------------------|
| <u>Footways and Paved Areas</u>                                                                                                                                                            |        |        |           |         |                  |
| Footpath type 1; comprising Type 1 granular material sub-base 150mm thick; AC20 DBM binder course 40/60 40mm thick; AC6 DBM surface course 20mm thick                                      | 21,020 | m²     | 35.33     | 742,645 |                  |
| <b>SERIES 1200: TRAFFIC SIGNS AND ROAD MARKINGS</b>                                                                                                                                        |        |        |           |         | <b>145,176</b>   |
| <u>Traffic Signs</u>                                                                                                                                                                       |        |        |           |         |                  |
| Signs - allowance                                                                                                                                                                          | 1      | nr     | 5,000.00  | 5,000   |                  |
| <u>Road Markings</u>                                                                                                                                                                       |        |        |           |         |                  |
| Road marking - allowance: to include ped crossings/adjoining roads/maintenance                                                                                                             | 17     | shifts | 1,000.00  | 17,000  |                  |
| <u>Traffic Lights</u>                                                                                                                                                                      |        |        |           |         |                  |
| Traffic signal installation; including; traffic signal head, 4m swan neck pole, NAL socket, pedestrian push button, pedestrian signal indicator, infrared detector, traffic detection loop | 18     | nr     | 5,332.00  | 95,976  |                  |
| Traffic signal installation; controller cabinet                                                                                                                                            | 8      | nr     | 3,400.00  | 27,200  |                  |
| <b>SERIES 1300: ROAD LIGHTING COLUMNS AND BRACKETS, CCTV MASTS AND CANTILEVER MASTS</b>                                                                                                    |        |        |           |         | <b>698,528</b>   |
| <u>Busway</u>                                                                                                                                                                              |        |        |           |         |                  |
| 8m mounting height tubular galvanised steel column complete with a post top mounted Philips Luma 3 (BGP627 DS50 - 40klm neutral white LED) mounted at 0° tilt - Allowance @ 20m centres    | 285    | nr     | 1,671.12  | 476,269 |                  |
| <u>Dual carriageway</u>                                                                                                                                                                    |        |        |           |         |                  |
| 8m mounting height tubular galvanised steel column complete with a post top mounted Philips Luma 3 (BGP627 DS50 - 40klm neutral white LED) mounted at 0° tilt - Allowance @ 20m centres    | 133    | nr     | 1,671.12  | 222,259 |                  |
| <b>SERIES 1400: ELECTRICAL WORK FOR ROAD LIGHTING AND TRAFFIC SIGNS</b>                                                                                                                    |        |        |           |         | <b>1,283,264</b> |
| <u>Busway</u>                                                                                                                                                                              |        |        |           |         |                  |
| Street lighting duct; 1 way x 100mm diameter duct route in verge; not exceeding 1m deep to invert                                                                                          | 5,694  | m      | 27.52     | 156,686 |                  |
| Cabling 3 core XLPE/SWA/PVC- Allowance                                                                                                                                                     | 10,254 | m      | 33.14     | 339,803 |                  |
| Terminations at each column- Allowance                                                                                                                                                     | 285    | Item   | 86.83     | 24,747  |                  |
| Tofco feeder pillar (medium), including DNO connection within 2m of LV main                                                                                                                | 15     | nr     | 3,382.51  | 50,738  |                  |
| Telensa CMS node - Allowance                                                                                                                                                               | 285    | nr     | 153.22    | 43,668  |                  |
| New DNO Connections - Allowance                                                                                                                                                            | 15     | nr     | 15,000.00 | 225,000 |                  |
| DNO connection within 2m of lv main (into feeder pillar) - Allowance                                                                                                                       | 3      | nr     | 356.45    | 1,069   |                  |
| Street lighting chambers 450 x 450 x 900 (allow 1 per 100m)                                                                                                                                | 57     | nr     | 575.75    | 32,818  |                  |
| <u>Dual carriageway</u>                                                                                                                                                                    |        |        |           |         |                  |
| Street lighting duct; 1 way x 100mm diameter duct route in verge; not exceeding 1m deep to invert                                                                                          | 2,660  | m      | 27.52     | 73,201  |                  |
| Cabling 3 core XLPE/SWA/PVC- Allowance                                                                                                                                                     | 4,788  | m      | 33.14     | 158,672 |                  |
| Terminations at each column- Allowance                                                                                                                                                     | 133    | Item   | 86.83     | 11,548  |                  |
| Tofco feeder pillar (medium), including DNO connection within 2m of LV main                                                                                                                | 7      | nr     | 3,382.51  | 23,678  |                  |
| Telensa CMS node - Allowance                                                                                                                                                               | 133    | nr     | 153.22    | 20,378  |                  |
| New DNO Connections - Allowance                                                                                                                                                            | 7      | nr     | 15,000.00 | 105,000 |                  |
| DNO connection within 2m of lv main (into feeder pillar) - Allowance                                                                                                                       | 2      | nr     | 356.45    | 713     |                  |
| Street lighting chambers 450 x 450 x 900 (allow 1 per 100m)                                                                                                                                | 27     | nr     | 575.75    | 15,545  |                  |
| <b>SERIES 1700: STRUCTURAL CONCRETE</b>                                                                                                                                                    |        |        |           |         | -                |
| Batching plant                                                                                                                                                                             | 1      | item   |           | -       |                  |

|                                                             |        |                |              |                   |                  |
|-------------------------------------------------------------|--------|----------------|--------------|-------------------|------------------|
| <b>SERIES 2500: SPECIAL STRUCTURES</b>                      |        |                |              |                   | <b>307,400</b>   |
| Bus stops (25m in length), including fittings               | 4      | nr             | 41,850.00    | 167,400           |                  |
| Ticket Machines - Allowance                                 | 4      | nr             | 35,000.00    | 140,000           |                  |
| <b>SERIES 3000: LANDSCAPING AND ECOLOGY</b>                 |        |                |              |                   | <b>1,457,620</b> |
| Landscaping                                                 | 71,119 | m <sup>2</sup> | 20.00        | 1,422,386         |                  |
| Planting normal sized shrubs (3L pots) and trees            | 469    | m <sup>2</sup> | 20.00        | 9,370             |                  |
| Meadow planting (90% wildflower, 10% area to include tress) | 18,525 | m <sup>2</sup> | 0.81         | 14,929            |                  |
| Extension to plantation woodland                            | 7,173  | m <sup>2</sup> | 1.33         | 9,560             |                  |
| Climbers and trailers                                       | 275    | m              | 5.00         | 1,375             |                  |
|                                                             |        |                | <b>Total</b> | <b>19,350,775</b> |                  |

|                                                                                                                                                       |        |                |              |                |                |
|-------------------------------------------------------------------------------------------------------------------------------------------------------|--------|----------------|--------------|----------------|----------------|
| <b>30% SURFACING RENEWALS</b>                                                                                                                         |        |                |              |                |                |
| <b>SERIES 200: SITE CLEARANCE</b>                                                                                                                     |        |                |              |                | <b>26,203</b>  |
| General Site Clearance                                                                                                                                | 12,131 | m <sup>2</sup> | 2.16         | 26,203         |                |
| <b>SERIES 600: EARTHWORKS</b>                                                                                                                         |        |                |              |                | <b>153,201</b> |
| <u>Excavation</u>                                                                                                                                     |        |                |              |                |                |
| Excavation of artificial hard material; Carriageway                                                                                                   | 1,573  | m <sup>3</sup> | 11.52        | 18,118         |                |
| Excavation of artificial hard material; Footpaths                                                                                                     | 1,324  | m <sup>3</sup> | 11.52        | 15,255         |                |
| Extra over for breaking out surfacing                                                                                                                 | 2,897  | m <sup>3</sup> | 9.74         | 28,217         |                |
| <u>Disposal of Material</u>                                                                                                                           |        |                |              |                |                |
| Disposal of acceptable material excluding Class 5A                                                                                                    | 2,897  | m <sup>3</sup> | 28.23        | 81,783         |                |
| <u>Completion of Formation and Sub-formation</u>                                                                                                      |        |                |              |                |                |
| Completion of sub-formation on acceptable material                                                                                                    | 12,131 | m <sup>2</sup> | 0.81         | 9,826          |                |
| <b>SERIES 700: PAVEMENTS</b>                                                                                                                          |        |                |              |                | <b>275,651</b> |
| <b>Pavement; Car Park</b>                                                                                                                             |        |                |              |                |                |
| <u>Sub-base</u>                                                                                                                                       |        |                |              |                |                |
| Imported granular sub-base; Type 1 aggregate; 20mm depth car park (top up)                                                                            | 243    | m <sup>2</sup> | 0.99         | 239            |                |
| <u>Pavement</u>                                                                                                                                       |        |                |              |                |                |
| AC32 HDM base 40/60 Rec 150mm thick                                                                                                                   | 5,825  | m <sup>2</sup> | 25.44        | 148,194        |                |
| AC20 Dense binder course 40/60 Rec 60mm thick in carriageway and car park                                                                             | 5,825  | m <sup>2</sup> | 10.72        | 62,468         |                |
| 40mm Thin Surface course system                                                                                                                       | 5,825  | m <sup>2</sup> | 11.12        | 64,750         |                |
| <b>SERIES 1100: KERBS, FOOTWAYS AMD PAVED AREAS</b>                                                                                                   |        |                |              |                | <b>222,794</b> |
| <u>Footways and Paved Areas</u>                                                                                                                       |        |                |              |                |                |
| Footpath type 1; comprising Type 1 granular material sub-base 150mm thick; AC20 DBM binder course 40/60 40mm thick; AC6 DBM surface course 20mm thick | 6,306  | m <sup>2</sup> | 35.33        | 222,794        |                |
| <b>SERIES 1200: TRAFFIC SIGNS AND ROAD MARKINGS</b>                                                                                                   |        |                |              |                | <b>6,000</b>   |
| <u>Road Markings</u>                                                                                                                                  |        |                |              |                |                |
| Road Marking                                                                                                                                          | 6      | shifts         | 1000.00      | 6,000          |                |
|                                                                                                                                                       |        |                | <b>Total</b> | <b>683,849</b> |                |

|                                                     |        |                |              |                  |                |
|-----------------------------------------------------|--------|----------------|--------------|------------------|----------------|
| <b>100% ROAD RESURFACE</b>                          |        |                |              |                  |                |
| <b>SERIES 200: SITE CLEARANCE</b>                   |        |                |              |                  | <b>137,317</b> |
| General Site Clearance                              | 63,573 | m <sup>2</sup> | 2.16         | 137,317          |                |
| <b>SERIES 700: PAVEMENTS</b>                        |        |                |              |                  | <b>865,569</b> |
| <b>Cold Milling</b>                                 |        |                |              |                  |                |
| Cold milling/planning; 40mm thick                   | 63,573 | m <sup>2</sup> | 2.00         | 127,145          |                |
| <b>Pavement; Car Park</b>                           |        |                |              |                  |                |
| <u>Pavement</u>                                     |        |                |              |                  |                |
| Tack coat                                           | 63,573 | m <sup>2</sup> | 0.50         | 31,786           |                |
| 40mm Thin Surface course system                     | 63,573 | m <sup>2</sup> | 11.12        | 706,637          |                |
| <b>SERIES 1200: TRAFFIC SIGNS AND ROAD MARKINGS</b> |        |                |              |                  | <b>17,000</b>  |
| <u>Road Markings</u>                                |        |                |              |                  |                |
| Road Marking                                        | 17     | shifts         | 1000.00      | 17,000           |                |
|                                                     |        |                | <b>Total</b> | <b>1,019,886</b> |                |

## 7 Option 2

## Cambridge to Cambourne

## Phase 2 Option 2

| Item                                                                                                                                                                  | Qty    | Unit           | Unit rate<br>£ | Total<br>£ | Subtotal<br>£    |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|----------------|----------------|------------|------------------|
| <b>INITIAL CONSTRUCTION</b>                                                                                                                                           |        |                |                |            |                  |
| <b>SERIES 200: SITE CLEARANCE</b>                                                                                                                                     |        |                |                |            | <b>130,931</b>   |
| General Site Clearance                                                                                                                                                | 60,616 | m <sup>2</sup> | 2.16           | 130,931    |                  |
| <b>SERIES 500: DRAINAGE AND SERVICE DUCTS</b>                                                                                                                         |        |                |                |            | <b>1,633,027</b> |
| <u>Busway</u>                                                                                                                                                         |        |                |                |            |                  |
| Precast concrete trapped gully with Class D400 grating and frame; 450mm x 750mm                                                                                       | 208    | nr             | 491.64         | 102,181    |                  |
| 150mm diameter carrier drain with type S bed and surround; depth to invert not exceeding 2m                                                                           | 686    | m              | 47.72          | 32,729     |                  |
| 225mm diameter carrier drain with type S bed and surround; depth to invert 2m - 2.5m                                                                                  | 4,572  | m              | 84.11          | 384,586    |                  |
| Connections to existing drainage/outfalls; 225mm dia; depth to invert exceeding 2m but not exceeding 4m                                                               | 4      | nr             | 277.32         | 1,109      |                  |
| Manhole: Depth : not exceeding 1.5 m; Type 2A (1.5m internal diameter) complete with allowance for concrete butt and rocker pipes                                     | 49     | nr             | 3,084.61       | 150,846    |                  |
| Drainage interceptor - Allowance of 1 per 1000m of drainage                                                                                                           | 4      | nr             | 10,000.00      | 40,000     |                  |
| Outfalls - Allowance of 1 per 1000m of drainage                                                                                                                       | 4      | nr             | 10,000.00      | 40,000     |                  |
| <u>Dual Carriageway</u>                                                                                                                                               |        |                |                |            |                  |
| 225mm diameter carrier drain with type S bed and surround; depth to invert 2m - 2.5m                                                                                  | 5,058  | m              | 84.11          | 425,450    |                  |
| Connections to existing drainage/outfalls; 225mm dia; depth to invert exceeding 2m but not exceeding 4m                                                               | 6      | nr             | 277.32         | 1,664      |                  |
| Precast concrete trapped gully with Class D400 grating and frame; 450mm x 750mm                                                                                       | 253    | nr             | 491.64         | 124,385    |                  |
| Manhole: Depth : not exceeding 1.5 m; Type 2A (1.5m internal diameter) complete with allowance for concrete butt and rocker pipes                                     | 60     | nr             | 3,084.61       | 185,077    |                  |
| Drainage interceptor - Allowance of 1 per 1000m of drainage                                                                                                           | 6      | nr             | 10,000.00      | 60,000     |                  |
| Outfalls - Allowance of 1 per 1000m of drainage                                                                                                                       | 6      | nr             | 10,000.00      | 60,000     |                  |
| Culverts - Allowance                                                                                                                                                  | 1      | nr             | 25,000.00      | 25,000     |                  |
| <b>SERIES 600: EARTHWORKS</b>                                                                                                                                         |        |                |                |            | <b>1,394,064</b> |
| <u>Excavation of Topsoil</u>                                                                                                                                          |        |                |                |            |                  |
| Excavation of acceptable material Class 5A Topsoil 150mm                                                                                                              | 9,092  | m <sup>3</sup> | 5.61           | 51,008     |                  |
| <u>General Excavation</u>                                                                                                                                             |        |                |                |            |                  |
| Excavation to busway subformation; Excavation of acceptable material normal material, excluding hard or artificially hard material, excluding Class 5A; > 2500m3      | 12,138 | m <sup>3</sup> | 1.49           | 18,085     |                  |
| Excavation to bus stop subformation; Excavation of acceptable material; excluding Class 5A; normal material, excluding hard or artificially hard material, <2500m3    | 342    | m <sup>3</sup> | 2.54           | 869        |                  |
| Excavation to carriageway subformation; Excavation of acceptable material normal material, excluding hard or artificially hard material, excluding Class 5A; > 2500m3 | 11,262 | m <sup>3</sup> | 1.49           | 16,781     |                  |
| Excavation to attenuation pond; Excavation of acceptable material normal material, excluding hard or artificially hard material, excluding Class 5A; > 2500m3         | 4,411  | m <sup>3</sup> | 1.49           | 6,573      |                  |
| <u>Imported Fill</u>                                                                                                                                                  |        |                |                |            |                  |
| Imported acceptable material; Capping material; Class 6F2; for carriageway, 240mm thk                                                                                 | 4,431  | m <sup>3</sup> | 40.64          | 180,077    |                  |
| <u>Compaction of Material</u>                                                                                                                                         |        |                |                |            |                  |
| Compaction of fill material to large areas                                                                                                                            | 4,431  | m <sup>3</sup> | 3.50           | 15,509     |                  |
| <u>Disposal of Material</u>                                                                                                                                           |        |                |                |            |                  |
| Disposal of acceptable Class 5A topsoil                                                                                                                               | 6,314  | m <sup>3</sup> | 28.23          | 178,235    |                  |
| Disposal of acceptable material excluding Class 5A                                                                                                                    | 28,153 | m <sup>3</sup> | 28.23          | 794,766    |                  |

|                                                                                                                                                       |        |                |          |           |                  |
|-------------------------------------------------------------------------------------------------------------------------------------------------------|--------|----------------|----------|-----------|------------------|
| <u>Topsoiling and Storage of Topsoil</u>                                                                                                              |        |                |          |           |                  |
| Topsoiling; Class 5A material excavated from site; 150mm thick; Sloping at 10 eg or less to the horizontal, >5000m2 (>750m3)                          | 18,525 | m <sup>2</sup> | 1.10     | 20,378    |                  |
| <u>Completion of Formation and Sub-formation</u>                                                                                                      |        |                |          |           |                  |
| Completion of sub-formation on acceptable material; bus stops                                                                                         | 360    | m <sup>2</sup> | 1.10     | 396       |                  |
| Completion of sub-formation on acceptable material; bus way                                                                                           | 16,624 | m <sup>2</sup> | 1.10     | 18,286    |                  |
| Completion of sub-formation on acceptable material; carriageway                                                                                       | 18,463 | m <sup>2</sup> | 1.10     | 20,309    |                  |
| Completion of sub-formation on acceptable material; footpath                                                                                          | 19,695 | m <sup>2</sup> | 1.10     | 21,665    |                  |
| <u>Lining of Watercourses</u>                                                                                                                         |        |                |          |           |                  |
| Lining of new watercourse; attenuation pond                                                                                                           | 5,474  | m <sup>2</sup> | 9.34     | 51,128    |                  |
| <b>SERIES 700: PAVEMENTS</b>                                                                                                                          |        |                |          |           | <b>1,648,558</b> |
| <u>Sub-Base</u>                                                                                                                                       |        |                |          |           |                  |
| Imported granular sub-base; Type 1 aggregate; 200mm depth; bus way                                                                                    | 3,325  | m <sup>3</sup> | 46.50    | 154,603   |                  |
| Imported granular sub-base; Type 1 aggregate; 200mm depth; bus stop                                                                                   | 72     | m <sup>3</sup> | 46.50    | 3,348     |                  |
| Imported granular sub-base; Type 1 aggregate; 200mm depth; carriageway                                                                                | 3,693  | m <sup>3</sup> | 46.50    | 171,706   |                  |
| <u>Dual carriageway</u>                                                                                                                               |        |                |          |           |                  |
| AC32 HDM base 40/60 Rec 150mm thick in carriageway                                                                                                    | 18,463 | m <sup>2</sup> | 25.44    | 469,690   |                  |
| AC20 Dense binder course 40/60 Rec 60mm thick in carriageway                                                                                          | 18,463 | m <sup>2</sup> | 10.72    | 197,986   |                  |
| 40mm Thin Surface course system                                                                                                                       | 18,463 | m <sup>2</sup> | 11.12    | 205,220   |                  |
| Resurfacing: 40mm Thin Surface course system                                                                                                          | 33,994 | m <sup>2</sup> | 11.12    | 378,016   |                  |
| <u>Cold Milling</u>                                                                                                                                   |        |                |          |           |                  |
| Cold milling/planning; 40mm thick; existing carriageway                                                                                               | 33,994 | m <sup>2</sup> | 2.00     | 67,989    |                  |
| <b>SERIES 1100: KERBS, FOOTWAYS AMD PAVED AREAS</b>                                                                                                   |        |                |          |           | <b>3,565,126</b> |
| <u>Slipform Guided Bus Route</u>                                                                                                                      |        |                |          |           |                  |
| Steel Reinforcement supply and fit for bus route                                                                                                      | 249    | t              | 1,127.46 | 281,194   |                  |
| Slip forming the mainline route. Excluding post grinding                                                                                              | 4,157  | m              | 409.99   | 1,704,203 |                  |
| Precision post grinding to achieve suitable gauge tolerance                                                                                           | 4,157  | m              | 128.12   | 532,564   |                  |
| Precision post grinding to achieve suitable gauge tolerance                                                                                           | 90     | m              | 128.12   | 11,531    |                  |
| In situ works for car traps/entry and exit splays                                                                                                     | 144    | m              | 1,024.96 | 147,595   |                  |
| <u>Kerbs, Channels, Edgings, Combined Drainage and Kerb Blocks</u>                                                                                    |        |                |          |           |                  |
| Precast concrete kerb; half battered (HB2 125 x 255 x 915mm) laid straight or curved                                                                  | 5,058  | m              | 20.19    | 102,126   |                  |
| Precast concrete edgings; Laid straight or curved to radius exceeding 12m; 50mm x 150mm                                                               | 6,565  | m              | 13.72    | 90,074    |                  |
| <u>Footways and Paved Areas</u>                                                                                                                       |        |                |          |           |                  |
| Footpath type 1; comprising Type 1 granular material sub-base 150mm thick; AC20 DBM binder course 40/60 40mm thick; AC6 DBM surface course 20mm thick | 19,695 | m <sup>2</sup> | 35.33    | 695,840   |                  |
| <b>SERIES 1200: TRAFFIC SIGNS AND ROAD MARKINGS</b>                                                                                                   |        |                |          |           | <b>83,920</b>    |

|                                                                                                                                                                                            |        |        |           |                   |                   |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|--------|-----------|-------------------|-------------------|
| <b>Traffic Signs</b>                                                                                                                                                                       |        |        |           |                   |                   |
| Signs - allowance                                                                                                                                                                          | 1      | item   | 5,000.00  | 5,000             |                   |
| <b>Road Markings</b>                                                                                                                                                                       |        |        |           |                   |                   |
| Road marking - allowance: to include ped crossings/adjoining roads/maintenance bays, traffic calming measures etc                                                                          | 12     | shifts | 1,000.00  | 12,000            |                   |
| <b>Traffic Lights</b>                                                                                                                                                                      |        |        |           |                   |                   |
| Traffic signal installation; including; traffic signal head, 4m swan neck pole, NAL socket, pedestrian push button, pedestrian signal indicator, infrared detector, traffic detection loop | 10     | nr     | 5,332.00  | 53,320            |                   |
| Traffic signal installation; controller cabinet                                                                                                                                            | 4      | nr     | 3,400.00  | 13,600            |                   |
| <b>SERIES 1300: ROAD LIGHTING COLUMNS AND BRACKETS, CCTV MASTS AND CANTILEVER MASTS</b>                                                                                                    |        |        |           |                   | <b>386,029</b>    |
| <b>Busway</b>                                                                                                                                                                              |        |        |           |                   |                   |
| 8m mounting height tubular galvanised steel column complete with a post top mounted Philips Luma 3 (BGP627 DS50 - 40km neutral white LED) mounted at 0° tilt - Allowance @ 20m centres     | 104    | nr     | 1,671.12  | 173,796           |                   |
| <b>Dual carriageway</b>                                                                                                                                                                    |        |        |           |                   |                   |
| 8m mounting height tubular galvanised steel column complete with a post top mounted Philips Luma 3 (BGP627 DS50 - 40km neutral white LED) mounted at 0° tilt - Allowance @ 20m centres     | 127    | nr     | 1,671.12  | 212,232           |                   |
| <b>SERIES 1400: ELECTRICAL WORK FOR ROAD LIGHTING AND TRAFFIC SIGNS</b>                                                                                                                    |        |        |           |                   | <b>724,311</b>    |
| <b>Busway</b>                                                                                                                                                                              |        |        |           |                   |                   |
| Street lighting duct; 1 way x 100mm diameter duct route in verge; not exceeding 1m deep to invert                                                                                          | 2,078  | m      | 27.52     | 57,197            |                   |
| Cabling 3 core XLPE/SWA/PVC- Allowance                                                                                                                                                     | 3,742  | m      | 33.14     | 124,022           |                   |
| Terminations at each column- Allowance                                                                                                                                                     | 104    | Item   | 86.83     | 9,030             |                   |
| Tofco feeder pillar (medium), including DNO connection within 2m of LV main                                                                                                                | 6      | nr     | 3,382.51  | 20,295            |                   |
| Telensa CMS node - Allowance                                                                                                                                                               | 104    | nr     | 153.22    | 15,935            |                   |
| New DNO Connections - Allowance                                                                                                                                                            | 6      | nr     | 15,000.00 | 90,000            |                   |
| DNO connection within 2m of lv main (into feeder pillar) - Allowance                                                                                                                       | 2      | nr     | 356.45    | 713               |                   |
| Street lighting chambers 450 x 450 x 900 (allow 1 per 100m)                                                                                                                                | 21     | nr     | 575.75    | 12,091            |                   |
| <b>Dual carriageway</b>                                                                                                                                                                    |        |        |           |                   |                   |
| Street lighting duct; 1 way x 100mm diameter duct route in verge; not exceeding 1m deep to invert                                                                                          | 2,529  | m      | 27.52     | 69,602            |                   |
| Cabling 3 core XLPE/SWA/PVC- Allowance                                                                                                                                                     | 4,561  | m      | 33.14     | 151,156           |                   |
| Terminations at each column- Allowance                                                                                                                                                     | 127    | Item   | 86.83     | 11,027            |                   |
| Tofco feeder pillar (medium), including DNO connection within 2m of LV main                                                                                                                | 7      | nr     | 3,382.51  | 23,678            |                   |
| Telensa CMS node - Allowance                                                                                                                                                               | 127    | nr     | 153.22    | 19,459            |                   |
| New DNO Connections - Allowance                                                                                                                                                            | 7      | nr     | 15,000.00 | 105,000           |                   |
| DNO connection within 2m of lv main (into feeder pillar) - Allowance                                                                                                                       | 2      | nr     | 356.45    | 713               |                   |
| Street lighting chambers 450 x 450 x 900 (allow 1 per 100m)                                                                                                                                | 25     | nr     | 575.75    | 14,394            |                   |
| <b>SERIES 1700: STRUCTURAL CONCRETE</b>                                                                                                                                                    |        |        |           |                   | -                 |
| Batching plant                                                                                                                                                                             | 1      | item   |           | -                 |                   |
| <b>SERIES 2500: SPECIAL STRUCTURES</b>                                                                                                                                                     |        |        |           |                   | <b>307,400</b>    |
| Bus stops (25m in length), including fittings                                                                                                                                              | 4      | nr     | 41,850.00 | 167,400           |                   |
| Ticket Machines - Allowance                                                                                                                                                                | 4      | nr     | 35,000.00 | 140,000           |                   |
| <b>SERIES 3000: LANDSCAPING AND ECOLOGY</b>                                                                                                                                                |        |        |           |                   | <b>1,246,807</b>  |
| Landscaping                                                                                                                                                                                | 61,570 | m²     | 20.00     | 1,231,393         |                   |
| Planting normal sized shrubs (3L pots) and trees                                                                                                                                           | 24     | m²     | 20.00     | 485               |                   |
| Meadow planting (90% wildflower, 10% area to include tress)                                                                                                                                | 18,525 | m²     | 0.81      | 14,929            |                   |
| <b>Total</b>                                                                                                                                                                               |        |        |           | <b>11,120,172</b> | <b>11,120,172</b> |

|                                                                                                                                                       |        |                |              |                |                |
|-------------------------------------------------------------------------------------------------------------------------------------------------------|--------|----------------|--------------|----------------|----------------|
| <b>30% SURFACING RENEWALS</b>                                                                                                                         |        |                |              |                |                |
| <b>SERIES 200: SITE CLEARANCE</b>                                                                                                                     |        |                |              |                | <b>24,726</b>  |
| General Site Clearance                                                                                                                                | 11,447 | m <sup>2</sup> | 2.16         | 24,726         |                |
| <b>SERIES 600: EARTHWORKS</b>                                                                                                                         |        |                |              |                | <b>144,691</b> |
| <u>Excavation</u>                                                                                                                                     |        |                |              |                |                |
| Excavation of artificial hard material; Carriageway                                                                                                   | 1,496  | m <sup>3</sup> | 11.52        | 17,228         |                |
| Excavation of artificial hard material; Footpaths                                                                                                     | 1,241  | m <sup>3</sup> | 11.52        | 14,294         |                |
| Extra over for breaking out surfacing                                                                                                                 | 2,736  | m <sup>3</sup> | 9.74         | 26,651         |                |
| <u>Disposal of Material</u>                                                                                                                           |        |                |              |                |                |
| Disposal of acceptable material excluding Class 5A                                                                                                    | 2,736  | m <sup>3</sup> | 28.23        | 77,245         |                |
| <u>Completion of Formation and Sub-formation</u>                                                                                                      |        |                |              |                |                |
| Completion of sub-formation on acceptable material                                                                                                    | 11,447 | m <sup>2</sup> | 0.81         | 9,272          |                |
| <b>SERIES 700: PAVEMENTS</b>                                                                                                                          |        |                |              |                | <b>262,095</b> |
| <b>Pavement; Car Park</b>                                                                                                                             |        |                |              |                |                |
| <u>Sub-base</u>                                                                                                                                       |        |                |              |                |                |
| Imported granular sub-base; Type 1 aggregate; 20mm depth car park (top up)                                                                            | 229    | m <sup>2</sup> | 0.99         | 226            |                |
| <u>Pavement</u>                                                                                                                                       |        |                |              |                |                |
| AC32 HDM base 40/60 Rec 150mm thick                                                                                                                   | 5,539  | m <sup>2</sup> | 25.44        | 140,907        |                |
| AC20 Dense binder course 40/60 Rec 60mm thick in carriageway and car park                                                                             | 5,539  | m <sup>2</sup> | 10.72        | 59,396         |                |
| 40mm Thin Surface course system                                                                                                                       | 5,539  | m <sup>2</sup> | 11.12        | 61,566         |                |
| <b>SERIES 1100: KERBS, FOOTWAYS AMD PAVED AREAS</b>                                                                                                   |        |                |              |                | <b>208,752</b> |
| <u>Footways and Paved Areas</u>                                                                                                                       |        |                |              |                |                |
| Footpath type 1; comprising Type 1 granular material sub-base 150mm thick; AC20 DBM binder course 40/60 40mm thick; AC6 DBM surface course 20mm thick | 5,909  | m <sup>2</sup> | 35.33        | 208,752        |                |
| <b>SERIES 1200: TRAFFIC SIGNS AND ROAD MARKINGS</b>                                                                                                   |        |                |              |                | <b>4,000</b>   |
| <u>Road Markings</u>                                                                                                                                  |        |                |              |                |                |
| Road Marking                                                                                                                                          | 4      | shifts         | 1000.00      | 4,000          |                |
|                                                                                                                                                       |        |                | <b>Total</b> | <b>644,264</b> |                |

| 100% ROAD RESURFACE                                 |        |        |         |                  |                |
|-----------------------------------------------------|--------|--------|---------|------------------|----------------|
| <b>SERIES 200: SITE CLEARANCE</b>                   |        |        |         |                  | <b>155,849</b> |
| General Site Clearance                              | 72,152 | m²     | 2.16    | 155,849          |                |
| <b>SERIES 700: PAVEMENTS</b>                        |        |        |         |                  | <b>982,384</b> |
| <b>Cold Milling</b>                                 |        |        |         |                  |                |
| Cold milling/planning; 40mm thick                   | 72,152 | m²     | 2.00    | 144,305          |                |
| <b>Pavement; Car Park</b>                           |        |        |         |                  |                |
| <u>Pavement</u>                                     |        |        |         |                  |                |
| Tack coat                                           | 72,152 | m²     | 0.50    | 36,076           |                |
| 40mm Thin Surface course system                     | 72,152 | m²     | 11.12   | 802,003          |                |
| <b>SERIES 1200: TRAFFIC SIGNS AND ROAD MARKINGS</b> |        |        |         |                  | <b>12,000</b>  |
| <u>Road Markings</u>                                |        |        |         |                  |                |
| Road Marking                                        | 12     | shifts | 1000.00 | 12,000           |                |
| <b>Total</b>                                        |        |        |         | <b>1,150,234</b> |                |

## 8 Option 3

## Cambridge to Cambourne

## Phase 2 Option 3

| Item                                                                                                                                                                  | Qty    | Unit | Unit rate<br>£ | Total<br>£ | Subtotal<br>£    |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------|----------------|------------|------------------|
| <b>INITIAL CONSTRUCTION</b>                                                                                                                                           |        |      |                |            |                  |
| <b>SERIES 200: SITE CLEARANCE</b>                                                                                                                                     |        |      |                |            | <b>326,768</b>   |
| General Site Clearance                                                                                                                                                | 85,779 | m²   | 2.16           | 185,283    |                  |
| Take up PCC Kerb and dispose of off site                                                                                                                              | 6,159  | m    | 9.42           | 58,020     |                  |
| Take up and remove from site; 8m mounting height tubular galvanised steel column complete with a post top mounted luminaire                                           | 308    | nr   | 270.99         | 83,465     |                  |
| <b>SERIES 500: DRAINAGE AND SERVICE DUCTS</b>                                                                                                                         |        |      |                |            | <b>2,725,333</b> |
| <u>Busway</u>                                                                                                                                                         |        |      |                |            |                  |
| Precast concrete trapped gully with Class D400 grating and frame; 450mm x 750mm                                                                                       | 208    | nr   | 491.64         | 102,181    |                  |
| 150mm diameter carrier drain with type S bed and surround; depth to invert not exceeding 2m                                                                           | 686    | m    | 47.72          | 32,729     |                  |
| 225mm diameter carrier drain with type S bed and surround; depth to invert 2m - 2.5m                                                                                  | 4,572  | m    | 84.11          | 384,586    |                  |
| Connections to existing drainage/outfalls; 225mm dia; depth to invert exceeding 2m but not exceeding 4m                                                               | 4      | nr   | 277.32         | 1,109      |                  |
| Manhole; Depth : not exceeding 1.5 m; Type 2A (1.5m internal diameter) complete with allowance for concrete butt and rocker pipes                                     | 49     | nr   | 3,084.61       | 150,846    |                  |
| Drainage interceptor - Allowance of 1 per 1000m of drainage                                                                                                           | 4      | nr   | 10,000.00      | 40,000     |                  |
| Outfalls - Allowance of 1 per 1000m of drainage                                                                                                                       | 4      | nr   | 10,000.00      | 40,000     |                  |
| <u>Dual Carriageway</u>                                                                                                                                               |        |      |                |            |                  |
| 225mm diameter carrier drain with type S bed and surround; depth to invert 2m - 2.5m                                                                                  | 11,394 | m    | 84.11          | 958,342    |                  |
| Connections to existing drainage/outfalls; 225mm dia; depth to invert exceeding 2m but not exceeding 4m                                                               | 14     | nr   | 277.32         | 3,882      |                  |
| Precast concrete trapped gully with Class D400 grating and frame; 450mm x 750mm                                                                                       | 570    | nr   | 491.64         | 280,235    |                  |
| Manhole; Depth : not exceeding 1.5 m; Type 2A (1.5m internal diameter) complete with allowance for concrete butt and rocker pipes                                     | 135    | nr   | 3084.61        | 416,422    |                  |
| Drainage interceptor - Allowance of 1 per 1000m of drainage                                                                                                           | 12     | nr   | 10,000.00      | 120,000    |                  |
| Outfalls - Allowance of 1 per 1000m of drainage                                                                                                                       | 12     | nr   | 10,000.00      | 120,000    |                  |
| Culverts - Allowance                                                                                                                                                  | 3      | nr   | 25,000.00      | 75,000     |                  |
| <b>SERIES 600: EARTHWORKS</b>                                                                                                                                         |        |      |                |            | <b>2,352,567</b> |
| <u>Excavation of Topsoil</u>                                                                                                                                          |        |      |                |            |                  |
| Excavation of acceptable material Class 5A Topsoil 150mm                                                                                                              | 12,867 | m³   | 5.61           | 72,183     |                  |
| <u>General Excavation</u>                                                                                                                                             |        |      |                |            |                  |
| Excavation to busway subformation; Excavation of acceptable material normal material, excluding hard or artificially hard material, excluding Class 5A; > 2500m³      | 12,138 | m³   | 1.49           | 18,085     |                  |
| Excavation to bus stop subformation; Excavation of acceptable material; excluding Class 5A; normal material, excluding hard or artificially hard material, <2500m³    | 342    | m³   | 2.54           | 869        |                  |
| Excavation to carriageway subformation; Excavation of acceptable material normal material, excluding hard or artificially hard material, excluding Class 5A; > 2500m³ | 25,369 | m³   | 1.49           | 37,799     |                  |
| Excavation to attenuation pond; Excavation of acceptable material normal material, excluding hard or artificially hard material, excluding Class 5A; > 2500m³         | 6,260  | m³   | 1.49           | 9,328      |                  |
| Extra over for breaking out surfacing                                                                                                                                 | 8,499  | m³   | 9.74           | 82,776     |                  |
| <u>Imported Fill</u>                                                                                                                                                  |        |      |                |            |                  |
| Imported acceptable material; Capping material; Class 6F2; for carriageway, 240mm thk                                                                                 | 9,981  | m³   | 40.64          | 405,630    |                  |
| <u>Compaction of Material</u>                                                                                                                                         |        |      |                |            |                  |
| Compaction of fill material to large areas                                                                                                                            | 9,981  | m³   | 3.50           | 34,934     |                  |

|                                                                                                                                                       |        |        |          |           |                  |
|-------------------------------------------------------------------------------------------------------------------------------------------------------|--------|--------|----------|-----------|------------------|
| <u>Disposal of Material</u>                                                                                                                           |        |        |          |           |                  |
| Disposal of acceptable Class 5A topsoil                                                                                                               | 9,334  | m³     | 28.23    | 263,501   |                  |
| Disposal of acceptable material excluding Class 5A                                                                                                    | 44,108 | m³     | 28.23    | 1,245,182 |                  |
| <u>Topsoiling and Storage of Topsoil</u>                                                                                                              |        |        |          |           |                  |
| Topsoiling: Class 5A material excavated from site; 150mm thick; Sloping at 10 eg or less to the horizontal, >5000m2 (>750m3)                          | 23,552 | m²     | 1.10     | 25,907    |                  |
| <u>Completion of Formation and Sub-formation</u>                                                                                                      |        |        |          |           |                  |
| Completion of sub-formation on acceptable material; bus stops                                                                                         | 360    | m²     | 1.10     | 396       |                  |
| Completion of sub-formation on acceptable material; bus way                                                                                           | 16,624 | m²     | 1.10     | 18,286    |                  |
| Completion of sub-formation on acceptable material; carriageway                                                                                       | 41,588 | m²     | 1.10     | 45,747    |                  |
| Completion of sub-formation on acceptable material; footpath                                                                                          | 19,681 | m²     | 1.10     | 21,649    |                  |
| <u>Lining of Watercourses</u>                                                                                                                         |        |        |          |           |                  |
| Lining of new watercourse; attenuation pond                                                                                                           | 7,526  | m²     | 9.34     | 70,295    |                  |
| <b>SERIES 700: PAVEMENTS</b>                                                                                                                          |        |        |          |           | <b>3,711,739</b> |
| <u>Sub-Base</u>                                                                                                                                       |        |        |          |           |                  |
| Imported granular sub-base; Type 1 aggregate; 200mm depth; bus way                                                                                    | 16,624 | m²     | 9.46     | 157,263   |                  |
| Imported granular sub-base; Type 1 aggregate; 200mm depth; bus stop                                                                                   | 360    | m²     | 9.46     | 3,406     |                  |
| Imported granular sub-base; Type 1 aggregate; 200mm depth; carriageway                                                                                | 41,588 | m²     | 9.46     | 393,422   |                  |
| <u>Dual carriageway</u>                                                                                                                               |        |        |          |           |                  |
| AC32 HDM base 40/60 Rec 150mm thick in carriageway                                                                                                    | 41,588 | m²     | 25.44    | 1,057,993 |                  |
| AC20 Dense binder course 40/60 Rec 60mm thick in carriageway                                                                                          | 41,588 | m²     | 10.72    | 445,970   |                  |
| 40mm Thin Surface course system                                                                                                                       | 19,107 | m²     | 11.12    | 212,382   |                  |
| Master tint- Red surface course (40mm)- bus lane                                                                                                      | 22,481 | m²     | 44.75    | 1,005,992 |                  |
| Resurfacing: 40mm Thin Surface course system                                                                                                          | 33,179 | m²     | 11.12    | 368,952   |                  |
| <u>Cold Milling</u>                                                                                                                                   |        |        |          |           |                  |
| Cold milling/planning; 40mm thick; existing carriageway; including disposal                                                                           | 33,179 | m²     | 2.00     | 66,358    |                  |
| <b>SERIES 1100: KERBS, FOOTWAYS AMD PAVED AREAS</b>                                                                                                   |        |        |          |           | <b>3,692,451</b> |
| <b>Slipform Guided Bus Route</b>                                                                                                                      |        |        |          |           |                  |
| Steel Reinforcement supply and fit for bus route                                                                                                      | 249    | t      | 1,127.46 | 281,194   |                  |
| Slip forming the mainline route. Excluding post grinding                                                                                              | 4,157  | m      | 409.99   | 1,704,203 |                  |
| Precision post grinding to achieve suitable gauge tolerance                                                                                           | 4,157  | m      | 128.12   | 532,564   |                  |
| Precision post grinding to achieve suitable gauge tolerance                                                                                           | 90     | m      | 128.12   | 11,531    |                  |
| In situ works for car traps/entry and exit splays                                                                                                     | 144    | m      | 1,024.96 | 147,595   |                  |
| <u>Kerbs, Channels, Edgings, Combined Drainage and Kerb Blocks</u>                                                                                    |        |        |          |           |                  |
| Precast concrete kerb; half battered (HB2 125 x 255 x 915mm) laid straight or curved                                                                  | 11,394 | m      | 20.19    | 230,043   |                  |
| Precast concrete edgings; Laid straight or curved to radius exceeding 12m; 50mm x 150mm                                                               | 6,560  | m      | 13.72    | 90,006    |                  |
| <u>Footways and Paved Areas</u>                                                                                                                       |        |        |          |           |                  |
| Footpath type 1; comprising Type 1 granular material sub-base 150mm thick; AC20 DBM binder course 40/60 40mm thick; AC6 DBM surface course 20mm thick | 19,681 | m²     | 35.33    | 695,316   |                  |
| <b>SERIES 1200: TRAFFIC SIGNS AND ROAD MARKINGS</b>                                                                                                   |        |        |          |           | <b>113,584</b>   |
| <u>Traffic Signs</u>                                                                                                                                  |        |        |          |           |                  |
| Signs - allowance                                                                                                                                     | 1      | nr     | 5,000.00 | 5,000     |                  |
| <u>Road Markings</u>                                                                                                                                  |        |        |          |           |                  |
| Road marking - allowance: to include ped crossings/adjoining roads/maintenance bays, traffic calming measures etc                                     | 31     | shifts | 1,000.00 | 31,000    |                  |

|                                                                                                                                                                                            |        |      |           |         |                  |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------|-----------|---------|------------------|
| <u>Traffic Lights</u>                                                                                                                                                                      |        |      |           |         |                  |
| Traffic signal installation; including; traffic signal head, 4m swan neck pole, NAL socket, pedestrian push button, pedestrian signal indicator, infrared detector, traffic detection loop | 12     | nr   | 5,332.00  | 63,984  |                  |
| Traffic signal installation; controller cabinet                                                                                                                                            | 4      | nr   | 3,400.00  | 13,600  |                  |
| <b>SERIES 1300: ROAD LIGHTING COLUMNS AND BRACKETS, CCTV MASTS AND CANTILEVER MASTS</b>                                                                                                    |        |      |           |         | <b>907,418</b>   |
| <u>Busway</u>                                                                                                                                                                              |        |      |           |         |                  |
| 8m mounting height tubular galvanised steel column complete with a post top mounted Philips Luma 3 (BGP627 DS50 - 40km neutral white LED) mounted at 0° tilt - Allowance @ 20m centres     | 104    | nr   | 1,671.12  | 173,796 |                  |
| <u>Dual carriageway</u>                                                                                                                                                                    |        |      |           |         |                  |
| 8m mounting height tubular galvanised steel column complete with a post top mounted Philips Luma 3 (BGP627 DS50 - 40km neutral white LED) mounted at 0° tilt - Allowance @ 20m centres     | 439    | nr   | 1,671.12  | 733,622 |                  |
| <b>SERIES 1400: ELECTRICAL WORK FOR ROAD LIGHTING AND TRAFFIC SIGNS</b>                                                                                                                    |        |      |           |         | <b>1,590,368</b> |
| <u>Busway</u>                                                                                                                                                                              |        |      |           |         |                  |
| Street lighting duct; 1 way x 100mm diameter duct route in verge; not exceeding 1m deep to invert                                                                                          | 2,080  | m    | 27.52     | 57,242  |                  |
| Cabling 3 core XLPE/SWA/PVC- Allowance                                                                                                                                                     | 3,744  | m    | 33.14     | 124,076 |                  |
| Terminations at each column- Allowance                                                                                                                                                     | 104    | nr   | 86.83     | 9,030   |                  |
| Tofco feeder pillar (medium), including DNO connection within 2m of LV main                                                                                                                | 6      | nr   | 3,382.51  | 20,295  |                  |
| Telensa CMS node - Allowance                                                                                                                                                               | 104    | nr   | 153.22    | 15,935  |                  |
| New DNO Connections - Allowance                                                                                                                                                            | 6      | nr   | 15,000.00 | 90,000  |                  |
| DNO connection within 2m of lv main (into feeder pillar) - Allowance                                                                                                                       | 2      | nr   | 356.45    | 713     |                  |
| Street lighting chambers 450 x 450 x 900 (allow 1 per 100m)                                                                                                                                | 21     | nr   | 575.75    | 12,091  |                  |
| <u>Dual carriageway</u>                                                                                                                                                                    |        |      |           |         |                  |
| Street lighting duct; 1 way x 100mm diameter duct route in verge; not exceeding 1m deep to invert                                                                                          | 7,777  | m    | 27.52     | 214,010 |                  |
| Cabling 3 core XLPE/SWA/PVC- Allowance                                                                                                                                                     | 14,801 | m    | 33.14     | 490,489 |                  |
| Terminations at each column- Allowance                                                                                                                                                     | 439    | Item | 86.83     | 38,118  |                  |
| Tofco feeder pillar (medium), including DNO connection within 2m of LV main                                                                                                                | 22     | nr   | 3,382.51  | 74,415  |                  |
| Telensa CMS node - Allowance                                                                                                                                                               | 439    | nr   | 153.22    | 67,264  |                  |
| New DNO Connections - Allowance                                                                                                                                                            | 22     | nr   | 15,000.00 | 330,000 |                  |
| DNO connection within 2m of lv main (into feeder pillar) - Allowance                                                                                                                       | 5      | nr   | 356.45    | 1,782   |                  |
| Street lighting chambers 450 x 450 x 900 (allow 1 per 100m)                                                                                                                                | 78     | nr   | 575.75    | 44,909  |                  |
| <b>SERIES 1700: STRUCTURAL CONCRETE</b>                                                                                                                                                    |        |      |           |         | <b>-</b>         |
| Batching plant                                                                                                                                                                             | 1      | item |           | -       |                  |

|                                                     |                                                                                                                                                       |        |        |          |                   |
|-----------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------|--------|--------|----------|-------------------|
| <b>SERIES 2500: SPECIAL STRUCTURES</b>              |                                                                                                                                                       |        |        |          | <b>307,400</b>    |
|                                                     | Bus stops (25m in length), including fittings                                                                                                         | 4      | nr     | 41850.00 | 167,400           |
|                                                     | Ticket Machines - Allowance                                                                                                                           | 4      | nr     | 35000.00 | 140,000           |
| <b>SERIES 3000: LANDSCAPING AND ECOLOGY</b>         |                                                                                                                                                       |        |        |          | <b>1,825,944</b>  |
|                                                     | Landscaping                                                                                                                                           | 88,862 | m²     | 20.00    | 1,777,234         |
|                                                     | 1.2m high clipped hedgerow (along the busway)                                                                                                         | 1,084  | m      | 15.55    | 16,856            |
|                                                     | Planting normal sized shrubs (3L pots) and trees                                                                                                      | 492    | m²     | 20.00    | 9,840             |
|                                                     | Meadow planting (90% wildflower, 10% area to include tress)                                                                                           | 17,794 | m²     | 0.81     | 14,340            |
|                                                     | Extension to plantation woodland                                                                                                                      | 5,758  | m²     | 1.33     | 7,674             |
|                                                     | <b>Total</b>                                                                                                                                          |        |        |          | <b>17,553,571</b> |
|                                                     |                                                                                                                                                       |        |        |          | <b>17,553,571</b> |
| <b>30% SURFACING RENEWALS</b>                       |                                                                                                                                                       |        |        |          |                   |
| <b>SERIES 200: SITE CLEARANCE</b>                   |                                                                                                                                                       |        |        |          | <b>50,708</b>     |
|                                                     | General Site Clearance                                                                                                                                | 23,476 | m²     | 2.16     | 50,708            |
| <b>SERIES 600: EARTHWORKS</b>                       |                                                                                                                                                       |        |        |          | <b>242,965</b>    |
|                                                     | <u>Excavation</u>                                                                                                                                     |        |        |          |                   |
|                                                     | Excavation of artificial hard material; Carriageway                                                                                                   | 3,369  | m³     | 11.52    | 38,807            |
|                                                     | Excavation of artificial hard material; Footpaths                                                                                                     | 1,240  | m³     | 11.52    | 14,284            |
|                                                     | Extra over for breaking out surfacing                                                                                                                 | 4,609  | m³     | 9.74     | 44,887            |
|                                                     | <u>Disposal of Material</u>                                                                                                                           |        |        |          |                   |
|                                                     | Disposal of acceptable material excluding Class 5A                                                                                                    | 4,609  | m³     | 28.23    | 130,099           |
|                                                     | <u>Completion of Formation and Sub-formation</u>                                                                                                      |        |        |          |                   |
|                                                     | Completion of sub-formation on acceptable material                                                                                                    | 18,381 | m²     | 0.81     | 14,888            |
| <b>SERIES 700: PAVEMENTS</b>                        |                                                                                                                                                       |        |        |          | <b>590,231</b>    |
|                                                     | <b>Pavement; Car Park</b>                                                                                                                             |        |        |          |                   |
|                                                     | <u>Sub-base</u>                                                                                                                                       |        |        |          |                   |
|                                                     | Imported granular sub-base; Type 1 aggregate; 20mm depth car park (top up)                                                                            | 368    | m²     | 0.99     | 363               |
|                                                     | <u>Pavement</u>                                                                                                                                       |        |        |          |                   |
|                                                     | AC32 HDM base 40/60 Rec 150mm thick                                                                                                                   | 12,476 | m²     | 25.44    | 317,398           |
|                                                     | AC20 Dense binder course 40/60 Rec 60mm thick in carriageway and car park                                                                             | 12,476 | m²     | 10.72    | 133,791           |
|                                                     | 40mm Thin Surface course system                                                                                                                       | 12,476 | m²     | 11.12    | 138,680           |
| <b>SERIES 1100: KERBS, FOOTWAYS AMD PAVED AREAS</b> |                                                                                                                                                       |        |        |          | <b>208,595</b>    |
|                                                     | <u>Footways and Paved Areas</u>                                                                                                                       |        |        |          |                   |
|                                                     | Footpath type 1; comprising Type 1 granular material sub-base 150mm thick; AC20 DBM binder course 40/60 40mm thick; AC6 DBM surface course 20mm thick | 5,904  | m²     | 35.33    | 208,595           |
| <b>SERIES 1200: TRAFFIC SIGNS AND ROAD MARKINGS</b> |                                                                                                                                                       |        |        |          | <b>10,000</b>     |
|                                                     | <u>Road Markings</u>                                                                                                                                  |        |        |          |                   |
|                                                     | Road Marking                                                                                                                                          | 10     | shifts | 1000.00  | 10,000            |
|                                                     | <b>Total</b>                                                                                                                                          |        |        |          | <b>1,102,498</b>  |

| <b>100% ROAD RESURFACE</b>                          |        |                |         |                  |                |
|-----------------------------------------------------|--------|----------------|---------|------------------|----------------|
| <b>SERIES 200: SITE CLEARANCE</b>                   |        |                |         |                  |                |
| General Site Clearance                              | 71,967 | m <sup>2</sup> | 2.16    | 155,448          | <b>155,448</b> |
| <b>SERIES 700: PAVEMENTS</b>                        |        |                |         |                  |                |
| <b>Cold Milling</b>                                 |        |                |         |                  |                |
| Cold milling/planning; 40mm thick                   | 71,967 | m <sup>2</sup> | 2.00    | 143,934          | <b>979,857</b> |
| <b>Pavement; Car Park</b>                           |        |                |         |                  |                |
| <u>Pavement</u>                                     |        |                |         |                  |                |
| Tack coat                                           | 71,967 | m <sup>2</sup> | 0.50    | 35,983           |                |
| 40mm Thin Surface course system                     | 71,967 | m <sup>2</sup> | 11.12   | 799,940          |                |
| <b>SERIES 1200: TRAFFIC SIGNS AND ROAD MARKINGS</b> |        |                |         |                  |                |
| <u>Road Markings</u>                                |        |                |         |                  |                |
| Road Marking                                        | 31     | shifts         | 1000.00 | 31,000           | <b>31,000</b>  |
| <b>Total</b>                                        |        |                |         | <b>1,166,306</b> |                |

## 9 Waterworks P&R

## Cambridge to Cambourne

## Waterworks P &amp; R

| Item                                                                                                                                                          | Qty    | Unit           | Unit rate<br>£ | Total<br>£ | Subtotal<br>£    |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|----------------|----------------|------------|------------------|
| <b>INITIAL CONSTRUCTION</b>                                                                                                                                   |        |                |                |            |                  |
| <b>SERIES 200: SITE CLEARANCE</b>                                                                                                                             |        |                |                |            | <b>137,685</b>   |
| General Site Clearance                                                                                                                                        | 63,743 | m <sup>2</sup> | 2.16           | 137,685    |                  |
| <b>SERIES 300: FENCING</b>                                                                                                                                    |        |                |                |            | <b>28,385</b>    |
| Close boarded fencing, 1.8m high, 125mm x 125mm concrete post, set in concrete foundation; painted                                                            | 894    | m              | 31.75          | 28,385     |                  |
| <b>SERIES 500: DRAINAGE AND SERVICE DUCTS</b>                                                                                                                 |        |                |                |            | <b>1,100,100</b> |
| 225mm diameter carrier drain with type S bed and surround; depth to invert 2m - 2.5m                                                                          | 5,100  | m              | 84.11          | 428,961    |                  |
| Connections to existing drainage/outfalls; 225mm dia; depth to invert exceeding 2m but not exceeding 4m                                                       | 5      | nr             | 277.32         | 1,387      |                  |
| Precast concrete trapped gully with Class D400 grating and frame; 450mm x 750mm                                                                               | 255    | nr             | 491.64         | 125,368    |                  |
| Manhole; Depth : not exceeding 1.5 m; Type 2A (1.5m internal diameter) complete with allowance for concrete butt and rocker pipes                             | 170    | nr             | 3,084.61       | 524,384    |                  |
| Drainage interceptor - Allowance                                                                                                                              | 1      | nr             | 10,000.00      | 10,000     |                  |
| Outfalls - Allowance                                                                                                                                          | 1      | nr             | 10,000.00      | 10,000     |                  |
| <b>SERIES 600: EARTHWORKS</b>                                                                                                                                 |        |                |                |            | <b>1,769,100</b> |
| <u>Excavation of Topsoil</u>                                                                                                                                  |        |                |                |            |                  |
| Excavation of acceptable material Class 5A Topsoil 150mm                                                                                                      | 9,561  | m <sup>3</sup> | 5.61           | 53,640     |                  |
| <u>General Excavation</u>                                                                                                                                     |        |                |                |            |                  |
| Excavation to sub-formation; Excavation of acceptable material normal material, excluding hard or artificially hard material, excluding Class 5A; > 2500m3    | 21,751 | m <sup>3</sup> | 1.49           | 32,409     |                  |
| Excavation to attenuation pond; Excavation of acceptable material normal material, excluding hard or artificially hard material, excluding Class 5A; > 2500m3 | 4,641  | m <sup>3</sup> | 1.49           | 6,915      |                  |
| <u>Deposition of Material</u>                                                                                                                                 |        |                |                |            |                  |
| Traffic island and Verge; Deposition of acceptable material; excluding Class 5A; normal material, excluding hard or artificially hard material, <2500m3       | 3,111  | m <sup>3</sup> | 6.03           | 18,759     |                  |
| <u>Imported Fill</u>                                                                                                                                          |        |                |                |            |                  |
| Imported acceptable material; Capping material; Class 6F2; for carriageway, 240mm thk                                                                         | 15,081 | m <sup>3</sup> | 40.64          | 612,904    |                  |
| <u>Disposal of Material</u>                                                                                                                                   |        |                |                |            |                  |
| Disposal of acceptable Class 5A topsoil                                                                                                                       | 9,561  | m <sup>3</sup> | 28.23          | 269,920    |                  |
| Disposal of acceptable material excluding Class 5A                                                                                                            | 23,281 | m <sup>3</sup> | 28.23          | 657,214    |                  |
| <u>Completion of Formation and Sub-formation</u>                                                                                                              |        |                |                |            |                  |
| Completion of sub-formation on acceptable material; carriageway                                                                                               | 50,271 | m <sup>2</sup> | 1.10           | 55,298     |                  |
| Completion of sub-formation on acceptable material; footpath                                                                                                  | 7,741  | m <sup>2</sup> | 1.10           | 8,515      |                  |
| <u>Lining of Watercourses</u>                                                                                                                                 |        |                |                |            |                  |
| Lining of new watercourse; attenuation pond                                                                                                                   | 5,731  | m <sup>2</sup> | 9.34           | 53,527     |                  |
| <b>SERIES 700: PAVEMENTS</b>                                                                                                                                  |        |                |                |            | <b>2,872,435</b> |
| <b>Pavement; Car Park</b>                                                                                                                                     |        |                |                |            |                  |
| <u>Sub-Base</u>                                                                                                                                               |        |                |                |            |                  |
| Imported granular sub-base; Type 1 aggregate; 200mm depth                                                                                                     | 50,271 | m <sup>3</sup> | 9.86           | 495,672    |                  |
| <u>Pavement</u>                                                                                                                                               |        |                |                |            |                  |
| AC32 HDM base 40/60 Rec 150mm thick                                                                                                                           | 50,271 | m <sup>2</sup> | 25.44          | 1,278,894  |                  |
| AC20 Dense binder course 40/60 Rec 60mm thick                                                                                                                 | 50,271 | m <sup>2</sup> | 10.72          | 539,086    |                  |
| 40mm Thin Surface course system                                                                                                                               | 50,271 | m <sup>2</sup> | 11.12          | 558,783    |                  |

## Cambridge to Cambourne

## Waterworks P &amp; R

| Item                                                                                                                                                  | Qty   | Unit           | Unit rate<br>£ | Total<br>£ | Subtotal<br>£  |
|-------------------------------------------------------------------------------------------------------------------------------------------------------|-------|----------------|----------------|------------|----------------|
| <b>SERIES 1100: KERBS, FOOTWAYS AND PAVED AREAS</b>                                                                                                   |       |                |                |            | <b>434,417</b> |
| <u>Kerbs, Channels, Edgings, Combined Drainage and Kerb Blocks</u>                                                                                    |       |                |                |            |                |
| Precast concrete kerb; half battered (HB2 125 x 255 x 915mm) laid straight or curved                                                                  | 5,633 | m              | 20.19          | 113,730    |                |
| Precast concrete edgings; Laid straight or curved to radius exceeding 12m; 50mm x 150mm                                                               | 3,440 | m              | 13.72          | 47,197     |                |
| <u>Footways and Paved Areas</u>                                                                                                                       |       |                |                |            |                |
| Footpath type 1; comprising Type 1 granular material sub-base 150mm thick; AC20 DBM binder course 40/60 40mm thick; AC6 DBM surface course 20mm thick | 7,741 | m <sup>2</sup> | 35.33          | 273,490    |                |
| <b>SERIES 1200: TRAFFIC SIGNS AND ROAD MARKINGS</b>                                                                                                   |       |                |                |            | <b>6,000</b>   |
| <u>Traffic Signs</u>                                                                                                                                  |       |                |                |            |                |
| Signs - allowance                                                                                                                                     | 1     | nr             | 2,000.00       | 2,000      |                |
| <u>Road Markings</u>                                                                                                                                  |       |                |                |            |                |
| Road Marking                                                                                                                                          | 2     | shifts         | 1,000.00       | 2,000      |                |
| White lining                                                                                                                                          | 2     | shift          | 1,000.00       | 2,000      |                |

## Cambridge to Cambourne

## Waterworks P &amp; R

| Item                                                                                                                                                         | Qty   | Unit | Unit rate<br>£ | Total<br>£       | Subtotal<br>£    |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|----------------|------------------|------------------|
| <b>SERIES 1300: ROAD LIGHTING COLUMNS AND BRACKETS, CCTV MASTS AND CANTILEVER MASTS</b>                                                                      |       |      |                |                  | <b>136,897</b>   |
| 8m mounting height tubular galvanised steel column complete with a post top mounted Philips Luma 3 (BGP627 DS50 - 40km neutral white LED) mounted at 0° tilt | 43    | nr   | 1,671.12       | 71,858           |                  |
| 8m mounting height tubular galvanised steel column complete with a post top mounted Philips Luma 1 (BGP623 DW50 - 15km neutral white LED) mounted at 0° tilt | 6     | nr   | 1,486.63       | 8,920            |                  |
| 8m mounting height tubular galvanised steel column complete with a post top mounted Philips Luma 3 (BGP627 DW10 - 35km neutral white LED) mounted at 0° tilt | 8     | nr   | 1,671.12       | 13,369           |                  |
| <b>CCTV</b>                                                                                                                                                  |       |      |                |                  |                  |
| Cameras to be mounted on Street lighting columns on 25% of SL poles - Allowance                                                                              | 14    | nr   | 3,000.00       | 42,750           |                  |
| <b>SERIES 1400: ELECTRICAL WORK FOR ROAD LIGHTING AND TRAFFIC SIGNS</b>                                                                                      |       |      |                |                  | <b>275,054</b>   |
| Street lighting duct; 1 way x 100mm diameter duct route in verge; not exceeding 1m deep to invert                                                            | 2,500 | m    | 27.52          | 68,800           |                  |
| Cabling 3 core XLPE/SWA/PVC- Allowance                                                                                                                       | 3,355 | m    | 33.14          | 111,185          |                  |
| CCTV communication cabling - Allowance                                                                                                                       | 839   | m    | 10.00          | 8,391            |                  |
| Terminations at each column- Allowance                                                                                                                       | 57    | nr   | 86.83          | 4,949            |                  |
| Tofco feeder pillar (medium), including DNO connection within 2m of LV main                                                                                  | 3     | nr   | 3,382.51       | 10,148           |                  |
| Telensa CMS node - Allowance                                                                                                                                 | 57    | nr   | 153.22         | 8,734            |                  |
| DNO connection within 2m of lv main (into feeder pillar) - Allowance                                                                                         | 3     | nr   | 15,000.00      | 45,000           |                  |
| Street lighting chambers 450 x 450 x 900 (allow 1 per 100m)                                                                                                  | 25    | nr   | 575.75         | 14,394           |                  |
| CCTV chambers 450 x 450 x 900 (allow 1 per 100m)                                                                                                             | 6     | nr   | 575.75         | 3,455            |                  |
| <b>SERIES 2500: SPECIAL STRUCTURES</b>                                                                                                                       |       |      |                |                  | <b>679,321</b>   |
| <b>Park and Ride Building</b>                                                                                                                                |       |      |                |                  |                  |
| Building (assumed 3m height)                                                                                                                                 | 224   | m²   | 2,500.00       | 560,000          |                  |
| Ticket machine @ Park and Ride - Allowance                                                                                                                   | 2     | nr   | 35,000.00      | 70,000           |                  |
| Cycle Parking (Assumed Cycle Shelter - 10 Space Cycle Shelter & Bike Stands)                                                                                 | 21    | item | 635.48         | 13,345           |                  |
| Cycle boxes (Assumed bike away locker)                                                                                                                       | 30    | item | 1,199.21       | 35,976           |                  |
| <b>SERIES 3000: LANDSCAPING AND ECOLOGY</b>                                                                                                                  |       |      |                |                  | <b>37,929</b>    |
| <u>Seeding and Turfing</u>                                                                                                                                   |       |      |                |                  |                  |
| Seeding                                                                                                                                                      | 6,481 | m²   | 0.54           | 3,521            |                  |
| <u>Special Ecological Measures</u>                                                                                                                           |       |      |                |                  |                  |
| Environmental barrier (assumed bare rooted native species whips)                                                                                             | 1,865 | m²   | 18.45          | 34,408           |                  |
| <b>Total</b>                                                                                                                                                 |       |      |                | <b>7,477,321</b> | <b>7,477,321</b> |

## Cambridge to Cambourne

## Waterworks P &amp; R

| Item                                                                                                                                                  | Qty    | Unit           | Unit rate<br>£ | Total<br>£       | Subtotal<br>£  |
|-------------------------------------------------------------------------------------------------------------------------------------------------------|--------|----------------|----------------|------------------|----------------|
| <b>30% SURFACING RENEWALS</b>                                                                                                                         |        |                |                |                  |                |
| <b>SERIES 200: SITE CLEARANCE</b>                                                                                                                     |        |                |                |                  | <b>37,592</b>  |
| General Site Clearance                                                                                                                                | 17,404 | m <sup>2</sup> | 2.16           | 37,592           |                |
| <b>SERIES 600: EARTHWORKS</b>                                                                                                                         |        |                |                |                  | <b>239,753</b> |
| <u>Excavation</u>                                                                                                                                     |        |                |                |                  |                |
| Excavation of artificial hard material; car park surface                                                                                              | 4,072  | m <sup>3</sup> | 11.52          | 46,909           |                |
| Excavation of artificial hard material; footpaths                                                                                                     | 488    | m <sup>3</sup> | 11.52          | 5,618            |                |
| Extra over for breaking out surfacing                                                                                                                 | 4,560  | m <sup>3</sup> | 9.74           | 44,411           |                |
| <u>Disposal of Material</u>                                                                                                                           |        |                |                |                  |                |
| Disposal of acceptable material excluding Class 5A                                                                                                    | 4,560  | m <sup>3</sup> | 28.23          | 128,718          |                |
| <u>Completion of Formation and Sub-formation</u>                                                                                                      |        |                |                |                  |                |
| Completion of sub-formation on acceptable material                                                                                                    | 17,404 | m <sup>2</sup> | 0.81           | 14,097           |                |
| <b>SERIES 700: PAVEMENTS</b>                                                                                                                          |        |                |                |                  | <b>823,168</b> |
| <b>Pavement; Car Park</b>                                                                                                                             |        |                |                |                  |                |
| <u>Sub-base</u>                                                                                                                                       |        |                |                |                  |                |
| Imported granular sub-base; Type 1 aggregate; 20mm depth car park (top up)                                                                            | 348    | m <sup>2</sup> | 0.99           | 343              |                |
| <u>Pavement</u>                                                                                                                                       |        |                |                |                  |                |
| AC32 HDM base 40/60 Rec 150mm thick                                                                                                                   | 17,404 | m <sup>2</sup> | 25.44          | 442,748          |                |
| AC20 Dense binder course 40/60 Rec 60mm thick in carriageway and car park                                                                             | 17,404 | m <sup>2</sup> | 10.72          | 186,629          |                |
| 40mm Thin Surface course system                                                                                                                       | 17,404 | m <sup>2</sup> | 11.12          | 193,448          |                |
| <b>SERIES 1100: KERBS, FOOTWAYS AND PAVED AREAS</b>                                                                                                   |        |                |                |                  | <b>82,047</b>  |
| <u>Footways and Paved Areas</u>                                                                                                                       |        |                |                |                  |                |
| Footpath type 1; comprising Type 1 granular material sub-base 150mm thick; AC20 DBM binder course 40/60 40mm thick; AC6 DBM surface course 20mm thick | 2,322  | m <sup>2</sup> | 35.33          | 82,047           |                |
| <b>SERIES 1200: TRAFFIC SIGNS AND ROAD MARKINGS</b>                                                                                                   |        |                |                |                  | <b>2,000</b>   |
| <u>Road Markings</u>                                                                                                                                  |        |                |                |                  |                |
| Road Marking                                                                                                                                          | 2      | shifts         | 1000.00        | 2,000            |                |
|                                                                                                                                                       |        |                | <b>Total</b>   | <b>1,184,560</b> |                |
| <b>CAR PARK RESURFACE</b>                                                                                                                             |        |                |                |                  |                |
| <b>SERIES 200: SITE CLEARANCE</b>                                                                                                                     |        |                |                |                  | <b>125,306</b> |
| General Site Clearance                                                                                                                                | 58,012 | m <sup>2</sup> | 2.16           | 125,306          |                |
| <b>SERIES 700: PAVEMENTS</b>                                                                                                                          |        |                |                |                  | <b>789,857</b> |
| <b>Pavement; Car Park</b>                                                                                                                             |        |                |                |                  |                |
| <b>Cold Milling</b>                                                                                                                                   |        |                |                |                  |                |
| Cold milling/planning; 40mm thick                                                                                                                     | 58,012 | m <sup>2</sup> | 2.00           | 116,024          |                |
| <u>Pavement</u>                                                                                                                                       |        |                |                |                  |                |
| Tack coat                                                                                                                                             | 58,012 | m <sup>2</sup> | 0.50           | 29,006           |                |
| 40mm Thin Surface course system                                                                                                                       | 58,012 | m <sup>2</sup> | 11.12          | 644,827          |                |
| <b>SERIES 1200: TRAFFIC SIGNS AND ROAD MARKINGS</b>                                                                                                   |        |                |                |                  | <b>2,000</b>   |
| <u>Road Markings</u>                                                                                                                                  |        |                |                |                  |                |

Mott MacDonald

Cambridge to Cambourne

Waterworks P & R

| Item         | Qty | Unit   | Unit rate<br>£ | Total<br>£ | Subtotal<br>£ |
|--------------|-----|--------|----------------|------------|---------------|
| Road Marking | 2   | shifts | 1000.00        | 2,000      |               |
|              |     |        | Total          | 917,163    |               |

## 10 Scotland Farm P&R

## Cambridge to Cambourne

Scotland Farm P &amp; R

| Item                                                                                                                                                                     | Qty    | Unit | Unit rate<br>£ | Total<br>£ | Subtotal<br>£    |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------|----------------|------------|------------------|
| <b>INITIAL CONSTRUCTION</b>                                                                                                                                              |        |      |                |            |                  |
| <b>SERIES 200: SITE CLEARANCE</b>                                                                                                                                        |        |      |                |            | <b>184,692</b>   |
| General Site Clearance                                                                                                                                                   | 85,505 | m²   | 2.16           | 184,692    |                  |
| <b>SERIES 300: FENCING</b>                                                                                                                                               |        |      |                |            | <b>31,274</b>    |
| Close boarded fencing, 1.8m high, 125mm x 125mm concrete post, set in concrete foundation; painted                                                                       | 985    | m    | 31.75          | 31,274     |                  |
| <b>SERIES 500: DRAINAGE AND SERVICE DUCTS</b>                                                                                                                            |        |      |                |            | <b>1,194,664</b> |
| <u>Drains and Service Ducts (Excluding Filter Drains, Narrow Filter Drains and Fin Drains)</u>                                                                           |        |      |                |            |                  |
| <u>Foul Water</u>                                                                                                                                                        |        |      |                |            |                  |
| 150mm diameter carrier drain with type S bed and surround; depth to invert not exceeding 2m                                                                              | 200    | m    | 47.72          | 9,544      |                  |
| Connections to existing drainage/outfalls; 150mm dia; depth to invert exceeding 2m but not exceeding 4m - allowance                                                      | 1      | nr   | 277.32         | 277        |                  |
| <u>Storm Water</u>                                                                                                                                                       |        |      |                |            |                  |
| 225mm diameter carrier drain with type S bed and surround; depth to invert 2m - 2.5m                                                                                     | 5,500  | m    | 84.11          | 462,605    |                  |
| Connections to existing drainage/outfalls; 225mm dia; depth to invert exceeding 2m but not exceeding 4m                                                                  | 6      | nr   | 277.32         | 1,525      |                  |
| <u>Chambers and Gullies</u>                                                                                                                                              |        |      |                |            |                  |
| Manhole; Depth : not exceeding 1.5 m; Type 2A (1.5m internal diameter) complete with allowance for concrete butt and rocker pipes                                        | 183    | nr   | 3,084.61       | 565,512    |                  |
| Precast concrete trapped gully with Class D400 grating and frame; 450mm x 750mm                                                                                          | 275    | nr   | 491.64         | 135,201    |                  |
| Drainage interceptor - Allowance                                                                                                                                         | 1      | nr   | 10,000.00      | 10,000     |                  |
| <u>Headwalls and Outfall Works</u>                                                                                                                                       |        |      |                |            |                  |
| Headwall and associated handrail/guardrail including outfall to attenuation pond - Allowance                                                                             | 1      | nr   | 10,000.00      | 10,000     |                  |
| <b>SERIES 600: EARTHWORKS</b>                                                                                                                                            |        |      |                |            | <b>2,208,818</b> |
| <u>General Excavation</u>                                                                                                                                                |        |      |                |            |                  |
| Excavation of acceptable material Class 5A Topsoil 150mm; excavate and set aside for re-use                                                                              | 12,826 | m³   | 5.61           | 71,953     |                  |
| Excavation of acceptable material normal material, excluding hard or artificially hard material, excluding Class 5A; > 2500m3; to form carpark and buildings foundations | 41,043 | m³   | 1.49           | 61,153     |                  |
| Excavation of acceptable material excluding Class 5A; for attenuation pond                                                                                               | 4,815  | m³   | 10.62          | 51,135     |                  |
| Excavation of acceptable material excluding Class 5A; for naturalised pond - 1m deep                                                                                     | 1,539  | m³   | 10.62          | 16,344     |                  |
| <u>Deposition of Fill</u>                                                                                                                                                |        |      |                |            |                  |
| Deposition of acceptable material normal material, excluding hard or artificially hard material, excluding Class 5A; > 2500m3; Topsoil                                   | 12,826 | m³   | 3.01           | 38,606     |                  |
| Deposition of acceptable material normal material, excluding hard or artificially hard material, excluding Class 5A; > 2500m3; to form new traffic island                | 4,717  | m³   | 3.01           | 14,199     |                  |
| <u>Disposal of Material</u>                                                                                                                                              |        |      |                |            |                  |
| Disposal of acceptable Class 5A topsoil                                                                                                                                  | 11,186 | m³   | 28.23          | 315,768    |                  |
| Disposal of acceptable material excluding Class 5A                                                                                                                       | 42,679 | m³   | 28.23          | 1,204,833  |                  |
| <u>Geotextiles</u>                                                                                                                                                       |        |      |                |            |                  |
| Geotextile separator (Terram 1000 or similar)                                                                                                                            | 80,299 | m²   | 2.84           | 228,049    |                  |
| <u>Topsoiling and Storage of Topsoiling</u>                                                                                                                              |        |      |                |            |                  |

|                                                                                                                                                       |        |        |          |           |                  |
|-------------------------------------------------------------------------------------------------------------------------------------------------------|--------|--------|----------|-----------|------------------|
| Topsoiling; Class 5A material excavated from site; 150mm thick; Sloping at 10 eg or less to the horizontal                                            | 10,935 | m²     | 1.10     | 12,029    |                  |
| <u>Completion of Formation and Sub-formation</u>                                                                                                      |        |        |          |           |                  |
| Completion of sub-formation on acceptable material                                                                                                    | 80,299 | m²     | 1.10     | 88,329    |                  |
| <u>Lining of Watercourses</u>                                                                                                                         |        |        |          |           |                  |
| Lining of new watercourse; attenuation pond                                                                                                           | 4,280  | m²     | 9.34     | 39,975    |                  |
| Lining of new watercourse; naturalised pond                                                                                                           | 926    | m²     | 9.34     | 8,653     | <b>3,302,155</b> |
| <u>Gabion Walling and Mattresses</u>                                                                                                                  |        |        |          |           |                  |
| Gabion walls; mesh basket filled with suitable aggregate; to attenuation pond                                                                         | 225    | m³     | 256.85   | 57,791    |                  |
| <b>SERIES 700: PAVEMENTS</b>                                                                                                                          |        |        |          |           |                  |
| <b>Pavement; Car Park</b>                                                                                                                             |        |        |          |           |                  |
| <u>Sub-base</u>                                                                                                                                       |        |        |          |           |                  |
| Imported granular sub-base; Type 1 aggregate; 200mm depth; Car park                                                                                   | 53,312 | m²     | 9.86     | 525,656   |                  |
| <u>Pavement</u>                                                                                                                                       |        |        |          |           |                  |
| AC32 HDM base 40/60 Rec 150mm thick                                                                                                                   | 53,312 | m²     | 25.44    | 1,356,257 |                  |
| AC20 Dense binder course 40/60 Rec 60mm thick in carriageway and car park                                                                             | 53,312 | m²     | 10.72    | 571,696   |                  |
| 40mm Thin Surface course system                                                                                                                       | 53,312 | m²     | 11.12    | 592,585   |                  |
| <b>Pavement; Access Road</b>                                                                                                                          |        |        |          |           |                  |
| <u>Sub-base</u>                                                                                                                                       |        |        |          |           |                  |
| Imported granular sub-base; Type 1 aggregate; 200mm depth car park                                                                                    | 4,480  | m²     | 9.86     | 44,173    |                  |
| <u>Pavement</u>                                                                                                                                       |        |        |          |           |                  |
| AC32 HDM base 40/60 Rec 150mm thick in carriageway and car park                                                                                       | 4,480  | m²     | 25.44    | 113,949   | <b>333,241</b>   |
| AC20 Dense binder course 40/60 Rec 60mm thick in carriageway and car park                                                                             | 4,480  | m²     | 10.72    | 48,042    |                  |
| 40mm Thin Surface course system                                                                                                                       | 4,480  | m²     | 11.12    | 49,797    |                  |
| <b>SERIES 1100: KERBS, FOOTWAYS AND PAVED AREAS</b>                                                                                                   |        |        |          |           |                  |
| <u>Kerbs, Channels, Edgings, Combined Drainage and Kerb Blocks</u>                                                                                    |        |        |          |           |                  |
| Precast concrete kerb; half battered (HB2 125 x 255 x 915mm) laid straight or curved                                                                  | 4,598  | m      | 20.19    | 92,834    |                  |
| Precast concrete kerbs (bus stop kerbs) laid straight or curved                                                                                       | 144    | m      | 190.76   | 27,469    |                  |
| Precast concrete edging(s) laid straight or curved                                                                                                    | 1,094  | m      | 13.72    | 15,014    |                  |
| <u>Footways and Paved Areas</u>                                                                                                                       |        |        |          |           |                  |
| 400mm square x 65mm thick buff tactile paving laid on 25mm to 35mm semidry mortar on 150mm thick type 1 subbase                                       | 609    | m²     | 85.87    | 52,295    | <b>6,000</b>     |
| Footpath type 1; comprising Type 1 granular material sub-base 150mm thick; AC20 DBM binder course 40/60 40mm thick; AC6 DBM surface course 20mm thick | 3,283  | m²     | 35.33    | 115,988   |                  |
| Footpath type 2; comprising Type 1 granular material sub-base 150mm thick; 50mm thick compacted sand and 60mm thick buff pavers                       | 609    | m²     | 48.67    | 29,640    |                  |
| <b>SERIES 1200: TRAFFIC SIGNS AND ROAD MARKINGS</b>                                                                                                   |        |        |          |           |                  |
| <u>Traffic Signs</u>                                                                                                                                  |        |        |          |           |                  |
| Signs - allowance                                                                                                                                     | 1      | nr     | 2,000.00 | 2,000     |                  |
| <u>Road Markings</u>                                                                                                                                  |        |        |          |           |                  |
| Road Marking                                                                                                                                          | 2      | shifts | 1,000.00 | 2,000     |                  |
| White lining                                                                                                                                          | 2      | shift  | 1,000.00 | 2,000     |                  |
| <b>SERIES 1300: ROAD LIGHTING COLUMNS AND BRACKETS, CCTV MASTS AND CANTILEVER MASTS</b>                                                               |        |        |          |           | <b>138,790</b>   |
| <u>Road Lighting Columns and Brackets, Wall Mountings, CCTV Masts and Cantilever Masts</u>                                                            |        |        |          |           |                  |

|                                                                                                                                                                |        |      |              |                  |                  |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------|--------------|------------------|------------------|
| 8m mounting height tubular galvanised steel column complete with a post top mounted Philips Luma 3 (BGP627 DS50 - 40km neutral white LED) mounted at 0° tilt   | 48     | nr   | 1,671.12     | 80,214           |                  |
| 8m mounting height tubular galvanised steel column complete with a post top mounted Philips Luma 3 (BGP627 DW10 - 35km neutral white LED) mounted at 0° tilt   | 4      | nr   | 1,671.12     | 6,684            |                  |
| 8m mounting height tubular galvanised steel column complete with a post top mounted Philips Luma 1 (BGP623 DX10 - 11km neutral white LED) mounted at 0° tilt   | 6      | nr   | 1,091.66     | 6,550            |                  |
| 8m mounting height tubular galvanised steel column complete with a post top mounted Philips Luma 1 (BGP623 DS50 - 13.5km neutral white LED) mounted at 0° tilt | 1      | nr   | 1,091.66     | 1,092            |                  |
| CCTV cameras to be mounted on Street lighting columns on 25% of SL poles - Allowance                                                                           | 15     | no   | 3,000.00     | 44,250           |                  |
| <b>SERIES 1400: ELECTRICAL WORK FOR ROAD LIGHTING AND TRAFFIC SIGNS</b>                                                                                        |        |      |              |                  | <b>233,706</b>   |
| <u>Cable and Duct</u>                                                                                                                                          |        |      |              |                  |                  |
| Street lighting duct; 1 way x 100mm diameter duct route in verge; not exceeding 1m deep to invert                                                              | 2,500  | m    | 27.52        | 68,800           |                  |
| Cabling 3 core XLPE/SWA/PVC                                                                                                                                    | 3,444  | m    | 33.14        | 114,134          |                  |
| CCTV communication cabling - Allowance                                                                                                                         | 861    | m    | 10.00        | 8,613            |                  |
| <u>Cable Joints and Terminations</u>                                                                                                                           |        |      |              |                  |                  |
| Terminations at each column - Allowance                                                                                                                        | 59     | nr   | 86.83        | 5,123            |                  |
| <u>Feeder Pillars</u>                                                                                                                                          |        |      |              |                  |                  |
| Tofco feeder pillar (medium), including DNO connection within 2m of LV main                                                                                    | 3      | nr   | 3,382.51     | 10,148           |                  |
| Telensa CMS node - Allowance                                                                                                                                   | 59     | nr   | 153.22       | 9,040            |                  |
| <u>Chambers</u>                                                                                                                                                |        |      |              |                  |                  |
| Street lighting chambers 450 x 450 x 900 (allow 1 per 100m)                                                                                                    | 25     | nr   | 575.75       | 14,394           |                  |
| CCTV chambers 450 x 450 x 900 (allow 1 per 100m)                                                                                                               | 6      | nr   | 575.75       | 3,455            |                  |
| <b>SERIES 2500: SPECIAL STRUCTURES</b>                                                                                                                         |        |      |              |                  | <b>896,331</b>   |
| Passenger waiting structure                                                                                                                                    | 224    | m²   | 3,500.00     | 784,000          |                  |
| Ticket machine @ Park and Ride - Allowance                                                                                                                     | 2      | nr   | 35,000.00    | 70,000           |                  |
| Cycle Parking (Assumed Cycle Shelter - 10 Space Cycle Shelter & Bike Stands)                                                                                   | 10     | item | 635.48       | 6,355            |                  |
| Cycle boxes (Assumed bike away locker)                                                                                                                         | 30     | item | 1,199.21     | 35,976           |                  |
| <b>SERIES 3000: LANDSCAPING AND ECOLOGY</b>                                                                                                                    |        |      |              |                  | <b>1,157,556</b> |
| <u>Seeding and Turfing</u>                                                                                                                                     |        |      |              |                  |                  |
| Seeding                                                                                                                                                        | 9,828  | m²   | 0.54         | 5,339            |                  |
| <u>Special Ecological Measures</u>                                                                                                                             |        |      |              |                  |                  |
| Environmental barrier (assumed bare rooted native species whips)                                                                                               | 62,453 | m²   | 18.45        | 1,152,217        |                  |
|                                                                                                                                                                |        |      | <b>Total</b> | <b>9,687,227</b> |                  |

|                                                                                                                                                       |        |        |              |                  |                  |
|-------------------------------------------------------------------------------------------------------------------------------------------------------|--------|--------|--------------|------------------|------------------|
| <b>30% SURFACING RENEWALS</b>                                                                                                                         |        |        |              |                  |                  |
| <b>SERIES 200: SITE CLEARANCE</b>                                                                                                                     |        |        |              |                  | <b>55,408</b>    |
| General Site Clearance                                                                                                                                | 25,652 | m²     | 2.16         | 55,408           |                  |
| <b>SERIES 600: EARTHWORKS</b>                                                                                                                         |        |        |              |                  | <b>262,819</b>   |
| <u>Excavation</u>                                                                                                                                     |        |        |              |                  |                  |
| Excavation of artificial hard material; car park surface                                                                                              | 4,318  | m³     | 11.52        | 49,746           |                  |
| Excavation of artificial hard material; access road surface                                                                                           | 363    | m³     | 11.52        | 4,180            |                  |
| Excavation of artificial hard material; footpaths                                                                                                     | 272    | m³     | 11.52        | 3,136            |                  |
| Extra over for breaking out surfacing                                                                                                                 | 4,953  | m³     | 9.74         | 48,246           |                  |
| <u>Disposal of Material</u>                                                                                                                           |        |        |              |                  |                  |
| Disposal of acceptable material excluding Class 5A                                                                                                    | 4,953  | m³     | 28.23        | 139,833          |                  |
| <u>Completion of Formation and Sub-formation</u>                                                                                                      |        |        |              |                  |                  |
| Completion of sub-formation on acceptable material                                                                                                    | 21,824 | m²     | 0.81         | 17,677           |                  |
| <b>SERIES 700: PAVEMENTS</b>                                                                                                                          |        |        |              |                  | <b>1,124,136</b> |
| <b>Pavement; Car Park</b>                                                                                                                             |        |        |              |                  |                  |
| <u>Sub-base</u>                                                                                                                                       |        |        |              |                  |                  |
| Imported granular sub-base; Type 1 aggregate; 20mm depth car park (top up)                                                                            | 15,994 | m²     | 0.99         | 15,780           |                  |
| <u>Pavement</u>                                                                                                                                       |        |        |              |                  |                  |
| AC32 HDM base 40/60 Rec 200mm thick in carriageway and car park                                                                                       | 15,994 | m²     | 33.91        | 542,397          |                  |
| AC20 Dense binder course 40/60 Rec 60mm thick in carriageway and car park                                                                             | 15,994 | m²     | 10.72        | 171,509          |                  |
| 40mm Thin Surface course system                                                                                                                       | 15,994 | m²     | 11.12        | 177,775          |                  |
| <b>Pavement; Access Road</b>                                                                                                                          |        |        |              |                  |                  |
| <u>Sub-base</u>                                                                                                                                       |        |        |              |                  |                  |
| Imported granular sub-base; Type 1 aggregate; 20mm depth car park (top up)                                                                            | 4,480  | m²     | 1.09         | 4,888            |                  |
| <u>Pavement</u>                                                                                                                                       |        |        |              |                  |                  |
| AC32 HDM base 40/60 Rec 150mm thick in carriageway and car park                                                                                       | 4,480  | m²     | 25.44        | 113,949          |                  |
| AC20 Dense binder course 40/60 Rec 60mm thick in carriageway and car park                                                                             | 4,480  | m²     | 10.72        | 48,042           |                  |
| 40mm Thin Surface course system                                                                                                                       | 4,480  | m²     | 11.12        | 49,797           |                  |
| <b>SERIES 1100: KERBS, FOOTWAYS AND PAVED AREAS</b>                                                                                                   |        |        |              |                  | <b>38,994</b>    |
| <u>Footways and Paved Areas</u>                                                                                                                       |        |        |              |                  |                  |
| 400mm square x 65mm thick buff tactile paving laid on 25mm to 35mm semidry mortar on 150mm thick type 1 subbase                                       | 183    | m²     | 43.54        | 7,955            |                  |
| Footpath type 1; comprising Type 1 granular material sub-base 150mm thick; AC20 DBM binder course 40/60 40mm thick; AC6 DBM surface course 20mm thick | 985    | m²     | 22.66        | 22,315           |                  |
| Footpath type 1; comprising Type 1 granular material sub-base 150mm thick; 50mm thick compacted sand and 60mm thick buff pavers                       | 183    | m²     | 47.75        | 8,724            |                  |
| <b>SERIES 1200: TRAFFIC SIGNS AND ROAD MARKINGS</b>                                                                                                   |        |        |              |                  | <b>4,000</b>     |
| <u>Road Markings</u>                                                                                                                                  |        |        |              |                  |                  |
| Road Marking                                                                                                                                          | 2      | shifts | 1000.00      | 2,000            |                  |
| White lining                                                                                                                                          | 2      | shift  | 1,000.00     | 2,000            |                  |
|                                                                                                                                                       |        |        | <b>Total</b> | <b>1,485,357</b> |                  |

| CAR PARK & ACCESS RD RESURFACE                      |        |        |         |                |                |
|-----------------------------------------------------|--------|--------|---------|----------------|----------------|
| <b>SERIES 200: SITE CLEARANCE</b>                   |        |        |         |                | <b>131,922</b> |
| General Site Clearance                              | 61,075 | m²     | 2.16    | 131,922        |                |
| <b>SERIES 700: PAVEMENTS</b>                        |        |        |         |                | <b>831,561</b> |
| <b>Cold Milling</b>                                 |        |        |         |                |                |
| Cold milling/planning; 40mm thick                   | 61,075 | m²     | 2.00    | 122,150        |                |
| <b>Pavement</b>                                     |        |        |         |                |                |
| <u>Pavement</u>                                     |        |        |         |                |                |
| Tack coat                                           | 61,075 | m²     | 0.50    | 30,538         |                |
| 40mm Thin Surface course system                     | 61,075 | m²     | 11.12   | 678,874        |                |
| <b>SERIES 1200: TRAFFIC SIGNS AND ROAD MARKINGS</b> |        |        |         |                | <b>2,000</b>   |
| <u>Road Markings</u>                                |        |        |         |                |                |
| Road Marking                                        | 2      | shifts | 1000.00 | 2,000          |                |
| <b>Total</b>                                        |        |        |         | <b>965,483</b> |                |

## 11 WLC Maintenance Costs

| Description                                        | Quantity | Units  | Rate       | 4Q18 Total (£) | 2Q19 Total (£) | Service Costs (£) | 4Q19 Outturn Cost (£) |
|----------------------------------------------------|----------|--------|------------|----------------|----------------|-------------------|-----------------------|
| <b>Street Cleaning</b>                             |          |        |            |                |                |                   |                       |
| Operated Road Sweeper Vehicle - Allowance          | 1        | day    | 440.00     | 440.00         | 446.60         | 66.99             |                       |
|                                                    | 1        | visit  |            |                | 446.60         | 66.99             | 513.59                |
| <b>Landscaping Maintenance</b>                     |          |        |            |                |                |                   |                       |
| Labourer                                           | 1        | days   | 159.84     | 159.84         | 162.24         | 24.34             |                       |
| Ride On Mower                                      | 1        | days   | 53.00      | 53.00          | 53.80          | 8.07              |                       |
| 5.5m Hedgecutter with operator                     | 1        | days   | 250.00     | 250.00         | 253.75         | 38.06             |                       |
|                                                    | 1        | visit  |            |                | 469.78         | 70.47             | 540.25                |
| <b>Gully cleansing / Emptying</b>                  |          |        |            |                |                |                   |                       |
| Labourer                                           | 1        | day    | 159.84     | 159.84         | 162.24         | 24.34             |                       |
| Gully Emptier                                      | 1        | day    | 790.00     | 790.00         | 801.85         | 120.28            |                       |
|                                                    | 1        | visit  |            |                | 964.09         | 144.61            | 1,108.70              |
| <b>Street &amp; CCTV Lighting</b>                  |          |        |            |                |                |                   |                       |
| Labour                                             | 4        | man.hr | 19.98      | 79.92          | 81.12          | 12.17             |                       |
| Cherrypicker                                       | 2        | hr     | 14.39      | 28.78          | 29.21          | 4.38              |                       |
| Electrical fittings                                | 1        | nr     | 550.00     | 550.00         | 558.25         | 83.74             |                       |
|                                                    | 1        | nr     |            |                | 668.58         | 100.29            | 768.87                |
| <b>Kerbing</b>                                     |          |        |            |                |                |                   |                       |
| Take up existing Kerbs and dispose off site        | 1        | m      | 9.42       | 9.42           | 9.56           | 1.43              |                       |
| HB2 Kerb                                           | 1        | m      | 21.65      | 21.65          | 21.97          | 3.30              |                       |
|                                                    | 1        | m      |            |                | 31.54          | 4.73              | 36.27                 |
| <b>Bus Stops</b>                                   |          |        |            |                |                |                   |                       |
| Fittings                                           | 2        | nr     | 3,000.00   | 6,000.00       | 6,090.00       | 913.50            |                       |
|                                                    |          |        |            |                | 6,090.00       | 913.50            | 7,003.50              |
| <b>Traffic lights</b>                              |          |        |            |                |                |                   |                       |
| Allowance to fix new traffic lights                | 1        | item   | 250,000.00 |                |                |                   |                       |
|                                                    |          |        |            |                | 0.00           | 0.00              | 250,000.00            |
| <b>Fencing Maintenance</b>                         |          |        |            |                |                |                   |                       |
| Take up and remove from site boundary fencing      | 1        | m      | 10.95      | 10.95          | 11.11          | 1.67              |                       |
| Replacement fencing                                | 1        | m      | 30.55      | 30.55          | 31.01          | 4.65              |                       |
|                                                    | 1        | m      |            |                | 42.12          | 6.32              | 48.44                 |
| <b>General Inspection (2 bridges)</b>              |          |        |            |                |                |                   |                       |
| Senior Engineer                                    | 50       | hr     | 50.00      |                | 2,500.00       | 375.00            |                       |
| Engineer                                           | 50       | hr     | 40.00      |                | 2,000.00       | 300.00            |                       |
| Gen. Labourer                                      | 100      | man.hr | 19.98      | 1,998.00       | 2,027.97       | 304.20            |                       |
| Access Platform                                    | 30       | hr     | 15.64      | 469.20         | 476.24         | 71.44             |                       |
| Materials Allowance                                |          |        |            |                | 2,000.00       |                   |                       |
| Senior Engineer                                    | 16       | hr     | 50.00      |                | 800.00         | 120.00            |                       |
|                                                    | 1        | m      |            |                | 9,804.21       | 1,170.63          | 10,974.84             |
| <b>Principal Inspection (2 bridges)</b>            |          |        |            |                |                |                   |                       |
| Senior Engineer                                    | 200      | hr     | 50.00      |                | 10,000.00      | 1,500.00          |                       |
| Engineer                                           | 200      | hr     | 40.00      |                | 8,000.00       | 1,200.00          |                       |
| Gen. Labourer                                      | 200      | man.hr | 19.98      | 3,996.00       | 4,055.94       | 608.39            |                       |
| Access Platform                                    | 50       | hr     | 15.64      | 782.00         | 793.73         | 119.06            |                       |
| Materials Allowance                                |          |        |            |                | 2,000.00       |                   |                       |
| Senior Engineer                                    | 32       | hr     | 50.00      |                | 1,600.00       | 240.00            |                       |
|                                                    | 1        | m      |            |                | 26,449.67      | 3,667.45          | 30,117.12             |
| <b>Special Inspection (2 bridges)</b>              |          |        |            |                |                |                   |                       |
| Senior Engineer                                    | 300      | hr     | 50.00      |                | 15,000.00      | 2,250.00          |                       |
| Engineer                                           | 300      | hr     | 40.00      |                | 12,000.00      | 1,800.00          |                       |
| Gen. Labourer                                      | 300      | man.hr | 19.98      | 5,994.00       | 6,083.91       | 912.59            |                       |
| Access Platform                                    | 100      | hr     | 15.64      | 1,564.00       | 1,587.46       | 238.12            |                       |
| Materials Allowance                                |          |        |            |                | 2,000.00       |                   |                       |
| Senior Engineer                                    | 40       | hr     | 50.00      |                | 2,000.00       | 300.00            |                       |
|                                                    | 1        | m      |            |                | 38,671.37      | 5,500.71          | 44,172.08             |
| <b>Bearing Replacement - Abutments (2 bridges)</b> |          |        |            |                |                |                   |                       |
| Senior Engineer                                    | 20       | hr     | 50.00      | 1000           | 1,015.00       | 152.25            |                       |
| Engineer                                           | 20       | hr     | 40.00      | 800            | 812.00         | 121.80            |                       |
| Gen. Labourer                                      | 40       | hr     | 26.40      | 1056           | 1,071.84       | 160.78            |                       |
| Bridge jacking                                     | 2        | item   | 25,000.00  |                | 50,000.00      |                   |                       |
| Minor Materials                                    | 2        | item   | 1,000.00   |                | 2,000.00       |                   |                       |
| Bearings                                           | 8        | nr     | 3,750.00   | 15000          | 15,225.00      | 2,283.75          |                       |
| Bearing Disposal                                   | 8        | nr     | 15.00      | 60             | 60.90          | 9.14              |                       |
| Testing of Bearings                                | 8        | nr     | 500.00     | 2000           | 2,030.00       | 304.50            |                       |
|                                                    | 1        | m      |            |                | 72,214.74      | 3,032.21          | 75,246.95             |

## 12 Phase 1 WLC

## Phase 1 Whole Life Costing

| Location Ref                    | Work element Scenario 1                                    | Assumptions                                                                                                   | Quantity | Unit | Rate (£)     | Cost per occurrence (£) | # Occurrences | Total Cost (£) | 1          | 2      | 3      | 4      | 5      | 6       | 7      | 8      | 9      | 10        |
|---------------------------------|------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------|----------|------|--------------|-------------------------|---------------|----------------|------------|--------|--------|--------|--------|---------|--------|--------|--------|-----------|
| <b>CAPITAL</b>                  |                                                            |                                                                                                               |          |      |              |                         |               |                |            |        |        |        |        |         |        |        |        |           |
|                                 | Construct Road                                             | P80 estimate                                                                                                  | 1        | item | 63,756,407   | 63,756,407              | 1             | 63,756,407     | 63,756,407 |        |        |        |        |         |        |        |        |           |
| <b>TOTAL COSTS - CAPITAL</b>    |                                                            |                                                                                                               |          |      |              |                         |               |                |            |        |        |        |        |         |        |        |        |           |
| <b>OPERATIONAL</b>              |                                                            |                                                                                                               |          |      |              |                         |               |                |            |        |        |        |        |         |        |        |        |           |
|                                 | Power Consumption - Lighting                               | 505nr lights x 254w = 13208w per hour = 128.27kW x 4,380 hours year = 561,822.60kW (as advised by DW Windsor) | 561,823  | kW   | 0.12         | 67,419                  | 60            | 4,045,123      | 67,419     | 67,419 | 67,419 | 67,419 | 67,419 | 67,419  | 67,419 | 67,419 | 67,419 | 67,419    |
| <b>TOTAL COST - OPERATIONAL</b> |                                                            |                                                                                                               |          |      |              |                         |               |                |            |        |        |        |        |         |        |        |        |           |
| <b>Maintenance and Renewals</b> |                                                            |                                                                                                               |          |      |              |                         |               |                |            |        |        |        |        |         |        |        |        |           |
|                                 | General inspection - 2 Bridge Structures                   | Every two years                                                                                               | 1        | item | 10,974.84    | 10,975                  | 30            | 329,245        |            | 10,975 |        | 10,975 |        | 10,975  |        | 10,975 |        | 10,975    |
|                                 | Principal inspection - 2 Bridge Structures                 | Every six years                                                                                               | 1        | item | 30,117.12    | 30,117                  | 10            | 301,171        |            |        |        |        |        | 30,117  |        |        |        |           |
|                                 | Special inspection - 2 Bridge Structures                   | Every twenty years                                                                                            | 1        | item | 44,172.08    | 44,172                  | 3             | 132,516        |            |        |        |        |        |         |        |        |        |           |
|                                 | Bearing Replacement - 2 Bridge Structures                  | Every 30 years                                                                                                | 1        | item | 75,246.95    | 75,247                  | 2             | 150,494        |            |        |        |        |        |         |        |        |        |           |
|                                 | Bridge Deck Resurfacing (Full depth) - 2 Bridge Structures | Every 20 Years                                                                                                | 1        | item | 320,657.36   | 320,657                 | 3             | 961,972        |            |        |        |        |        |         |        |        |        |           |
|                                 | 100% Road Resurfacing                                      | Every 20 Years                                                                                                | 1        | item | 1,423,260.38 | 1,423,260               | 3             | 4,269,781      |            |        |        |        |        |         |        |        |        | 1,423,260 |
|                                 | 30% Renew Road and Footpaths                               | Every 20 Years                                                                                                | 1        | item | 1,752,901.41 | 1,752,901               | 2             | 3,505,803      |            |        |        |        |        |         |        |        |        |           |
|                                 | Landscaping maintenance                                    | Yearly                                                                                                        | 1        | item | 540.25       | 540                     | 60            | 32,415         | 540        | 540    | 540    | 540    | 540    | 540     | 540    | 540    | 540    | 540       |
|                                 | Street Cleaning                                            | Yearly                                                                                                        | 1        | item | 513.59       | 514                     | 60            | 30,815         | 514        | 514    | 514    | 514    | 514    | 514     | 514    | 514    | 514    | 514       |
|                                 | Gully Cleansing / Emptying                                 | Yearly                                                                                                        | 1        | item | 1,108.70     | 1,109                   | 60            | 66,522         | 1,109      | 1,109  | 1,109  | 1,109  | 1,109  | 1,109   | 1,109  | 1,109  | 1,109  | 1,109     |
|                                 | Street Lighting                                            | Every 20 Years                                                                                                | 505      | nr   | 768.87       | 388,639                 | 2             | 777,277        |            |        |        |        |        |         |        |        |        |           |
|                                 | Kerb Replacement                                           | 10% every 20 years                                                                                            | 286      | m    | 36.27        | 10,362                  | 2             | 20,724         |            |        |        |        |        |         |        |        |        |           |
|                                 | Fencing                                                    | Every 20 Years                                                                                                | 2340     | m    | 48.44        | 113,352                 | 2             | 226,703        |            |        |        |        |        |         |        |        |        |           |
| <b>TOTAL COST - MAINTENANCE</b> |                                                            |                                                                                                               |          |      |              |                         |               |                |            |        |        |        |        |         |        |        |        |           |
| <b>TOTAL COST</b>               |                                                            |                                                                                                               |          |      |              |                         |               |                |            |        |        |        |        |         |        |        |        |           |
| <b>Subtotals</b>                |                                                            |                                                                                                               |          |      |              |                         |               |                | 63,825,988 | 80,556 | 69,581 | 80,556 | 69,581 | 110,673 | 69,581 | 80,556 | 69,581 | 1,503,816 |

|                  |             |            |        |        |        |        |        |        |        |        |           |
|------------------|-------------|------------|--------|--------|--------|--------|--------|--------|--------|--------|-----------|
| NPV @ 3.5%       | 0.9662      | 0.9335     | 0.9019 | 0.8714 | 0.8420 | 0.8135 | 0.7860 | 0.7594 | 0.7337 | 0.7089 |           |
| NPV (2019) Total | £67,424,939 | 61,667,621 | 75,200 | 62,758 | 70,200 | 58,586 | 90,033 | 54,690 | 61,175 | 51,054 | 1,066,084 |

[illegible]

| 38     | 39     | 40        | 41     | 42      | 43     | 44     | 45     | 46     | 47     | 48      | 49     | 50        | 51     | 52     | 53     | 54      | 55     | 56     | 57     | 58     | 59     | 60      |
|--------|--------|-----------|--------|---------|--------|--------|--------|--------|--------|---------|--------|-----------|--------|--------|--------|---------|--------|--------|--------|--------|--------|---------|
|        |        |           |        |         |        |        |        |        |        |         |        |           |        |        |        |         |        |        |        |        |        |         |
|        |        |           |        |         |        |        |        |        |        |         |        |           |        |        |        |         |        |        |        |        |        |         |
|        |        |           |        |         |        |        |        |        |        |         |        |           |        |        |        |         |        |        |        |        |        |         |
|        |        |           |        |         |        |        |        |        |        |         |        |           |        |        |        |         |        |        |        |        |        | 0       |
|        |        |           |        |         |        |        |        |        |        |         |        |           |        |        |        |         |        |        |        |        |        |         |
|        |        |           |        |         |        |        |        |        |        |         |        |           |        |        |        |         |        |        |        |        |        |         |
|        |        |           |        |         |        |        |        |        |        |         |        |           |        |        |        |         |        |        |        |        |        |         |
|        |        |           |        |         |        |        |        |        |        |         |        |           |        |        |        |         |        |        |        |        |        |         |
| 67,419 | 67,419 | 67,419    | 67,419 | 67,419  | 67,419 | 67,419 | 67,419 | 67,419 | 67,419 | 67,419  | 67,419 | 67,419    | 67,419 | 67,419 | 67,419 | 67,419  | 67,419 | 67,419 | 67,419 | 67,419 | 67,419 | 67,419  |
|        |        |           |        |         |        |        |        |        |        |         |        |           |        |        |        |         |        |        |        |        |        |         |
|        |        |           |        |         |        |        |        |        |        |         |        |           |        |        |        |         |        |        |        |        |        |         |
|        |        |           |        |         |        |        |        |        |        |         |        |           |        |        |        |         |        |        |        |        |        |         |
|        |        |           |        |         |        |        |        |        |        |         |        |           |        |        |        |         |        |        |        |        |        |         |
|        |        |           |        |         |        |        |        |        |        |         |        |           |        |        |        |         |        |        |        |        |        |         |
|        |        |           |        |         |        |        |        |        |        |         |        |           |        |        |        |         |        |        |        |        |        |         |
| 10,975 |        | 10,975    |        | 10,975  |        | 10,975 |        | 10,975 |        | 10,975  |        | 10,975    |        | 10,975 |        | 10,975  |        | 10,975 |        | 10,975 |        | 10,975  |
|        |        |           |        | 30,117  |        |        |        |        |        | 30,117  |        |           |        |        |        | 30,117  |        |        |        |        |        | 30,117  |
|        |        | 44,172    |        |         |        |        |        |        |        |         |        |           |        |        |        |         |        |        |        |        |        | 44,172  |
|        |        |           |        |         |        |        |        |        |        |         |        |           |        |        |        |         |        |        |        |        |        | 75,247  |
|        |        |           |        |         |        |        |        |        |        |         |        |           |        |        |        |         |        |        |        |        |        |         |
|        |        | 320,657   |        |         |        |        |        |        |        |         |        |           |        |        |        |         |        |        |        |        |        | 320,657 |
|        |        |           |        |         |        |        |        |        |        |         |        |           |        |        |        |         |        |        |        |        |        |         |
|        |        |           |        |         |        |        |        |        |        |         |        | 1,423,260 |        |        |        |         |        |        |        |        |        |         |
|        |        | 1,752,901 |        |         |        |        |        |        |        |         |        |           |        |        |        |         |        |        |        |        |        |         |
| 540    | 540    | 540       | 540    | 540     | 540    | 540    | 540    | 540    | 540    | 540     | 540    | 540       | 540    | 540    | 540    | 540     | 540    | 540    | 540    | 540    | 540    | 540     |
| 514    | 514    | 514       | 514    | 514     | 514    | 514    | 514    | 514    | 514    | 514     | 514    | 514       | 514    | 514    | 514    | 514     | 514    | 514    | 514    | 514    | 514    | 514     |
| 1,109  | 1,109  | 1,109     | 1,109  | 1,109   | 1,109  | 1,109  | 1,109  | 1,109  | 1,109  | 1,109   | 1,109  | 1,109     | 1,109  | 1,109  | 1,109  | 1,109   | 1,109  | 1,109  | 1,109  | 1,109  | 1,109  | 1,109   |
|        |        | 388,639   |        |         |        |        |        |        |        |         |        |           |        |        |        |         |        |        |        |        |        |         |
|        |        | 10,362    |        |         |        |        |        |        |        |         |        |           |        |        |        |         |        |        |        |        |        |         |
|        |        | 113,352   |        |         |        |        |        |        |        |         |        |           |        |        |        |         |        |        |        |        |        |         |
|        |        |           |        |         |        |        |        |        |        |         |        |           |        |        |        |         |        |        |        |        |        |         |
|        |        |           |        |         |        |        |        |        |        |         |        |           |        |        |        |         |        |        |        |        |        |         |
|        |        |           |        |         |        |        |        |        |        |         |        |           |        |        |        |         |        |        |        |        |        |         |
| 80,556 | 69,581 | 2,710,639 | 69,581 | 110,673 | 69,581 | 80,556 | 69,581 | 80,556 | 69,581 | 110,673 | 69,581 | 1,503,816 | 69,581 | 80,556 | 69,581 | 110,673 | 69,581 | 80,556 | 69,581 | 80,556 | 69,581 | 550,750 |

£78,606,968.55

|        |        |        |        |        |        |        |        |        |        |        |        |        |        |        |        |        |        |        |        |        |        |        |
|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| 0.2706 | 0.2614 | 0.2526 | 0.2440 | 0.2358 | 0.2278 | 0.2201 | 0.2127 | 0.2055 | 0.1985 | 0.1918 | 0.1853 | 0.1791 | 0.1730 | 0.1671 | 0.1615 | 0.1560 | 0.1508 | 0.1457 | 0.1407 | 0.1360 | 0.1314 | 0.1269 |
|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|

|        |        |         |        |        |        |        |        |        |        |        |        |         |        |        |        |        |        |        |       |        |       |        |
|--------|--------|---------|--------|--------|--------|--------|--------|--------|--------|--------|--------|---------|--------|--------|--------|--------|--------|--------|-------|--------|-------|--------|
| 21,795 | 18,189 | 684,633 | 16,980 | 26,094 | 15,851 | 17,731 | 14,797 | 16,552 | 13,813 | 21,228 | 12,895 | 269,263 | 12,037 | 13,465 | 11,237 | 17,269 | 10,490 | 11,734 | 9,792 | 10,954 | 9,141 | 69,909 |
|--------|--------|---------|--------|--------|--------|--------|--------|--------|--------|--------|--------|---------|--------|--------|--------|--------|--------|--------|-------|--------|-------|--------|

£67,424,939.44 Net Present Value Total Sum

## 13 Option 1 WLC

Option 1 Whole Life Costing

| Location Ref             | Work element Scenario 1               | Assumptions                                                                                                  | Quantity | Unit | Rate (£)      | Cost per occurrence (£) | # Occurrences | Total Cost (£) | 1              | 2          | 3      | 4      | 5      | 6      | 7      | 8      | 9      | 10        |           |
|--------------------------|---------------------------------------|--------------------------------------------------------------------------------------------------------------|----------|------|---------------|-------------------------|---------------|----------------|----------------|------------|--------|--------|--------|--------|--------|--------|--------|-----------|-----------|
| CAPITAL                  |                                       |                                                                                                              |          |      |               |                         |               |                |                |            |        |        |        |        |        |        |        |           |           |
|                          | Construct Road                        | P80 estimate                                                                                                 | 1        | item | 47,619,348.39 | 47,619,348              | 1             | 47,619,348     | 47,619,348     |            |        |        |        |        |        |        |        |           |           |
|                          |                                       |                                                                                                              |          |      |               |                         |               |                |                |            |        |        |        |        |        |        |        |           |           |
| TOTAL COSTS - CAPITAL    |                                       |                                                                                                              |          |      |               |                         |               | 47,619,348     |                |            |        |        |        |        |        |        |        |           |           |
| OPERATIONAL              |                                       |                                                                                                              |          |      |               |                         |               |                |                |            |        |        |        |        |        |        |        |           |           |
|                          | Power Consumption - Lighting (Luma 3) | 418nr lights x 254w = 106,172w per hour = 106.17kW x 4,380 hours year = 465,025kW (as advised by DW Windsor) | 465,025  | kW   | 0.12          | 55,803                  | 60            | 3,348,180      | 55,803         | 55,803     | 55,803 | 55,803 | 55,803 | 55,803 | 55,803 | 55,803 | 55,803 | 55,803    |           |
|                          |                                       |                                                                                                              |          |      |               |                         |               |                |                |            |        |        |        |        |        |        |        |           |           |
| TOTAL COST - OPERATIONAL |                                       |                                                                                                              |          |      |               |                         |               | 3,348,180      |                |            |        |        |        |        |        |        |        |           |           |
| Maintenance and Renewals |                                       |                                                                                                              |          |      |               |                         |               |                |                |            |        |        |        |        |        |        |        |           |           |
|                          | 100% Road Resurfacing                 | Every 20 Years                                                                                               | 1        | item | 1,694,742.98  | 1,694,743               | 3             | 5,084,229      |                |            |        |        |        |        |        |        |        | 1,694,743 |           |
|                          | 30% Renew Road and Footpaths          | Every 20 Years                                                                                               | 1        | item | 2,527,524.62  | 2,527,525               | 2             | 5,055,049      |                |            |        |        |        |        |        |        |        |           |           |
|                          | Landscaping maintenance               | Yearly                                                                                                       | 1        | item | 540.25        | 540                     | 60            | 32,415         | 540            | 540        | 540    | 540    | 540    | 540    | 540    | 540    | 540    | 540       |           |
|                          | Street Cleaning                       | Yearly                                                                                                       | 1        | item | 513.59        | 514                     | 60            | 30,815         | 514            | 514        | 514    | 514    | 514    | 514    | 514    | 514    | 514    | 514       |           |
|                          | Gully Cleansing / Emptying            | Yearly                                                                                                       | 1        | item | 1,108.70      | 1,109                   | 60            | 66,522         | 1,109          | 1,109      | 1,109  | 1,109  | 1,109  | 1,109  | 1,109  | 1,109  | 1,109  | 1,109     |           |
|                          | Street Lighting                       | Every 20 Years                                                                                               | 418      | nr   | 768.87        | 321,387                 | 2             | 642,773        |                |            |        |        |        |        |        |        |        |           |           |
|                          | Kerb Replacement                      | 10% every 20 years                                                                                           | 532      | m    | 36.27         | 19,293                  | 2             | 38,587         |                |            |        |        |        |        |        |        |        |           |           |
|                          |                                       |                                                                                                              |          |      |               |                         |               |                |                |            |        |        |        |        |        |        |        |           |           |
| TOTAL COST - MAINTENANCE |                                       |                                                                                                              |          |      |               |                         |               | 10,950,391     |                |            |        |        |        |        |        |        |        |           |           |
| TOTAL COST               |                                       |                                                                                                              |          |      |               |                         |               | 61,917,919     |                |            |        |        |        |        |        |        |        |           |           |
| Subtotals                |                                       |                                                                                                              |          |      |               |                         |               |                | 47,677,314     | 57,966     | 57,966 | 57,966 | 57,966 | 57,966 | 57,966 | 57,966 | 57,966 | 1,752,709 |           |
| NPV @ 3.5%               |                                       |                                                                                                              |          |      |               |                         |               |                | 0.9662         | 0.9335     | 0.9019 | 0.8714 | 0.8420 | 0.8135 | 0.7860 | 0.7594 | 0.7337 | 0.7089    |           |
| NPV (2019) Total         |                                       |                                                                                                              |          |      |               |                         |               |                | £51,729,543.53 | 46,065,038 | 54,111 | 52,282 | 50,514 | 48,805 | 47,155 | 45,560 | 44,020 | 42,531    | 1,242,528 |

[illegible]

[illegible]

## 14 Option 2 WLC

## Option 2 Whole Life Costing

| Location Ref                    | Work element Scenario 1               | Assumptions                                                                                                      | Quantity | Unit | Rate (£)      | Cost per occurrence (£) | # Occurrences | Total Cost (£) | 1          | 2      | 3      | 4      | 5      | 6      | 7      | 8      | 9      | 10        |
|---------------------------------|---------------------------------------|------------------------------------------------------------------------------------------------------------------|----------|------|---------------|-------------------------|---------------|----------------|------------|--------|--------|--------|--------|--------|--------|--------|--------|-----------|
| <b>CAPITAL</b>                  |                                       |                                                                                                                  |          |      |               |                         |               |                |            |        |        |        |        |        |        |        |        |           |
|                                 | Construct Road                        | P80 estimate                                                                                                     | 1        | item | 27,365,073.29 | 27,365,073              | 1             | 27,365,073     | 27,365,073 |        |        |        |        |        |        |        |        |           |
| <b>TOTAL COSTS - CAPITAL</b>    |                                       |                                                                                                                  |          |      |               |                         |               |                | 27,365,073 |        |        |        |        |        |        |        |        |           |
| <b>OPERATIONAL</b>              |                                       |                                                                                                                  |          |      |               |                         |               |                |            |        |        |        |        |        |        |        |        |           |
|                                 | Power Consumption - Lighting (Luma 3) | 231nr lights x 254w = 58,674w per hour =<br>58.67kW x 4,380 hours year = 256,975kW<br>(as advised by DW Windsor) | 256,975  | kW   | 0.12          | 30,837                  | 60            | 1,850,220      | 30,837     | 30,837 | 30,837 | 30,837 | 30,837 | 30,837 | 30,837 | 30,837 | 30,837 | 30,837    |
| <b>TOTAL COST - OPERATIONAL</b> |                                       |                                                                                                                  |          |      |               |                         |               |                | 1,850,220  |        |        |        |        |        |        |        |        |           |
| <b>Maintenance and Renewals</b> |                                       |                                                                                                                  |          |      |               |                         |               |                |            |        |        |        |        |        |        |        |        |           |
|                                 | Resurfacing Road                      | Every 10 Years                                                                                                   | 1        | item | 1,596,643.37  | 1,596,643               | 3             | 4,789,930      |            |        |        |        |        |        |        |        |        | 1,596,643 |
|                                 | Renew Road and Footpaths              | Every 20 Years                                                                                                   | 1        | item | 2,850,557.88  | 2,850,558               | 2             | 5,701,116      |            |        |        |        |        |        |        |        |        |           |
|                                 | Landscaping maintenance               | Yearly                                                                                                           | 1        | item | 540.25        | 540                     | 60            | 32,415         | 540        | 540    | 540    | 540    | 540    | 540    | 540    | 540    | 540    | 540       |
|                                 | Street Cleaning                       | Yearly                                                                                                           | 1        | item | 513.59        | 514                     | 60            | 30,815         | 514        | 514    | 514    | 514    | 514    | 514    | 514    | 514    | 514    | 514       |
|                                 | Gully Cleansing / Emptying            | Yearly                                                                                                           | 1        | item | 1,108.70      | 1,109                   | 60            | 66,522         | 1,109      | 1,109  | 1,109  | 1,109  | 1,109  | 1,109  | 1,109  | 1,109  | 1,109  | 1,109     |
|                                 | Street Lighting                       | Every 20 Years                                                                                                   | 231      | nr   | 768.87        | 177,608                 | 2             | 355,217        |            |        |        |        |        |        |        |        |        |           |
|                                 | Kerb Replacement                      | 10% every 20 years                                                                                               | 506      | m    | 36.27         | 18,345                  | 2             | 36,689         |            |        |        |        |        |        |        |        |        |           |
| <b>TOTAL COST - MAINTENANCE</b> |                                       |                                                                                                                  |          |      |               |                         |               |                | 11,012,704 |        |        |        |        |        |        |        |        |           |
| <b>TOTAL COST</b>               |                                       |                                                                                                                  |          |      |               |                         |               |                | 40,227,998 |        |        |        |        |        |        |        |        |           |
| <b>Subtotals</b>                |                                       |                                                                                                                  |          |      |               |                         |               |                | 27,398,073 | 33,000 | 33,000 | 33,000 | 33,000 | 33,000 | 33,000 | 33,000 | 33,000 | 1,629,643 |

|            |        |        |        |        |        |        |        |        |        |        |
|------------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| NPV @ 3.5% | 0.9662 | 0.9335 | 0.9019 | 0.8714 | 0.8420 | 0.8135 | 0.7860 | 0.7594 | 0.7337 | 0.7089 |
|------------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|

|                  |                |            |        |        |        |        |        |        |        |        |           |
|------------------|----------------|------------|--------|--------|--------|--------|--------|--------|--------|--------|-----------|
| NPV (2019) Total | £31,550,010.78 | 26,471,568 | 30,805 | 29,764 | 28,757 | 27,785 | 26,845 | 25,937 | 25,060 | 24,213 | 1,155,285 |
|------------------|----------------|------------|--------|--------|--------|--------|--------|--------|--------|--------|-----------|

[illegible]

**£31,550,010.78 Net Present Value Total Sum**

## 15 Option 3 WLC

## Option 3 Whole Life Costing

| Location Ref                    | Work element Scenario 1               | Assumptions                                                                                                  | Quantity | Unit | Rate (£)      | Cost per occurrence (£) | # Occurrences | Total Cost (£) | 1          | 2      | 3      | 4      | 5      | 6      | 7      | 8      | 9      | 10        |
|---------------------------------|---------------------------------------|--------------------------------------------------------------------------------------------------------------|----------|------|---------------|-------------------------|---------------|----------------|------------|--------|--------|--------|--------|--------|--------|--------|--------|-----------|
| <b>CAPITAL</b>                  |                                       |                                                                                                              |          |      |               |                         |               |                |            |        |        |        |        |        |        |        |        |           |
|                                 | Construct Road                        | P80 estimate                                                                                                 | 1        | item | 43,196,700.58 | 43,196,701              | 1             | 43,196,701     | 43,196,701 |        |        |        |        |        |        |        |        |           |
| <b>TOTAL COSTS - CAPITAL</b>    |                                       |                                                                                                              |          |      |               |                         |               |                | 43,196,701 |        |        |        |        |        |        |        |        |           |
| <b>OPERATIONAL</b>              |                                       |                                                                                                              |          |      |               |                         |               |                |            |        |        |        |        |        |        |        |        |           |
|                                 | Power Consumption - Lighting (Luma 3) | 543nr lights x 254w = 137,922w per hour = 137.92kW x 4,380 hours year = 604,090kW (as advised by DW Windsor) | 604,090  | kW   | 0.12          | 72,491                  | 60            | 4,349,448      | 72,491     | 72,491 | 72,491 | 72,491 | 72,491 | 72,491 | 72,491 | 72,491 | 72,491 | 72,491    |
| <b>TOTAL COST - OPERATIONAL</b> |                                       |                                                                                                              |          |      |               |                         |               |                | 4,349,448  |        |        |        |        |        |        |        |        |           |
| <b>Maintenance and Renewals</b> |                                       |                                                                                                              |          |      |               |                         |               |                |            |        |        |        |        |        |        |        |        |           |
|                                 | Resurfacing Road                      | Every 10 Years                                                                                               | 1        | item | 2,732,258.61  | 2,732,259               | 3             | 8,196,776      |            |        |        |        |        |        |        |        |        | 2,732,259 |
|                                 | Renew Road and Footpaths              | Every 20 Years                                                                                               | 1        | item | 2,890,388.53  | 2,890,389               | 2             | 5,780,777      |            |        |        |        |        |        |        |        |        |           |
|                                 | Landscaping maintenance               | Yearly                                                                                                       | 1        | item | 540.25        | 540                     | 60            | 32,415         | 540        | 540    | 540    | 540    | 540    | 540    | 540    | 540    | 540    | 540       |
|                                 | Street Cleaning                       | Yearly                                                                                                       | 1        | item | 513.59        | 514                     | 60            | 30,815         | 514        | 514    | 514    | 514    | 514    | 514    | 514    | 514    | 514    | 514       |
|                                 | Gully Cleansing / Emptying            | Yearly                                                                                                       | 1        | item | 1,108.70      | 1,109                   | 60            | 66,522         | 1,109      | 1,109  | 1,109  | 1,109  | 1,109  | 1,109  | 1,109  | 1,109  | 1,109  | 1,109     |
|                                 | Street Lighting                       | Every 20 Years                                                                                               | 543      | nr   | 768.87        | 417,495                 | 2             | 834,990        |            |        |        |        |        |        |        |        |        |           |
|                                 | Kerb Replacement                      | 10% every 20 years                                                                                           | 1139     | m    | 36.27         | 41,322                  | 2             | 82,644         |            |        |        |        |        |        |        |        |        |           |
| <b>TOTAL COST - MAINTENANCE</b> |                                       |                                                                                                              |          |      |               |                         |               |                | 15,024,939 |        |        |        |        |        |        |        |        |           |
| <b>TOTAL COST</b>               |                                       |                                                                                                              |          |      |               |                         |               |                | 62,571,088 |        |        |        |        |        |        |        |        |           |
| <b>Subtotals</b>                |                                       |                                                                                                              |          |      |               |                         |               |                | 43,271,354 | 74,653 | 74,653 | 74,653 | 74,653 | 74,653 | 74,653 | 74,653 | 74,653 | 2,806,912 |

|            |        |        |        |        |        |        |        |        |        |        |
|------------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| NPV @ 3.5% | 0.9662 | 0.9335 | 0.9019 | 0.8714 | 0.8420 | 0.8135 | 0.7860 | 0.7594 | 0.7337 | 0.7089 |
|------------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|

|                  |                |            |        |        |        |        |        |        |        |        |           |
|------------------|----------------|------------|--------|--------|--------|--------|--------|--------|--------|--------|-----------|
| NPV (2019) Total | £49,526,878.24 | 41,808,071 | 69,690 | 67,333 | 65,056 | 62,856 | 60,731 | 58,677 | 56,693 | 54,775 | 1,989,873 |
|------------------|----------------|------------|--------|--------|--------|--------|--------|--------|--------|--------|-----------|

[illegible]

[illegible]

## 16 Waterworks P&R WLC

Mott Macdonald

## Waterworks Park and Ride Whole Life Costing

| Location Ref             | Work element Scenario 1                 | Assumptions                                                                                              | Quantity | Unit | Rate (£)      | Cost per occurrence (£) | # Occurrences | Total Cost (£) | 1              | 2          | 3      | 4      | 5      | 6      | 7      | 8      | 9      | 10        | 11        | 12     |        |
|--------------------------|-----------------------------------------|----------------------------------------------------------------------------------------------------------|----------|------|---------------|-------------------------|---------------|----------------|----------------|------------|--------|--------|--------|--------|--------|--------|--------|-----------|-----------|--------|--------|
| CAPITAL                  |                                         |                                                                                                          |          |      |               |                         |               |                |                |            |        |        |        |        |        |        |        |           |           |        |        |
|                          | Construct Car Park                      | P80 estimate                                                                                             | 1        | item | 17,056,883.92 | 17,056,884              | 1             | 17,056,884     | 17,056,884     |            |        |        |        |        |        |        |        |           |           |        |        |
| TOTAL COSTS - CAPITAL    |                                         |                                                                                                          |          |      |               |                         |               |                |                |            |        |        |        |        |        |        |        |           |           |        |        |
| OPERATIONAL              |                                         |                                                                                                          |          |      |               |                         |               |                |                |            |        |        |        |        |        |        |        |           |           |        |        |
|                          | General Cleaning for the P&R building   | Daily and 2 people for 2hrs at £15/hr required plus 10% to cover consumables/disposal                    | 1,460    | hr   | 16.50         | 24,090                  | 60            | 1,445,400      | 24,090         | 24,090     | 24,090 | 24,090 | 24,090 | 24,090 | 24,090 | 24,090 | 24,090 | 24,090    | 24,090    | 24,090 |        |
|                          | Utilities cost for the P&R building     | Yearly                                                                                                   | 224.00   | m2   | 23.67         | 5,302                   | 60            | 318,125        | 5,302          | 5,302      | 5,302  | 5,302  | 5,302  | 5,302  | 5,302  | 5,302  | 5,302  | 5,302     | 5,302     | 5,302  |        |
|                          | Monitor CCTV cameras                    | Allow 1 person hour per day to monitor the cameras (overtime paid to cover additional requirement)       | 365      | hr   | 20.00         | 7,300                   | 60            | 438,000        | 7,300          | 7,300      | 7,300  | 7,300  | 7,300  | 7,300  | 7,300  | 7,300  | 7,300  | 7,300     | 7,300     | 7,300  |        |
|                          | Power Consumption - Lighting (Luma 3)   | 51nr lights x 254w = 13,208w per hour = 12.95kW x 4,380 hours year = 56,739kW (as advised by DW Windsor) | 56,739   | kW   | 0.12          | 6,809                   | 60            | 408,521        | 6,809          | 6,809      | 6,809  | 6,809  | 6,809  | 6,809  | 6,809  | 6,809  | 6,809  | 6,809     | 6,809     | 6,809  |        |
|                          | Power Consumption - Lighting (Luma 1)   | 6nr lights x 107w = 642w per hour = 0.64kW x 4,380 hours year = 2,803kW (as advised by DW Windsor)       | 2,803    | kW   | 0.12          | 336                     | 60            | 20,182         | 336            | 336        | 336    | 336    | 336    | 336    | 336    | 336    | 336    | 336       | 336       | 336    |        |
|                          | Power Consumption - CCTV Cameras        | Allow 25% of the above                                                                                   | 14,886   | kW   | 0.12          | 1,786                   | 60            | 107,176        | 1,786          | 1,786      | 1,786  | 1,786  | 1,786  | 1,786  | 1,786  | 1,786  | 1,786  | 1,786     | 1,786     | 1,786  |        |
| TOTAL COST - OPERATIONAL |                                         |                                                                                                          |          |      |               |                         |               |                |                |            |        |        |        |        |        |        |        |           |           |        |        |
| Maintenance and Renewals |                                         |                                                                                                          |          |      |               |                         |               |                |                |            |        |        |        |        |        |        |        |           |           |        |        |
|                          | Resurfacing Car Park and Access Road    | Every 10 Years                                                                                           | 1        | item | 2,718,173.55  | 2,718,174               | 3             | 8,154,521      |                |            |        |        |        |        |        |        |        | 2,718,174 |           |        |        |
|                          | Renew Car Park, Access Road and Footpat | Every 20 Years                                                                                           | 1        | item | 2,104,586.19  | 2,104,586               | 2             | 4,209,172      |                |            |        |        |        |        |        |        |        |           |           |        |        |
|                          | Landscaping maintenance                 | Yearly                                                                                                   | 1        | item | 540.25        | 540                     | 60            | 32,415         | 540            | 540        | 540    | 540    | 540    | 540    | 540    | 540    | 540    | 540       | 540       | 540    |        |
|                          | Street Cleaning                         | Yearly                                                                                                   | 1        | item | 513.59        | 514                     | 60            | 30,815         | 514            | 514        | 514    | 514    | 514    | 514    | 514    | 514    | 514    | 514       | 514       | 514    |        |
|                          | Gully Cleansing / Emptying              | Yearly                                                                                                   | 1        | item | 1,108.70      | 1,109                   | 60            | 66,522         | 1,109          | 1,109      | 1,109  | 1,109  | 1,109  | 1,109  | 1,109  | 1,109  | 1,109  | 1,109     | 1,109     | 1,109  |        |
|                          | Street Lighting                         | Every 20 Years                                                                                           | 57       | nr   | 768.87        | 43,825                  | 2             | 87,651         |                |            |        |        |        |        |        |        |        |           |           |        |        |
|                          | CCTV                                    | Every 20 Years                                                                                           | 14       | nr   | 768.87        | 10,956                  | 2             | 21,913         |                |            |        |        |        |        |        |        |        |           |           |        |        |
|                          | Fencing                                 | Every 20 Years                                                                                           | 89       | m    | 48.44         | 4,331                   | 2             | 8,661          |                |            |        |        |        |        |        |        |        |           |           |        |        |
|                          | General Maintenance- Building           | Yearly                                                                                                   | 1        | item | 6,557.56      | 6,558                   | 60            | 393,454        | 6,558          | 6,558      | 6,558  | 6,558  | 6,558  | 6,558  | 6,558  | 6,558  | 6,558  | 6,558     | 6,558     | 6,558  |        |
|                          | Cycle Parking                           | Every 20 Years                                                                                           | 1        | item | 49,321.26     | 49,321                  | 2             | 98,643         |                |            |        |        |        |        |        |        |        |           |           |        |        |
| TOTAL COST - MAINTENANCE |                                         |                                                                                                          |          |      |               |                         |               |                |                |            |        |        |        |        |        |        |        |           |           |        |        |
| TOTAL COST               |                                         |                                                                                                          |          |      |               |                         |               |                |                |            |        |        |        |        |        |        |        |           |           |        |        |
| Subtotals                |                                         |                                                                                                          |          |      |               |                         |               | 17,111,227     | 54,343         | 54,343     | 54,343 | 54,343 | 54,343 | 54,343 | 54,343 | 54,343 | 54,343 | 2,772,517 | 54,343    | 54,343 |        |
| NPV @ 3.5%               |                                         |                                                                                                          |          |      |               |                         |               |                | 0.9662         | 0.9335     | 0.9019 | 0.8714 | 0.8420 | 0.8135 | 0.7860 | 0.7594 | 0.7337 | 0.7089    | 0.6849    | 0.6618 |        |
| NPV (2019) Total         |                                         |                                                                                                          |          |      |               |                         |               |                | £22,888,889.98 | 16,532,587 | 50,730 | 49,015 | 47,357 | 45,756 | 44,208 | 42,713 | 41,269 | 39,873    | 1,965,489 | 37,222 | 35,964 |



**£32,898,053.08**

**£22,888,889.98      Net Present Value Total Sum**

## 17 Scotland Farm P&R WLC

**Mott Macdonald**

**Scotland Farm Park and Ride Whole Life Costing**

| Location Ref             | Work element Scenario 1                  | Assumptions                                                                                            | Quantity | Unit | Rate (£)      | Cost per occurrence (£) | # Occurrences | Total Cost (£) | 1          | 2      | 3      | 4      | 5      | 6      | 7      | 8      | 9      | 10        | 11     | 12     |
|--------------------------|------------------------------------------|--------------------------------------------------------------------------------------------------------|----------|------|---------------|-------------------------|---------------|----------------|------------|--------|--------|--------|--------|--------|--------|--------|--------|-----------|--------|--------|
| CAPITAL                  |                                          |                                                                                                        |          |      |               |                         |               |                |            |        |        |        |        |        |        |        |        |           |        |        |
|                          | Construct Car Park                       | P80 estimate                                                                                           | 1        | item | 22,098,007.94 | 22,098,008              | 1             | 22,098,008     | 22,098,008 |        |        |        |        |        |        |        |        |           |        |        |
| TOTAL COSTS - CAPITAL    |                                          |                                                                                                        |          |      |               |                         |               |                |            |        |        |        |        |        |        |        |        |           |        |        |
| OPERATIONAL              |                                          |                                                                                                        |          |      |               |                         |               |                |            |        |        |        |        |        |        |        |        |           |        |        |
|                          | General Cleaning for the P&R building    | Daily and 2 people for 2hrs at £15/hr required plus 10% to cover consumables/disposal                  | 1,460    | hr   | 16.50         | 24,090                  | 60            | 1,445,400      | 24,090     | 24,090 | 24,090 | 24,090 | 24,090 | 24,090 | 24,090 | 24,090 | 24,090 | 24,090    | 24,090 | 24,090 |
|                          | Utilities cost for the P&R building      | Yearly                                                                                                 | 224.00   | m2   | 23.67         | 5,302                   | 60            | 318,125        | 5,302      | 5,302  | 5,302  | 5,302  | 5,302  | 5,302  | 5,302  | 5,302  | 5,302  | 5,302     | 5,302  | 5,302  |
|                          | Monitor CCTV cameras                     | Allow 1 person hour per day to monitor the cameras (overtime paid to cover additional requirement)     | 365      | hr   | 15.00         | 5,475                   | 60            | 328,500        | 5,475      | 5,475  | 5,475  | 5,475  | 5,475  | 5,475  | 5,475  | 5,475  | 5,475  | 5,475     | 5,475  | 5,475  |
|                          | Power Consumption - Lighting (Luma 3)    | 52nr lights x 254w = 13208w per hour = 13.21kW x 4,380 hours year = 57860kW (as advised by DW Windsor) | 57,860   | kW   | 0.12          | 6,943                   | 60            | 416,592        | 6,943      | 6,943  | 6,943  | 6,943  | 6,943  | 6,943  | 6,943  | 6,943  | 6,943  | 6,943     | 6,943  | 6,943  |
|                          | Power Consumption - Lighting (Luma 1)    | 7nr lights x 107w = 749w per hour = 0.75kW x 4,380 hours year = 3285kW (as advised by DW Windsor)      | 3,285    | kW   | 0.12          | 394                     | 60            | 23,652         | 394        | 394    | 394    | 394    | 394    | 394    | 394    | 394    | 394    | 394       | 394    | 394    |
|                          | Power Consumption - CCTV Cameras         | Allow 25% of the above                                                                                 | 14,465   | kW   | 0.12          | 1,736                   | 60            | 104,148        | 1,736      | 1,736  | 1,736  | 1,736  | 1,736  | 1,736  | 1,736  | 1,736  | 1,736  | 1,736     | 1,736  | 1,736  |
| TOTAL COST - OPERATIONAL |                                          |                                                                                                        |          |      |               |                         |               |                |            |        |        |        |        |        |        |        |        |           |        |        |
| Maintenance and Renewals |                                          |                                                                                                        |          |      |               |                         |               |                |            |        |        |        |        |        |        |        |        |           |        |        |
|                          | Resurfacing Car Park and Access Road     | Every 10 Years                                                                                         | 1        | item | 3,408,402.01  | 3,408,402               | 3             | 10,225,206     |            |        |        |        |        |        |        |        |        | 3,408,402 |        |        |
|                          | Renew Car Park, Access Road and Footpath | Every 20 Years                                                                                         | 1        | item | 2,215,464.81  | 2,215,465               | 2             | 4,430,930      |            |        |        |        |        |        |        |        |        |           |        |        |
|                          | Landscaping maintenance                  | Yearly                                                                                                 | 1        | item | 540.25        | 540                     | 60            | 32,415         | 540        | 540    | 540    | 540    | 540    | 540    | 540    | 540    | 540    | 540       | 540    | 540    |
|                          | Street Cleaning                          | Yearly                                                                                                 | 1        | item | 513.59        | 514                     | 60            | 30,815         | 514        | 514    | 514    | 514    | 514    | 514    | 514    | 514    | 514    | 514       | 514    | 514    |
|                          | Gully Cleansing / Emptying               | Yearly                                                                                                 | 1        | item | 1,108.70      | 1,109                   | 60            | 66,522         | 1,109      | 1,109  | 1,109  | 1,109  | 1,109  | 1,109  | 1,109  | 1,109  | 1,109  | 1,109     | 1,109  | 1,109  |
|                          | Street Lighting                          | Every 20 Years                                                                                         | 59       | nr   | 768.87        | 45,363                  | 2             | 90,726         |            |        |        |        |        |        |        |        |        |           |        |        |
|                          | CCTV                                     | Every 20 Years                                                                                         | 15       | nr   | 768.87        | 11,341                  | 2             | 22,682         |            |        |        |        |        |        |        |        |        |           |        |        |
|                          | Fencing                                  | Every 20 Years                                                                                         | 99       | m    | 48.44         | 4,771                   | 2             | 9,543          |            |        |        |        |        |        |        |        |        |           |        |        |
|                          | General Maintenance- Building            | Yearly                                                                                                 | 1        | item | 6,557.56      | 6,558                   | 60            | 393,454        | 6,558      | 6,558  | 6,558  | 6,558  | 6,558  | 6,558  | 6,558  | 6,558  | 6,558  | 6,558     | 6,558  | 6,558  |
|                          | Cycle Parking                            | Every 20 Years                                                                                         | 1        | item | 42,331.01     | 42,331                  | 2             | 84,662         |            |        |        |        |        |        |        |        |        |           |        |        |
| TOTAL COST - MAINTENANCE |                                          |                                                                                                        |          |      |               |                         |               |                |            |        |        |        |        |        |        |        |        |           |        |        |
| TOTAL COST               |                                          |                                                                                                        |          |      |               |                         |               |                |            |        |        |        |        |        |        |        |        |           |        |        |
| Subtotals                |                                          |                                                                                                        |          |      |               |                         |               | 22,150,668     | 52,660     | 52,660 | 52,660 | 52,660 | 52,660 | 52,660 | 52,660 | 52,660 | 52,660 | 3,461,062 | 52,660 | 52,660 |
| NPV @ 3.5%               |                                          |                                                                                                        |          |      |               |                         |               |                | 0.9662     | 0.9335 | 0.9019 | 0.8714 | 0.8420 | 0.8135 | 0.7860 | 0.7594 | 0.7337 | 0.7089    | 0.6849 | 0.6618 |
| NPV (2019) Total         |                                          |                                                                                                        |          |      |               |                         |               | £28,656,608.36 | 21,401,612 | 49,159 | 47,497 | 45,890 | 44,339 | 42,839 | 41,391 | 39,991 | 38,639 | 2,453,612 | 36,070 | 34,850 |

[illegible]

|                |                             |
|----------------|-----------------------------|
| £40,121,379.15 |                             |
| £28,656,608.36 | Net Present Value Total Sum |

