



CLIMBER PLANTING							
Tree/Shrub species	Form/habit	Root condition	Minimum no. of Breaks	Age/Condition or Number of Times Transplanted	minimum size of container	Overall Height (cm)	Planting Block m 340
Hedera helix	Ivy	Transplant - seed raised	Container	3	Dev. Shoots	1	40-60
Total Plant No.s (@ 2m centres)							Total 170

WOODLAND SCRUB PLANTING							
Tree/Shrub species	Form/habit	Root condition	Minimum no. of Breaks	Age/Condition or Number of Times Transplanted	minimum size of container	Overall Height (cm)	Planting Block m ²
Acer campestre	Field Maple	Transplant - seed raised	Bagged/Bareroot	3	1+1 or 1/1	60-80	5%
Corylus avellana	Hazel	Branched	Bagged/Bareroot	3	1+2 or 1/2	60-80	10%
Crataegus monogyna	Hawthorn	Transplant - seed raised	Bagged/Bareroot	3	1+1 or 1/1	60-80	10%
Ilex aquifolium	Holly	Leaders and Laterals	Container	3	1+1 or 1/1	60-80	2.5%
Malus sylvestris	Crab apple	Transplant - seed raised	Bagged/Bareroot	3	1+1 or 1/1	60-80	2.5%
Prunus avium	Wild Cherry	Transplant - seed raised	Bagged/Bareroot	3	1+1 or 1/1	60-80	5%
Prunus spinosa	Blackthorn	Transplant - seed raised	Bagged/Bareroot	3	1+1 or 1/1	60-80	2.5%
Quercus robur	Pedunculated oak	Transplant - seed raised	Bagged/Bareroot	3	1+1 or 1/1	60-80	35%
Rosa canina	Dog rose	Transplant - seed raised	Bagged/Bareroot	3	1+1 or 1/1	60-80	2.5%
Sorbus aria	Whitebeam	Transplant - seed raised	Bagged/Bareroot	3	1+1 or 1/1	60-80	15%
Viburnum opulus	Guedler rose	Branched	Bagged/Bareroot	3	1+2 or 1/2	60-80	10%
Total							100%
Total Plant No.s (@ 2m centres)							WP1 8383 WP3 4525

SCRUB PLANTING							
Tree/Shrub species	Form/habit	Root condition	Minimum no. of Breaks	Age/Condition or Number of Times Transplanted	Minimum size of container	Overall Height (cm)	Percentage Mix (%)
Corylus avellana	Hazel	Branched	Bagged/Bareroot	3	1+2 or 1/2	60-80	30%
Crataegus monogyna	Hawthorn	Transplant - seed raised	Bagged/Bareroot	3	1+1 or 1/1	60-80	20%
Ilex aquifolium	Holly	Leaders and Laterals	Container	3	1+1 or 1/1	60-80	10%
Prunus spinosa	Blackthorn	Transplant - seed raised	Bagged/Bareroot	3	1+1 or 1/1	60-80	25%
Rosa canina	Dog rose	Transplant - seed raised	Bagged/Bareroot	3	1+1 or 1/1	60-80	5%
Viburnum opulus	Guedler rose	Branched	Bagged/Bareroot	3	1+2 or 1/2	60-80	10%
Total							100
Total Plant No.s @ 1m Centres							SC1 6437 SC2 1666 SC3 4693 SC4 3970 SC5 572

HEDGE PLANTING							
Tree/Shrub species	Form/habit	Root condition	Minimum no. of Breaks	Age/Condition or Number of Times Transplanted	minimum size of container	Overall Height (cm)	Planting Block m
Corylus avellana	Hazel	Branched	Bagged/Bareroot	3	1+2 or 1/2	60-80	10%
Crataegus monogyna	Hawthorn	Transplant - seed raised	Bagged/Bareroot	3	1+1 or 1/1	60-80	30%
Ilex aquifolium	Holly	Leaders and Laterals	Container	3	1+1 or 1/1	60-80	10%
Prunus spinosa	Blackthorn	Transplant - seed raised	Bagged/Bareroot	3	1+1 or 1/1	60-80	40%
Rosa canina	Dog rose	Transplant - seed raised	Bagged/Bareroot	3	1+1 or 1/1	60-80	10%
Total							100%
Total Plant No.s (@ 5 per 1m)							H1 576 H2 773 H3 54 H4A 214 H4B 235 H5 390 H6 547 H7 572 H8 361 H9 171 Total 1945

FEATHERED TREES IN HEDGEROWS							
Tree/Shrub species	Form/habit	Root condition	Minimum no. of Breaks	Age/Condition or Number of Times Transplanted	Overall Height (cm)	Planting Block m	H1 H2 H3 H4A H4B H5 H6 H7 H8 H9 Total
Acer campestre	Field Maple	Feather	Bagged	5	2X	175-200	33%
Carpinus betulus	Hornbeam	Feather	Bagged	3	2X	175-200	33%
Ilex aquifolium	Holly	Feather	Bagged	5	2X	175-200	34%
Total							100%
Total Plant No.s (@ 10 per 1m)							58 77 5 21 24 39 55 38 36 17 370

Legend:

- SLOPE
- DIVERTED / EXISTING PUBLIC RIGHT OF WAY
- INITIAL BRIDLEWAY
- PERMISSIVE FOOTPATH
- EXISTING WATERCOURSE
- RETAINED BOREHOLES
- PROPOSED WATERCOURSE OPEN CHANNEL
- PROPOSED RIVER NAST DIVERSION (PERFORATED PIPE)
- PROPOSED RIVER NAST DIVERSION (SOLID PIPE)
- NAST CULVERT AND SURFACE WATER MONITORING POINT
- EXISTING PONDS
- PROPOSED GREAT CRESTED NEWT PONDS
- GAS PIPELINE ROUTE TAKEN FROM NATIONAL GRID DRAWING EA_TE_26_2S_16351
- PROPOSED ACOUSTIC FENCING
- PROPOSED STOCK PROOF FENCING
- MINERAL EXTRACTION AREA
- PROPOSED ACCESS ROAD
- PROPOSED HAUL ROAD
- PROPOSED INTERPRETATION BOARD
- PROPOSED SIGNAGE
- PROPOSED CROSSING POINT
- EXISTING VEGETATION
- PROPOSED ADVANCED PLANTING
- PROPOSED ADVANCED HEDGEROW PLANTING
- PROPOSED BUND
- PROPOSED AREA OF DISTURBANCE FROM SITE PREPARATION WORKS
- PROPOSED PERIMETER SCREENING/STORAGE BUNDS
- PROPOSED PERIMETER SEALS
- TOPSOIL STORAGE MOUND
- SUBSOIL STORAGE MOUND
- BUND WITH ACOUSTIC FENCE ON TOP
- LIMIT OF LOWER MINERAL EXTRACTION (100m OFFSET)

S	REVISIONS FOLLOWING CHANGES TO PUBLIC ACCESS	02/26	HD	MJ	MJ
R	PREVIOUSLY SUBMITTED	10/22	EW	MJ	MJ
Rev	Amendments	Date	By	Chk	Auth

www.slrconsulting.com

Drawing Purpose: **PLANNING**

Client: **ROBERT BRETT & SONS LTD**

Project: **HATFIELD AERODROME**

Drawing Title: **PHASE G**

Scale: **1:2500**

Authorised: **@ A1**

SLR Project No.: **403.065431.00001**

Designed: MJ	Drawn: HD	Checked: MJ	Authorised: MJ
Date: 02/26	Date: 02/26	Date: 02/26	Date: 02/26

Drawing Number: **HQ 3/14**

Rev: **S**

© Crown copyright and database rights [2026] Ordnance Survey Licence number 0100031673

© This drawing and its content are the copyright of SLR Consulting Ltd and may not be reproduced or amended except by prior written permission. SLR Consulting Ltd accepts no liability for any amendments made by other persons.