

Appendix 6 - Times when Bridges are being modified and no trains running

I have concentrated on the Oldham Road bridge reconstruction

Bridge no	Bridge name	page no	Comment from Statement of case
MVL3/27B and 28	Oldham Road Footbridge and Overbridge	125	This would be removed circa six to eight weeks from the full road closure
MVL3/27B and 28	Oldham Road Footbridge and Overbridge	129	Utilisation of a heavy-duty rail-mounted crane during a 27-hour possession to lift the weathering steel I-beams and precast deck units for the new footbridge into position.
MVL3/27B and 28	Oldham Road Footbridge and Overbridge	129	During a designated 5-day rail blockade , the existing stone masonry arch is demolished and replaced with new precast concrete deck elements
MVL3/27B and 28	Oldham Road Footbridge and Overbridge		However at the public consultation a Network Rail Emma rep said the line would be closed for 16 to 20 weeks but I could not find this mention in the Statement of Case (NR 30).
MVL3/	Moorgate bespoke footbridge	206	The piling rig would need to be delivered remotely via the track and due to the limited space adjacent to the railway all works would need to be completed during the closure of the railway.

Moorgate - There are enough closure times mentioned above when the piling rig can have a choice on the times for drilling the many bore holes